MathGL

for version 2.1.2

A.A. Balakin ()

This manual is for MathGL (version 2.1.2), a collection of classes and routines for scientific plotting. Please report any errors in this manual to mathgl.abalakin@gmail.org.

Table of Contents

1 Overview

MathGL is ...

- a library for making high-quality scientific graphics under Linux and Windows;
- a library for the fast data plotting and handling of large data arrays;
- a library for working in window and console modes and for easy embedding into other programs;
- a library with large and growing set of graphics.

1.1 What is MathGL?

A code for making high-quality scientific graphics under Linux and Windows. A code for the fast handling and plotting of large data arrays. A code for working in window and console regimes and for easy including into another program. A code with large and renewal set of graphics. Exactly such a code I tried to put in MathGL library.

At this version (2.1.2) MathGL has more than 50 general types of graphics for 1d, 2d and 3d data arrays. It can export graphics to bitmap and vector (EPS or SVG) files. It has OpenGL interface and can be used from console programs. It has functions for data handling and script MGL language for simplification of data plotting. It also has several types of transparency and smoothed lighting, vector fonts and TeX-like symbol parsing, arbitrary curvilinear coordinate system and many other useful things (see pictures section at homepage). Finally it is platform-independent and free (under GPL v.2.0 or later license).

1.2 MathGL features

MathGL can plot a wide range of graphics. It includes:

- one-dimensional (Plot, Area, Bars, Step, Stem, Torus, Chart, Error, Tube, Mark, see Section 4.10 [1D plotting], page 167);
- two-dimensional plots (Mesh, Surf, Dens, Cont, ContF, Boxs, Axial, Fall, Belt, Tile, see Section 4.11 [2D plotting], page 177);
- three-dimensional plots (Surf3, Dens3, Cont3, ContF3, Cloud-like, see Section 4.12 [3D plotting], page 183);
- dual data plots: vector fields Vect, flow threads Flow, mapping chart Map, surfaces and isosurfaces, transparent or colored (i.e. with transparency or color varied) by other data SurfA, SurfC, Surf3A, Surf3C (see Section 4.13 [Dual plotting], page 187);
- and so on. For details see see Chapter 4 [MathGL core], page 135.

In fact, I created the functions for drawing of all the types of scientific plots that I know. The list of plots is growing; if you need some special type of a plot then please email me e-mail and it will appear in the new version.

I tried to make plots as nice looking as possible: e.g., a surface can be transparent and highlighted by several (up to 10) light sources. Most of the drawing functions have 2 variants: simple one for the fast plotting of data, complex one for specifying of the exact position of the plot (including parametric representation). Resulting image can be saved in bitmap PNG, JPEG, GIF, TGA, BMP format, or in vector EPS, SVG or TeX format, or in 3D formats OBJ, OFF, STL, or in PRC format which can be converted into U3D.

All texts are drawn by vector fonts, which allows for high scalability and portability. Texts may contain commands for: some of the TeX-like symbols, changing index (upper or lower indexes) and the style of font inside the text string (see Section 3.5 [Font styles], page 130). Texts of ticks are rotated with axis rotation. It is possible to create a legend of plot and put text in an arbitrary position on the plot. Arbitrary text encoding (by the help of function `setlocale()`) and UTF-16 encoding are supported.

Special class mglData is used for data encapsulation (see Chapter 6 [Data processing], page 214). In addition to a safe creation and deletion of data arrays it includes functions for data processing (smoothing, differentiating, integrating, interpolating and so on) and reading of data files with automatic size determination. Class mglData can handle arrays with up to three dimensions (arrays which depend on up to 3 independent indexes $a_{\{ijk\}}$). Using an array with higher number of dimensions is not meaningful, because I do not know how it can be plotted. Data filling and modification may be done manually or by textual formulas.

There is fast evaluation of a textual mathematical expression (see Section 3.6 [Textual formulas], page 131). It is based on string precompilation to tree-like code at the creation of class instance. At evaluation stage code performs only fast tree-walk and returns the value of the expression. In addition to changing data values, textual formulas are also used for drawing in *arbitrary* curvilinear coordinates. A set of such curvilinear coordinates is limited only by user's imagination rather than a fixed list like: polar, parabolic, spherical, and so on.

1.3 Installation

MathGL can be installed in 4 different ways.

1. Compile from sources. The cmake build system is useded in the library. To run it, one should execute commands: `cmake .` twice, after it `make` and `make install` with root/sudo rights. Sometimes after installation you may need to update the library list – just execute `ldconfig` with root/sudo rights.

   There are several additional options which are switched off by default. They are: `enable-fltk, enable-glut, enable-qt` for ebabling FLTK, GLUT and/or Qt windows; `enable-jpeg, enable-gif, enable-hdf5` and so on for enabling corresponding file formats; `enable-all` for enabling all additional features. For using `double` as base internal data type use option `enable-double`. For enabling language interfaces use `enable-python, enable-octave` or `enable-all-swig` for all languages. You can use WYSIWYG tool (`cmake-gui`) to view all of them, or type `cmake -D enable-all=on -D enable-all-widgets=on -D enable-all-swig=on .` in command line for enabling all features.

2. Use a precompiled binary. There are binaries for MinGW (platform Win32). For a precompiled variant one needs only to unpack the archive to the location of the compiler (i.e. mathgl/lib in mingw/lib, mathgl/include in mingw/include and so on) or in arbitrary other folder and setup paths in compiler. By default, precompiled versions include the support of GSL (www.gsl.org) and PNG. So, one needs to have these libraries installed on system (it can be found, for example, at `http://gnuwin32.sourceforge.net/packages.html`).

3. Install precompiled versions from standard packages (RPM, deb, DevPak and so on).

Note, you can download the latest sources (which can be not stable) from sourceforge.net SVN by command

```
svn checkout http://svn.code.sf.net/p/mathgl/code/mathgl-2x mathgl-code
```

1.4 Quick guide

There are 3 steps to prepare the plot in MathGL: (1) prepare data to be plotted, (2) setup plot, (3) plot data. Let me show this on the example of surface plotting.

First we need the data. MathGL use its own class `mglData` to handle data arrays (see Chapter 6 [Data processing], page 214). This class give ability to handle data arrays by more or less format independent way. So, create it

```
int main()
{
    mglData dat(30,40);      // data to for plotting
    for(long i=0;i<30;i++)   for(long j=0;j<40;j++)
        dat.a[i+30*j] = 1/(1+(i-15)*(i-15)/225.+(j-20)*(j-20)/400.);
```

Here I create matrix 30*40 and initialize it by formula. Note, that I use `long` type for indexes i, j because data arrays can be really large and `long` type will automatically provide proper indexing.

Next step is setup of the plot. The only setup I need is axis rotation and lighting.

```
    mglGraph gr;             // class for plot drawing
    gr.Rotate(50,60);        // rotate axis
    gr.Light(true);          // enable lighting
```

Everything is ready. And surface can be plotted.

```
    gr.Surf(dat);            // plot surface
```

Basically plot is done. But I decide to add yellow ('y' color, see Section 3.2 [Color styles], page 127) contour lines on the surface. To do it I can just add:

```
    gr.Cont(dat,"y");        // plot yellow contour lines
```

This demonstrate one of base MathGL concept (see, Chapter 3 [General concepts], page 126) – "new drawing never clears things drawn already". So, you can just consequently call different plotting functions to obtain "combined" plot. For example, if one need to draw axis then he can just call one more plotting function

```
    gr.Axis();                       // draw axis
```

Now picture is ready and we can save it in a file.

```
    gr.WriteFrame("sample.png");    // save it
}
```

To compile your program, you need to specify the linker option `-lmgl`.

This is enough for a compilation of console program or with external (non-MathGL) window library. If you want to use FLTK or Qt windows provided by MathGL then you need to add the option `-lmgl-wnd`.

Fortran users also should add C++ library by the option `-lstdc++`. If library was built with `enable-double=ON` (this default for v.2.1 and later) then all real numbers must be real*8. You can make it automatic if use option `-fdefault-real-8`.

1.5 Changes from v.1.*

There are a lot of changes for v.2. Here I denote only main of them.

- mglGraph class is single plotter class instead of mglGraphZB, mglGraphPS and so on.
- Text style and text color positions are swapped. I.e. text style 'r:C' give red centered text, but not roman dark cyan text as for v.1.*.
- ColumnPlot() indexing is reverted.
- Move most of arguments of plotting functions into the string parameter and/or options.
- "Bright" colors (like {b8}) can be used in color schemes and line styles.
- Intensively use pthread internally for parallelization of drawing and data processing.
- Add tick labels rotation and skipping. Add ticks in time/date format.
- New kinds of plots (Tape(), Label(), Cones(), ContV()). Extend existing plots. New primitives (Circle(), Ellipse(), Rhomb(), ...). New plot positioning (MultiPlot(), Grid-Plot())
- Improve MGL scripts. Add 'ask' command and allow string concatenation from different lines.
- Export to LaTeX and to 3D formats (OBJ, OFF, STL).
- Add pipes support in utilities (`mglconv, mglview`).

1.6 Utilities for parsing MGL

MathGL library provides several tools for parsing MGL scripts. There is tools saving it to bitmap or vectorial images (`mglconv`). Tool `mglview` show MGL script and allow to rotate and setup the image. Another feature of `mglview` is loading *.mgld files (see `ExportMGLD()`) for quick viewing 3d pictures.

   Both tools have similar set of arguments. They can be name of script file or options. You can use '`-`' as script name for using standard input (i.e. pipes). Options are:

- **-1** *str* set *str* as argument $1 for script;
- ... ...
- **-9** *str* set *str* as argument $9 for script;
- **-A** *val* add *val* into the list of animation parameters;
- **-C** *v1:v2[:dv]* add values from *v1* ot *v2* with step *dv* (default is 1) into the list of animation parameters;
- **-L** *loc* set locale to *loc*;
- **-o** *name* set output file name;
- **-h** print help message.

   Additionally you can create animated GIF file or a set of JPEG files with names '`frameNNNN.jpg`' (here 'NNNN' is frame index). Values of the parameter `$0` for making animation can be specified inside the script by comment `##a val` for each value `val` (one comment for one value) or by option(s) '`-A val`'. Also you can specify a cycle for animation by comment `##c v1 v2 dv` or by option `-C v1:v2:dv`. In the case of found/specified animation parameters, tool will execute script several times – once for each value of `$0`.

MathGL also provide another simple tool `mgl.cgi` which parse MGL script from CGI request and send back produced PNG file. Usually this program should be placed in `/usr/lib/cgi-bin/`. But you need to put this program by yourself due to possible security issues and difference of Apache server settings.

1.7 Thanks

- My special thanks to my wife for the patience during the writing of this library and for the help in documentation writing and spelling.
- I'm thankful to my coauthors D. Kulagin and M. Vidassov for help in developing MathGL.
- I'm thankful to D. Eftaxiopoulos, V. Lipatov and S.M. Plis for making binary packages for Linux.
- I'm thankful to S. Skobelev, C. Mikhailenko, M. Veysman, A. Prokhorov, A. Korotkevich, V. Onuchin, S.M. Plis, R. Kiselev, A. Ivanov, N. Troickiy and V. Lipatov for fruitful comments.
- I'm thankful to sponsors M. Veysman (IHED RAS) and A. Prokhorov ($DATADVANCE).

Javascript interface was developed with support of $DATADVANCE company.

2 MathGL examples

This chapter contain information about basic and advanced MathGL, hints and samples for all types of graphics. I recommend you read first 2 sections one after another and at least look on Section 2.9 [Hints], page 99 section. Also I recommend you to look at Chapter 3 [General concepts], page 126 and Section 2.10 [FAQ], page 122.

Note, that MathGL v.2.* have only 2 end-user interfaces: one for C/Fortran and similar languages which don't support classes, another one for C++/Python/Octave and similar languages which support classes. So, most of samples placed in this chapter can be run as is (after minor changes due to different syntaxes for different languages). For example, the C++ code

```
#include <mgl2/mgl.h>
int main()
{
  mglGraph gr;
  gr.FPlot("sin(pi*x)");
  gr.WriteFrame("test.png");
}
```

in Python will be as

```
from mathgl import *
gr = mglGraph();
gr.FPlot("sin(pi*x)");
gr.WriteFrame("test.png");
```

in Octave will be as (you need first install MathGL package by command `octave:1> pkg install /usr/share/mathgl/octave/mathgl.tar.gz` from `sudo octave`)

```
gr = mglGraph();
gr.FPlot("sin(pi*x)");
gr.WriteFrame("test.png");
```

in C will be as

```
#include <mgl2/mgl_cf.h>
int main()
{
  HMGL gr = mgl_create_graph(600,400);
  mgl_fplot(gr,"sin(pi*x)","","");
  mgl_write_frame(gr,"test.png","");
  mgl_delete_graph(gr);
}
```

in Fortran will be as

```
integer gr, mgl_create_graph
gr = mgl_create_graph(600,400);
call mgl_fplot(gr,'sin(pi*x)','','');
call mgl_write_frame(gr,'test.png','');
call mgl_delete_graph(gr);
```

and so on.

2.1 Basic usage

MathGL library can be used by several manners. Each has positive and negative sides:

- *Using of MathGL library features for creating graphical window (requires FLTK, Qt or GLUT libraries).*

  Positive side is the possibility to view the plot at once and to modify it (rotate, zoom or switch on transparency or lighting) by hand or by mouse. Negative sides are: the need of X-terminal and limitation consisting in working with the only one set of data at a time.

- *Direct writing to file in bitmap or vector format without creation of graphical window.*

  Positive aspects are: batch processing of similar data set (for example, a set of resulting data files for different calculation parameters), running from the console program (including the cluster calculation), fast and automated drawing, saving pictures for further analysis (or demonstration). Negative sides are: the usage of the external program for picture viewing. Also, the data plotting is non-visual. So, you have to imagine the picture (view angles, lighting and so on) before the plotting. I recommend to use graphical window for determining the optimal parameters of plotting on the base of some typical data set. And later use these parameters for batch processing in console program.

- *Drawing in memory with the following displaying by other graphical program.*

  In this case the programmer has more freedom in selecting the window libraries (not only FLTK, Qt or GLUT), in positioning and surroundings control and so on. I recommend to use such way for "stand alone" programs.

- *Using FLTK or Qt widgets provided by MathGL*

  Here one can use a set of standard widgets which support export to many file formats, copying to clipboard, handle mouse and so on.

MathGL drawing can be created not only by object oriented languages (like, C++ or Python), but also by pure C or Fortran-like languages. The usage of last one is mostly identical to usage of classes (except the different function names). But there are some differences. C functions must have argument HMGL (for graphics) and/or HMDT (for data arrays) which specifies the object for drawing or manipulating (changing). Fortran users may regard these variables as integer. So, firstly the user has to create this object by function mgl_create_*() and has to delete it after the using by function mgl_delete_*().

Let me consider the aforesaid in more detail.

2.1.1 Using MathGL window

The "interactive" way of drawing in MathGL consists in window creation with help of class `mglWindow` or `mglGLUT` (see Chapter 5 [Widget classes], page 205) and the following drawing in this window. There is a corresponding code:

```
#include <mgl2/window.h>
int sample(mglGraph *gr)
{
  gr->Rotate(60,40);
  gr->Box();
  return 0;
```

```
}
//-------------------------------------------------------
int main(int argc,char **argv)
{
  mglWindow gr(sample,"MathGL examples");
  return gr.Run();
}
```

Here callback function `sample` is defined. This function does all drawing. Other function `main` is entry point function for console program. For compilation, just execute the command

```
gcc test.cpp -lmgl-wnd -lmgl
```

Alternatively you can create yours own class inherited from class `mglDraw` and re-implement the function `Draw()` in it:

```
#include <mgl2/window.h>
class Foo : public mglDraw
{
public:
  int Draw(mglGraph *gr);
};
//-------------------------------------------------------
int Foo::Draw(mglGraph *gr)
{
  gr->Rotate(60,40);
  gr->Box();
  return 0;
}
//-------------------------------------------------------
int main(int argc,char **argv)
{
  Foo foo;
  mglWindow gr(&foo,"MathGL examples");
  return gr.Run();
}
```

Or use pure C-functions:

```
#include <mgl2/mgl_cf.h>
int sample(HMGL gr, void *)
{
  mgl_rotate(gr,60,40,0);
  mgl_box(gr);
}
int main(int argc,char **argv)
{
  HMGL gr;
  gr = mgl_create_graph_qt(sample,"MathGL examples",0,0);
  return mgl_qt_run();
```

```
/* generally I should call mgl_delete_graph() here,
 * but I omit it in main() function. */
}
```

The similar code can be written for `mglGLUT` window (function `sample()` is the same):

```
#include <mgl2/glut.h>
int main(int argc,char **argv)
{
  mglGLUT gr(sample,"MathGL examples");
  return 0;
}
```

The rotation, shift, zooming, switching on/off transparency and lighting can be done with help of tool-buttons (for `mglWindow`) or by hot-keys: 'a', 'd', 'w', 's' for plot rotation, 'r' and 'f' switching on/off transparency and lighting. Press 'x' for exit (or closing the window).

In this example function `sample` rotates axes (`Rotate()`, see Section 4.4 [Subplots and rotation], page 147) and draws the bounding box (`Box()`). Drawing is placed in separate function since it will be used on demand when window canvas needs to be redrawn.

2.1.2 Drawing to file

Another way of using MathGL library is the direct writing of the picture to the file. It is most usable for plot creation during long calculation or for using of small programs (like Matlab or Scilab scripts) for visualizing repetitive sets of data. But the speed of drawing is much higher in comparison with a script language.

The following code produces a bitmap PNG picture:

```
#include <mgl2/mgl.h>
int main(int ,char **)
{
  mglGraph gr;
  gr.Alpha(true);   gr.Light(true);
  sample(&gr);                 // The same drawing function.
  gr.WritePNG("test.png");  // Don't forget to save the result!
  return 0;
}
```

For compilation, you need only libmgl library not the one with widgets

```
gcc test.cpp -lmgl
```

This can be important if you create a console program in computer/cluster where X-server (and widgets) is inaccessible.

The only difference from the previous variant (using windows) is manual switching on the transparency `Alpha` and lightning `Light`, if you need it. The usage of frames (see Section 2.1.3 [Animation], page 10) is not advisable since the whole image is prepared each time. If function `sample` contains frames then only last one will be saved to the file. In principle, one does not need to separate drawing functions in case of direct file writing in consequence of the single calling of this function for each picture. However, one may use the same drawing procedure to create a plot with changeable parameters, to export in different

file types, to emphasize the drawing code and so on. So, in future I will put the drawing in the separate function.

The code for export into other formats (for example, into vector EPS file) looks the same:

```
#include <mgl2/mgl.h>
int main(int ,char **)
{
  mglGraph gr;
  gr.Light(true);
  sample(&gr);                 // The same drawing function.
  gr.WriteEPS("test.eps");  // Don't forget to save the result!
  return 0;
}
```

The difference from the previous one is using other function `WriteEPS()` for EPS format instead of function `WritePNG()`. Also, there is no switching on of the plot transparency `Alpha` since EPS format does not support it.

2.1.3 Animation

Widget classes (`mglWindow`, `mglGLUT`) support a delayed drawing, when all plotting functions are called once at the beginning of writing to memory lists. Further program displays the saved lists faster. Resulting redrawing will be faster but it requires sufficient memory. Several lists (frames) can be displayed one after another (by pressing ',', '.') or run as cinema. To switch these feature on one needs to modify function `sample`:

```
int sample(mglGraph *gr)
{
  gr->NewFrame();              // the first frame
  gr->Rotate(60,40);
  gr->Box();
  gr->EndFrame();              // end of the first frame
  gr->NewFrame();              // the second frame
  gr->Box();
  gr->Axis("xy");
  gr->EndFrame();              // end of the second frame
  return gr->GetNumFrame();   // returns the frame number
}
```

First, the function creates a frame by calling `NewFrame()` for rotated axes and draws the bounding box. The function `EndFrame()` **must be** called after the frame drawing! The second frame contains the bounding box and axes `Axis("xy")` in the initial (unrotated) coordinates. Function `sample` returns the number of created frames `GetNumFrame()`.

Note, that such kind of animation is rather slow and not well suitable for visualization of running calculations. For the last case one can use `Update()` function. The most simple case for doing this is to use `mglDraw` class and reimplement its `Calc()` method.

```
#include <mgl2/window.h>
class Foo : public mglDraw
{
```

```
    mglPoint pnt;  // some result of calculation
public:
    mglWindow *Gr;  // graphics to be updated
    int Draw(mglGraph *gr);
    void Calc();
} foo;
//----------------------------------------------------
void Foo::Calc()
{
    for(int i=0;i<30;i++)   // do calculation
    {
        sleep(2);                 // which can be very long
        pnt = mglPoint(2*mgl_rnd()-1,2*mgl_rnd()-1);
        Gr->Update();          // update window
    }
}
//----------------------------------------------------
int Foo::Draw(mglGraph *gr)
{
    gr->Line(mglPoint(),pnt,"Ar2");
    gr->Box();
    return 0;
}
//----------------------------------------------------
int main(int argc,char **argv)
{
    mglWindow gr(&foo,"MathGL examples");
    foo.Gr = &gr;    foo.Run();
    return gr.Run();
}
```

Previous sample can be run in C++ only since it use C++ class mglDraw. However similar idea can be used even in Fortran or SWIG-based (Python/Octave/...) if one use FLTK window. Such limitation come from the Qt requirement to be run in the primary thread only. The sample code will be:

```
int main(int argc,char **argv)
{
    mglWindow gr("test");    // create window
    gr.RunThr();                  // run event loop in separate thread
    for(int i=0;i<10;i++)   // do calculation
    {
        sleep(1);                 // which can be very long
        pnt = mglPoint(2*mgl_rnd()-1,2*mgl_rnd()-1);
        gr.Clf();                 // make new drawing
        gr.Line(mglPoint(),pnt,"Ar2");
        char str[10] = "i=0"; str[2] = '0'+i;
        gr.Puts(mglPoint(),"");
```

```
    gr.Update();            // update window when you need it
  }
  return 0;   // finish calculations and close the window
}
```

Pictures with **animation can be saved in file(s)** as well. You can: export in animated GIF, or save each frame in separate file (usually JPEG) and convert these files into the movie (for example, by help of ImageMagic). Let me show both methods.

The simplest methods is making animated GIF. There are 3 steps: (1) open GIF file by `StartGIF()` function; (2) create the frames by calling `NewFrame()` before and `EndFrame()` after plotting; (3) close GIF by `CloseGIF()` function. So the simplest code for "running" sinusoid will look like this:

```
#include <mgl2/mgl.h>
int main(int ,char **)
{
  mglGraph gr;
  mglData dat(100);
  char str[32];
  gr.StartGIF("sample.gif");
  for(int i=0;i<40;i++)
  {
    gr.NewFrame();     // start frame
    gr.Box();          // some plotting
    for(int j=0;j<dat.nx;j++)
      dat.a[j]=sin(M_PI*j/dat.nx+M_PI*0.05*i);
    gr.Plot(dat,"b");
    gr.EndFrame();     // end frame
  }
  gr.CloseGIF();
  return 0;
}
```

The second way is saving each frame in separate file (usually JPEG) and later make the movie from them. MathGL have special function for saving frames – it is `WriteFrame()`. This function save each frame with automatic name 'frame0001.jpg, frame0002.jpg' and so on. Here prefix 'frame' is defined by *PlotId* variable of `mglGraph` class. So the similar code will look like this:

```
#include <mgl2/mgl.h>
int main(int ,char **)
{
  mglGraph gr;
  mglData dat(100);
  char str[32];
  for(int i=0;i<40;i++)
  {
    gr.NewFrame();     // start frame
    gr.Box();          // some plotting
    for(int j=0;j<dat.nx;j++)
```

```
      dat.a[j]=sin(M_PI*j/dat.nx+M_PI*0.05*i);
    gr.Plot(dat,"b");
    gr.EndFrame();      // end frame
    gr.WriteFrame();    // save frame
  }
  return 0;
}
```

Created files can be converted to movie by help of a lot of programs. For example, you can use ImageMagic (command 'convert frame*.jpg movie.mpg'), MPEG library, GIMP and so on.

Finally, you can use `mglconv` tool for doing the same with MGL scripts (see Section 1.6 [Utilities], page 4).

2.1.4 Drawing in memory

The last way of MathGL using is the drawing in memory. Class `mglGraph` allows one to create a bitmap picture in memory. Further this picture can be displayed in window by some window libraries (like wxWidgets, FLTK, Windows GDI and so on). For example, the code for drawing in wxWidget library looks like:

```
void MyForm::OnPaint(wxPaintEvent& event)
{
  int w,h,x,y;
  GetClientSize(&w,&h);   // size of the picture
  mglGraph gr(w,h);

  gr.Alpha(true);         // draws something using MathGL
  gr.Light(true);
  sample(&gr,NULL);

  wxImage img(w,h,gr.GetRGB(),true);
  ToolBar->GetSize(&x,&y);    // gets a height of the toolbar if any
  wxPaintDC dc(this);         // and draws it
  dc.DrawBitmap(wxBitmap(img),0,y);
}
```

The drawing in other libraries is most the same.

For example, FLTK code will look like

```
void Fl_MyWidget::draw()
{
  mglGraph gr(w(),h());
  gr.Alpha(true);         // draws something using MathGL
  gr.Light(true);
  sample(&gr,NULL);
  fl_draw_image(gr.GetRGB(), x(), y(), gr.GetWidth(), gr.GetHeight(), 3);
}
```

Qt code will look like

```
void MyWidget::paintEvent(QPaintEvent *)
```

```
{
  mglGraph gr(w(),h());

  gr.Alpha(true);           // draws something using MathGL
  gr.Light(true);           gr.Light(0,mglPoint(1,0,-1));
  sample(&gr,NULL);

  // Qt don't support RGB format as is. So, let convert it to BGRN.
  long w=gr.GetWidth(), h=gr.GetHeight();
  unsigned char *buf = new uchar[4*w*h];
  gr.GetBGRN(buf, 4*w*h)
  QPixmap pic = QPixmap::fromImage(QImage(*buf, w, h, QImage::Format_RGB32));

  QPainter paint;
  paint.begin(this);  paint.drawPixmap(0,0,pic);  paint.end();
  delete []buf;
}
```

2.1.5 Using QMathGL

MathGL have several interface widgets for different widget libraries. There are QMathGL
for Qt, Fl_MathGL for FLTK. These classes provide control which display MathGL graphics.
Unfortunately there is no uniform interface for widget classes because all libraries have
slightly different set of functions, features and so on. However the usage of MathGL widgets
is rather simple. Let me show it on the example of QMathGL.

First of all you have to define the drawing function or inherit a class from `mglDraw` class.
After it just create a window and setup QMathGL instance as any other Qt widget:

```
#include <QApplication>
#include <QMainWindow>
#include <QScrollArea>
#include <mgl2/qmathgl.h>
int main(int argc,char **argv)
{
  QApplication a(argc,argv);
  QMainWindow *Wnd = new QMainWindow;
  Wnd->resize(810,610);  // for fill up the QMGL, menu and toolbars
  Wnd->setWindowTitle("QMathGL sample");
  // here I allow to scroll QMathGL -- the case
  // then user want to prepare huge picture
  QScrollArea *scroll = new QScrollArea(Wnd);

  // Create and setup QMathGL
  QMathGL *QMGL = new QMathGL(Wnd);
//QMGL->setPopup(popup); // if you want to setup popup menu for QMGL
  QMGL->setDraw(sample);
  // or use QMGL->setDraw(foo); for instance of class Foo:public mglDraw
  QMGL->update();
```

```
  // continue other setup (menu, toolbar and so on)
  scroll->setWidget(QMGL);
  Wnd->setCentralWidget(scroll);
  Wnd->show();
  return a.exec();
}
```

2.1.6 MathGL and PyQt

Generally SWIG based classes (including the Python one) are the same as C++ classes. However, there are few tips for using MathGL with PyQt. Below I place a very simple python code which demonstrate how MathGL can be used with PyQt. This code is mostly written by Prof. Dr. Heino Falcke. You can just copy it to a file `mgl-pyqt-test.py` and execute it from python shell by command `execfile("mgl-pyqt-test.py")`

```python
from PyQt4 import QtGui,QtCore
from mathgl import *
import sys
app = QtGui.QApplication(sys.argv)
qpointf=QtCore.QPointF()

class hfQtPlot(QtGui.QWidget):
    def __init__(self, parent=None):
        QtGui.QWidget.__init__(self, parent)
        self.img=(QtGui.QImage())
    def setgraph(self,gr):
        self.buffer='\t'
        self.buffer=self.buffer.expandtabs(4*gr.GetWidth()*gr.GetHeight())
        gr.GetBGRN(self.buffer,len(self.buffer))
        self.img=QtGui.QImage(self.buffer, gr.GetWidth(),gr.GetHeight(),QtGui.QImage.Format_
        self.update()
    def paintEvent(self, event):
        paint = QtGui.QPainter()
        paint.begin(self)
        paint.drawImage(qpointf,self.img)
        paint.end()

BackgroundColor=[1.0,1.0,1.0]
size=100
gr=mglGraph()
y=mglData(size)
#y.Modify("((0.7*cos(2*pi*(x+.2)*500)+0.3)*(rnd*0.5+0.5)+362.135+10000.)")
y.Modify("(cos(2*pi*x*10)+1.1)*1000.*rnd-501")
x=mglData(size)
x.Modify("x^2");

def plotpanel(gr,x,y,n):
```

```
    gr.SubPlot(2,2,n)
    gr.SetXRange(x)
    gr.SetYRange(y)
    gr.AdjustTicks()
    gr.Axis()
    gr.Box()
    gr.Label("x","x-Axis",1)
    gr.Label("y","y-Axis",1)
    gr.ClearLegend()
    gr.AddLegend("Legend: "+str(n),"k")
    gr.Legend()
    gr.Plot(x,y)


gr.Clf(BackgroundColor[0],BackgroundColor[1],BackgroundColor[2])
gr.SetPlotFactor(1.5)
plotpanel(gr,x,y,0)
y.Modify("(cos(2*pi*x*10)+1.1)*1000.*rnd-501")
plotpanel(gr,x,y,1)
y.Modify("(cos(2*pi*x*10)+1.1)*1000.*rnd-501")
plotpanel(gr,x,y,2)
y.Modify("(cos(2*pi*x*10)+1.1)*1000.*rnd-501")
plotpanel(gr,x,y,3)

gr.WritePNG("test.png","Test Plot")

qw = hfQtPlot()
qw.show()
qw.setgraph(gr)
qw.raise_()
```

2.1.7 MathGL and MPI

For using MathGL in MPI program you just need to: (1) plot its own part of data for each
running node; (2) collect resulting graphical information in a single program (for example,
at node with rank=0); (3) save it. The sample code below demonstrate this for very simple
sample of surface drawing.

   First you need to initialize MPI

```
#include <stdio.h>
#include <mgl2/mgl.h>
#include <mpi.h>

int main(int argc, char *argv[])
{
  // initialize MPI
  int rank=0, numproc=1;
  MPI_Init(&argc, &argv);
```

```
MPI_Comm_size(MPI_COMM_WORLD,&numproc);
MPI_Comm_rank(MPI_COMM_WORLD,&rank);
if(rank==0) printf("Use %d processes.\n", numproc);
```

Next step is data creation. For simplicity, I create data arrays with the same sizes for all nodes. At this, you have to create `mglGraph` object too.

```
// initialize data similarly for all nodes
mglData a(128,256);
mglGraph gr;
```

Now, data should be filled by numbers. In real case, it should be some kind of calculations. But I just fill it by formula.

```
// do the same plot for its own range
char buf[64];
sprintf(buf,"xrange %g %g",2.*rank/numproc-1,2.*(rank+1)/numproc-1);
gr.Fill(a,"sin(2*pi*x)",buf);
```

It is time to plot the data. Don't forget to set proper axis range(s) by using parametric form or by using options (as in the sample).

```
// plot data in each node
gr.Clf();    // clear image before making the image
gr.Rotate(40,60);
gr.Surf(a,"",buf);
```

Finally, let send graphical information to node with rank=0.

```
// collect information
if(rank!=0) gr.MPI_Send(0);
else for(int i=1;i<numproc;i++)  gr.MPI_Recv(i);
```

Now, node with rank=0 have whole image. It is time to save the image to a file. Also, you can add a kind of annotations here – I draw axis and bounding box in the sample.

```
if(rank==0)
{
  gr.Box();   gr.Axis();   // some post processing
  gr.WritePNG("test.png"); // save result
}
```

In my case the program is done, and I finalize MPI. In real program, you can repeat the loop of data calculation and data plotting as many times as you need.

```
MPI_Finalize();
return 0;
}
```

You can type 'mpic++ test.cpp -lmgl && mpirun -np 8 ./a.out' for compilation and running the sample program on 8 nodes. Note, that you have to set enable-mpi=ON at MathGL configure to use this feature.

2.2 Advanced usage

Now I show several non-obvious features of MathGL: several subplots in a single picture, curvilinear coordinates, text printing and so on. Generally you may miss this section at first reading.

2.2.1 Subplots

Let me demonstrate possibilities of plot positioning and rotation. MathGL has a set of functions: [subplot], page 147, [inplot], page 148, [title], page 148, [aspect], page 149 and [rotate], page 149 and so on (see Section 4.4 [Subplots and rotation], page 147). The order of their calling is strictly determined. First, one changes the position of plot in image area (functions [subplot], page 147, [inplot], page 148 and [multiplot], page 147). Secondly, you can add the title of plot by [title], page 148 function. After that one may rotate the plot (function [rotate], page 149). Finally, one may change aspects of axes (function [aspect], page 149). The following code illustrates the aforesaid it:

```
int sample(mglGraph *gr)
{
  gr->SubPlot(2,2,0); gr->Box();
  gr->Puts(mglPoint(-1,1.1),"Just box",":L");
  gr->InPlot(0.2,0.5,0.7,1,false);  gr->Box();
  gr->Puts(mglPoint(0,1.2),"InPlot example");
  gr->SubPlot(2,2,1); gr->Title("Rotate only");
  gr->Rotate(50,60);  gr->Box();
  gr->SubPlot(2,2,2); gr->Title("Rotate and Aspect");
  gr->Rotate(50,60);  gr->Aspect(1,1,2);  gr->Box();
  gr->SubPlot(2,2,3); gr->Title("Aspect in other direction");
  gr->Rotate(50,60);  gr->Aspect(1,2,2);  gr->Box();
  return 0;
}
```

Here I used function `Puts` for printing the text in arbitrary position of picture (see Section 4.7 [Text printing], page 161). Text coordinates and size are connected with axes. However, text coordinates may be everywhere, including the outside the bounding box. I'll show its features later in Section 2.2.7 [Text features], page 28.

More complicated sample show how to use most of positioning functions:

```
int sample(mglGraph *gr)
{
  gr->SubPlot(3,2,0); gr->Title("StickPlot");
  gr->StickPlot(3, 0, 20, 30);  gr->Box("r"); gr->Puts(mglPoint(0),"0","r");
  gr->StickPlot(3, 1, 20, 30);  gr->Box("g"); gr->Puts(mglPoint(0),"1","g");
  gr->StickPlot(3, 2, 20, 30);  gr->Box("b"); gr->Puts(mglPoint(0),"2","b");
  gr->SubPlot(3,2,3,"");  gr->Title("ColumnPlot");
  gr->ColumnPlot(3, 0); gr->Box("r"); gr->Puts(mglPoint(0),"0","r");
  gr->ColumnPlot(3, 1); gr->Box("g"); gr->Puts(mglPoint(0),"1","g");
  gr->ColumnPlot(3, 2); gr->Box("b"); gr->Puts(mglPoint(0),"2","b");
  gr->SubPlot(3,2,4,"");  gr->Title("GridPlot");
  gr->GridPlot(2, 2, 0);  gr->Box("r"); gr->Puts(mglPoint(0),"0","r");
  gr->GridPlot(2, 2, 1);  gr->Box("g"); gr->Puts(mglPoint(0),"1","g");
  gr->GridPlot(2, 2, 2);  gr->Box("b"); gr->Puts(mglPoint(0),"2","b");
  gr->GridPlot(2, 2, 3);  gr->Box("m"); gr->Puts(mglPoint(0),"3","m");
  gr->SubPlot(3,2,5,"");  gr->Title("InPlot");  gr->Box();
  gr->InPlot(0.4, 1, 0.6, 1, true); gr->Box("r");
  gr->MultiPlot(3,2,1, 2, 1,"");  gr->Title("MultiPlot"); gr->Box();
  return 0;
}
```


2.2.2 Axis and ticks

MathGL library can draw not only the bounding box but also the axes, grids, labels and so on. The ranges of axes and their origin (the point of intersection) are determined by functions SetRange(), SetRanges(), SetOrigin() (see Section 4.3.1 [Ranges (bounding box)],

). Ticks on axis are specified by function `SetTicks`, `SetTicksVal`, `SetTicksTime` (see Section 4.3.3 [Ticks], page 144). But usually

Function [axis], page 163 draws axes. Its textual string shows in which directions the axis or axes will be drawn (by default `"xyz"`, function draws axes in all directions). Function [grid], page 164 draws grid perpendicularly to specified directions. Example of axes and grid drawing is:

```
int sample(mglGraph *gr)
{
  gr->SubPlot(2,2,0); gr->Title("Axis origin, Grid"); gr->SetOrigin(0,0);
  gr->Axis(); gr->Grid(); gr->FPlot("x^3");

  gr->SubPlot(2,2,1); gr->Title("2 axis");
  gr->SetRanges(-1,1,-1,1); gr->SetOrigin(-1,-1,-1);  // first axis
  gr->Axis(); gr->Label('y',"axis 1",0);  gr->FPlot("sin(pi*x)");
  gr->SetRanges(0,1,0,1);   gr->SetOrigin(1,1,1);   // second axis
  gr->Axis(); gr->Label('y',"axis 2",0);  gr->FPlot("cos(pi*x)");

  gr->SubPlot(2,2,3); gr->Title("More axis");
  gr->SetOrigin(NAN,NAN); gr->SetRange('x',-1,1);
  gr->Axis(); gr->Label('x',"x",0); gr->Label('y',"y_1",0);
  gr->FPlot("x^2","k");
  gr->SetRanges(-1,1,-1,1); gr->SetOrigin(-1.3,-1); // second axis
  gr->Axis("y","r");   gr->Label('y',"#r{y_2}",0.2);
  gr->FPlot("x^3","r");

  gr->SubPlot(2,2,2); gr->Title("4 segments, inverted axis");
  gr->SetOrigin(0,0);
  gr->InPlot(0.5,1,0.5,1);  gr->SetRanges(0,10,0,2);  gr->Axis();
  gr->FPlot("sqrt(x/2)");    gr->Label('x',"W",1); gr->Label('y',"U",1);
  gr->InPlot(0,0.5,0.5,1);  gr->SetRanges(1,0,0,2); gr->Axis("x");
  gr->FPlot("sqrt(x)+x^3"); gr->Label('x',"\\tau",-1);
  gr->InPlot(0.5,1,0,0.5);  gr->SetRanges(0,10,4,0);  gr->Axis("y");
  gr->FPlot("x/4"); gr->Label('y',"L",-1);
  gr->InPlot(0,0.5,0,0.5);  gr->SetRanges(1,0,4,0); gr->FPlot("4*x^2");
  return 0;
}
```

Note, that MathGL can draw not only single axis (which is default). But also several axis on the plot (see right plots). The idea is that the change of settings does not influence on the already drawn graphics. So, for 2-axes I setup the first axis and draw everything concerning it. Then I setup the second axis and draw things for the second axis. Generally, the similar idea allows one to draw rather complicated plot of 4 axis with different ranges (see bottom left plot).

At this inverted axis can be created by 2 methods. First one is used in this sample – just specify minimal axis value to be large than maximal one. This method work well for 2D axis, but can wrongly place labels in 3D case. Second method is more general and work in 3D case too – just use [aspect], page 149 function with negative arguments. For example,

following code will produce exactly the same result for 2D case, but 2nd variant will look better in 3D.

```
// variant 1
gr->SetRanges(0,10,4,0);  gr->Axis();

// variant 2
gr->SetRanges(0,10,0,4);  gr->Aspect(1,-1);   gr->Axis();
```


Another MathGL feature is fine ticks tunning. By default (if it is not changed by `SetTicks` function), MathGL try to adjust ticks positioning, so that they looks most human readable. At this, MathGL try to extract common factor for too large or too small axis ranges, as well as for too narrow ranges. Last one is non-common notation and can be disabled by `SetTuneTicks` function.

Also, one can specify its own ticks with arbitrary labels by help of `SetTicksVal` function. Or one can set ticks in time format. In last case MathGL will try to select optimal format for labels with automatic switching between years, months/days, hours/minutes/seconds or microseconds. However, you can specify its own time representation using formats described in http://www.manpagez.com/man/3/strftime/. Most common variants are '`%X`' for national representation of time, '`%x`' for national representation of date, '`%Y`' for year with century.

The sample code, demonstrated ticks feature is

```
int sample(mglGraph *gr)
{
  gr->SubPlot(3,2,0); gr->Title("Usual axis");  gr->Axis();
  gr->SubPlot(3,2,1); gr->Title("Too big/small range");
  gr->SetRanges(-1000,1000,0,0.001);  gr->Axis();
  gr->SubPlot(3,2,3); gr->Title("Too narrow range");
  gr->SetRanges(100,100.1,10,10.01);  gr->Axis();
```

```
  gr->SubPlot(3,2,4); gr->Title("Disable ticks tuning");
  gr->SetTuneTicks(0);  gr->Axis();

  gr->SubPlot(3,2,2); gr->Title("Manual ticks");  gr->SetRanges(-M_PI,M_PI, 0, 2);█
  mreal val[]={-M_PI, -M_PI/2, 0, 0.886, M_PI/2, M_PI};
  gr->SetTicksVal('x', mglData(6,val), "-\\pi\n-\\pi/2\n0\nx^*\n\\pi/2\n\\pi");█
  gr->Axis(); gr->Grid(); gr->FPlot("2*cos(x^2)^2", "r2");

  gr->SubPlot(3,2,5); gr->Title("Time ticks");  gr->SetRange('x',0,3e5);
  gr->SetTicksTime('x',0);  gr->Axis();
  return 0;
}
```


The last sample I want to show in this subsection is Log-axis. From MathGL's point of view, the log-axis is particular case of general curvilinear coordinates. So, we need first define new coordinates (see also Section 2.2.3 [Curvilinear coordinates], page 23) by help of `SetFunc` or `SetCoor` functions. At this one should wary about proper axis range. So the code looks as following:

```
int sample(mglGraph *gr)
{
  gr->SubPlot(2,2,0,"<_");  gr->Title("Semi-log axis");
  gr->SetRanges(0.01,100,-1,1); gr->SetFunc("lg(x)","");
  gr->Axis(); gr->Grid("xy","g"); gr->FPlot("sin(1/x)");
  gr->Label('x',"x",0); gr->Label('y', "y = sin 1/x",0);

  gr->SubPlot(2,2,1,"<_");  gr->Title("Log-log axis");
  gr->SetRanges(0.01,100,0.1,100);  gr->SetFunc("lg(x)","lg(y)");
  gr->Axis(); gr->FPlot("sqrt(1+x^2)"); gr->Label('x',"x",0);
```

```
  gr->Label('y', "y = \\sqrt{1+x^2}",0);

  gr->SubPlot(2,2,2,"<_");  gr->Title("Minus-log axis");
  gr->SetRanges(-100,-0.01,-100,-0.1);  gr->SetFunc("-lg(-x)","-lg(-y)");
  gr->Axis(); gr->FPlot("-sqrt(1+x^2)");
  gr->Label('x',"x",0); gr->Label('y', "y = -\\sqrt{1+x^2}",0);

  gr->SubPlot(2,2,3,"<_");  gr->Title("Log-ticks");
  gr->SetRanges(0.1,100,0,100); gr->SetFunc("sqrt(x)","");
  gr->Axis(); gr->FPlot("x");
  gr->Label('x',"x",1); gr->Label('y', "y = x",0);
  return 0;
}
```


You can see that MathGL automatically switch to log-ticks as we define log-axis formula (in difference from v.1.*). Moreover, it switch to log-ticks for any formula if axis range will be large enough (see right bottom plot). Another interesting feature is that you not necessary define usual log-axis (i.e. when coordinates are positive), but you can define "minus-log" axis when coordinate is negative (see left bottom plot).

2.2.3 Curvilinear coordinates

As I noted in previous subsection, MathGL support curvilinear coordinates. In difference from other plotting programs and libraries, MathGL uses textual formulas for connection of the old (data) and new (output) coordinates. This allows one to plot in arbitrary coordinates. The following code plots the line $y=0$, $z=0$ in Cartesian, polar, parabolic and spiral coordinates:

```
int sample(mglGraph *gr)
{
```

```
  gr->SetOrigin(-1,1,-1);

  gr->SubPlot(2,2,0); gr->Title("Cartesian"); gr->Rotate(50,60);
  gr->FPlot("2*t-1","0.5","0","r2");
  gr->Axis(); gr->Grid();

  gr->SetFunc("y*sin(pi*x)","y*cos(pi*x)",0);
  gr->SubPlot(2,2,1); gr->Title("Cylindrical"); gr->Rotate(50,60);
  gr->FPlot("2*t-1","0.5","0","r2");
  gr->Axis(); gr->Grid();

  gr->SetFunc("2*y*x","y*y - x*x",0);
  gr->SubPlot(2,2,2); gr->Title("Parabolic"); gr->Rotate(50,60);
  gr->FPlot("2*t-1","0.5","0","r2");
  gr->Axis(); gr->Grid();

  gr->SetFunc("y*sin(pi*x)","y*cos(pi*x)","x+z");
  gr->SubPlot(2,2,3); gr->Title("Spiral");  gr->Rotate(50,60);
  gr->FPlot("2*t-1","0.5","0","r2");
  gr->Axis(); gr->Grid();
  gr->SetFunc(0,0,0); // set to default Cartesian
  return 0;
}
```

2.2.4 Colorbars

MathGL handle [colorbar], page 164 as special kind of axis. So, most of functions for axis and ticks setup will work for colorbar too. Colorbars can be in log-scale, and generally as arbitrary function scale; common factor of colorbar labels can be separated; and so on.

But of course, there are differences – colorbars usually located out of bounding box. At this, colorbars can be at subplot boundaries (by default), or at bounding box (if symbol 'I' is specified). Colorbars can handle sharp colors. And they can be located at arbitrary position too. The sample code, which demonstrate colorbar features is:

```
int sample(mglGraph *gr)
{
  gr->SubPlot(2,2,0); gr->Title("Colorbar out of box"); gr->Box();
  gr->Colorbar("<");  gr->Colorbar(">");
  gr->Colorbar("_");  gr->Colorbar("^");

  gr->SubPlot(2,2,1); gr->Title("Colorbar near box");    gr->Box();
  gr->Colorbar("<I"); gr->Colorbar(">I");
  gr->Colorbar("_I"); gr->Colorbar("^I");

  gr->SubPlot(2,2,2); gr->Title("manual colors");
  mglData a,v;  mgls_prepare2d(&a,0,&v);
  gr->Box();  gr->ContD(v,a);
  gr->Colorbar(v,"<");  gr->Colorbar(v,">");
  gr->Colorbar(v,"_");  gr->Colorbar(v,"^");

  gr->SubPlot(2,2,3);   gr->Title(" ");
  gr->Puts(mglPoint(-0.5,1.55),"Color positions",":C",-2);
  gr->Colorbar("bwr>",0.25,0);  gr->Puts(mglPoint(-0.9,1.2),"Default");
  gr->Colorbar("b{w,0.3}r>",0.5,0); gr->Puts(mglPoint(-0.1,1.2),"Manual");

  gr->Puts(mglPoint(1,1.55),"log-scale",":C",-2);
  gr->SetRange('c',0.01,1e3);
  gr->Colorbar(">",0.75,0);  gr->Puts(mglPoint(0.65,1.2),"Normal scale");
  gr->SetFunc("","","","lg(c)");
  gr->Colorbar(">");    gr->Puts(mglPoint(1.35,1.2),"Log scale");
  return 0;
}
```

2.2.5 Bounding box

Box around the plot is rather useful thing because it allows one to: see the plot boundaries, and better estimate points position since box contain another set of ticks. MathGL provide special function for drawing such box – [box], page 165 function. By default, it draw black or white box with ticks (color depend on transparency type, see Section 2.9.3 [Types of transparency], page 102). However, you can change the color of box, or add drawing of rectangles at rear faces of box. Also you can disable ticks drawing, but I don't know why anybody will want it. The sample code, which demonstrate [box], page 165 features is:

```
int sample(mglGraph *gr)
{
  gr->SubPlot(2,2,0); gr->Title("Box (default)"); gr->Rotate(50,60);
  gr->Box();
  gr->SubPlot(2,2,1); gr->Title("colored");   gr->Rotate(50,60);
  gr->Box("r");
  gr->SubPlot(2,2,2); gr->Title("with faces");  gr->Rotate(50,60);
  gr->Box("@");
  gr->SubPlot(2,2,3); gr->Title("both");  gr->Rotate(50,60);
  gr->Box("@cm");
  return 0;
}
```

Box (default)   colored

with faces   both

2.2.6 Ternary axis

There are another unusual axis types which are supported by MathGL. These are ternary
and quaternary axis. Ternary axis is special axis of 3 coordinates a, b, c which satisfy
relation $a+b+c=1$. Correspondingly, quaternary axis is special axis of 4 coordinates a, b, c,
d which satisfy relation $a+b+c+d=1$.

Generally speaking, only 2 of coordinates (3 for quaternary) are independent. So,
MathGL just introduce some special transformation formulas which treat a as 'x', b as
'y' (and c as 'z' for quaternary). As result, all plotting functions (curves, surfaces, contours
and so on) work as usual, but in new axis. You should use [ternary], page 144 function for
switching to ternary/quaternary coordinates. The sample code is:

```
int sample(mglGraph *gr)
{
  gr->SetRanges(0,1,0,1,0,1);
  mglData x(50),y(50),z(50),rx(10),ry(10), a(20,30);
  a.Modify("30*x*y*(1-x-y)^2*(x+y<1)");
  x.Modify("0.25*(1+cos(2*pi*x))");
  y.Modify("0.25*(1+sin(2*pi*x))");
  rx.Modify("rnd"); ry.Modify("(1-v)*rnd",rx);
  z.Modify("x");

  gr->SubPlot(2,2,0); gr->Title("Ordinary axis 3D");
  gr->Rotate(50,60);    gr->Light(true);
  gr->Plot(x,y,z,"r2"); gr->Surf(a,"BbcyrR#");
  gr->Axis(); gr->Grid(); gr->Box();
  gr->Label('x',"B",1); gr->Label('y',"C",1); gr->Label('z',"Z",1);

  gr->SubPlot(2,2,1); gr->Title("Ternary axis (x+y+t=1)");
  gr->Ternary(1);
```

```
gr->Plot(x,y,"r2"); gr->Plot(rx,ry,"q^ ");  gr->Cont(a,"BbcyrR");
gr->Line(mglPoint(0.5,0), mglPoint(0,0.75), "g2");
gr->Axis(); gr->Grid("xyz","B;");
gr->Label('x',"B"); gr->Label('y',"C"); gr->Label('t',"A");

gr->SubPlot(2,2,2); gr->Title("Quaternary axis 3D");
gr->Rotate(50,60);     gr->Light(true);
gr->Ternary(2);
gr->Plot(x,y,z,"r2"); gr->Surf(a,"BbcyrR#");
gr->Axis(); gr->Grid(); gr->Box();
gr->Label('t',"A",1); gr->Label('x',"B",1);
gr->Label('y',"C",1); gr->Label('z',"D",1);

gr->SubPlot(2,2,3); gr->Title("Ternary axis 3D");
gr->Rotate(50,60);     gr->Light(true);
gr->Ternary(1);
gr->Plot(x,y,z,"r2"); gr->Surf(a,"BbcyrR#");
gr->Axis(); gr->Grid(); gr->Box();
gr->Label('t',"A",1); gr->Label('x',"B",1);
gr->Label('y',"C",1); gr->Label('z',"Z",1);
return 0;
}
```


2.2.7 Text features

MathGL prints text by vector font. There are functions for manual specifying of text position (like Puts) and for its automatic selection (like Label, Legend and so on). MathGL prints text always in specified position even if it lies outside the bounding box. The default

size of font is specified by functions *SetFontSize** (see). However, the actual size of output string depends on subplot size (depends on functions `SubPlot`, `InPlot`). The switching of the font style (italic, bold, wire and so on) can be done for the whole string (by function parameter) or inside the string. By default MathGL parses TeX-like commands for symbols and indexes (see).

Text can be printed as usual one (from left to right), along some direction (rotated text), or along a curve. Text can be printed on several lines, divided by new line symbol '`\n`'.

Example of MathGL font drawing is:

```
int sample(mglGraph *gr)
{
  gr->SubPlot(2,2,0,"");
  gr->Putsw(mglPoint(0,1),L"Text can be in ASCII and in Unicode");
  gr->Puts(mglPoint(0,0.6),"It can be \\wire{wire}, \\big{big} or #r{colored}");
  gr->Puts(mglPoint(0,0.2),"One can change style in string: "
  "\\b{bold}, \\i{italic, \\b{both}}");
  gr->Puts(mglPoint(0,-0.2),"Easy to \\a{overline} or "
  "\\u{underline}");
  gr->Puts(mglPoint(0,-0.6),"Easy to change indexes ^{up} _{down} @{center}");
  gr->Puts(mglPoint(0,-1),"It parse TeX: \\int \\alpha \\cdot "
  "\\sqrt3{sin(\\pi x)^2 + \\gamma_{i_k}} dx");

  gr->SubPlot(2,2,1,"");
  gr->Puts(mglPoint(0,0.5), "\\sqrt{\\frac{\\alpha^{\\gamma^2}+\\overset 1{\\big\\infty}}{\\
  gr->Puts(mglPoint(0,-0.5),"Text can be printed\non several lines");

  gr->SubPlot(2,2,2,"");
  mglData y;  mgls_prepare1d(&y);
  gr->Box();  gr->Plot(y.SubData(-1,0));
  gr->Text(y,"This is very very long string drawn along a curve",":k");
  gr->Text(y,"Another string drawn above a curve","T:r");

  gr->SubPlot(2,2,3,"");
  gr->Line(mglPoint(-1,-1),mglPoint(1,-1),"rA");
  gr->Puts(mglPoint(0,-1),mglPoint(1,-1),"Horizontal");
  gr->Line(mglPoint(-1,-1),mglPoint(1,1),"rA");
  gr->Puts(mglPoint(0,0),mglPoint(1,1),"At angle","@");
  gr->Line(mglPoint(-1,-1),mglPoint(-1,1),"rA");
  gr->Puts(mglPoint(-1,0),mglPoint(-1,1),"Vertical");
  return 0;
}
```

Text can be in ASCII and in Unicode

It can be wire, **big** or colored

One can change style in string: bold, italic, both

Easy to $\overline{\text{overline}}$ or $\underline{\text{underline}}$

Easy to change indexes ^{up} $_{down}$ center

It parse TeX: $\int \alpha \sqrt[3]{\sin(\pi x)^2 + \gamma_{i_k}}\, dx$

$$\sqrt{\frac{\alpha r^\eta + \bar{1}}{\sqrt[3]{2+b}}}$$

Text can be printed
on several lines

You can change font faces by loading font files by function [loadfont], page 139. Note, that this is long-run procedure. Font faces can be downloaded from MathGL website or from here. The sample code is:

```
int sample(mglGraph *gr)
{
  double h=1.1, d=0.25;
  gr->LoadFont("STIX");      gr->Puts(mglPoint(0,h), "default font (STIX)");
  gr->LoadFont("adventor"); gr->Puts(mglPoint(0,h-d), "adventor font");
  gr->LoadFont("bonum");     gr->Puts(mglPoint(0,h-2*d), "bonum font");
  gr->LoadFont("chorus");    gr->Puts(mglPoint(0,h-3*d), "chorus font");
  gr->LoadFont("cursor");    gr->Puts(mglPoint(0,h-4*d), "cursor font");
  gr->LoadFont("heros");     gr->Puts(mglPoint(0,h-5*d), "heros font");
  gr->LoadFont("heroscn");   gr->Puts(mglPoint(0,h-6*d), "heroscn font");
  gr->LoadFont("pagella");   gr->Puts(mglPoint(0,h-7*d), "pagella font");
  gr->LoadFont("schola");    gr->Puts(mglPoint(0,h-8*d), "schola font");
  gr->LoadFont("termes");    gr->Puts(mglPoint(0,h-9*d), "termes font");
  return 0;
}
```

default font (STIX)

adventor font

bonum font

chorus font

cursor font

heros font

heroscn font

pagella font

schola font

termes font

2.2.8 Legend sample

Legend is one of standard ways to show plot annotations. Basically you need to connect the plot style (line style, marker and color) with some text. In MathGL, you can do it by 2 methods: manually using [addlegend], page 166 function; or use 'legend' option (see Section 3.7 [Command options], page 132), which will use last plot style. In both cases, legend entries will be added into internal accumulator, which later used for legend drawing itself. [clearlegend], page 166 function allow you to remove all saved legend entries.

There are 2 features. If plot style is empty then text will be printed without indent. If you want to plot the text with indent but without plot sample then you need to use space ' ' as plot style. Such style ' ' will draw a plot sample (line with marker(s)) which is invisible line (i.e. nothing) and print the text with indent as usual one.

Function [legend], page 166 draw legend on the plot. The position of the legend can be selected automatic or manually. You can change the size and style of text labels, as well as setup the plot sample. The sample code demonstrating legend features is:

```
int sample(mglGraph *gr)
{
  gr->AddLegend("sin(\\pi {x^2})","b");
  gr->AddLegend("sin(\\pi x)","g*");
  gr->AddLegend("sin(\\pi \\sqrt{x})","rd");
  gr->AddLegend("just text"," ");
  gr->AddLegend("no indent for this","");

  gr->SubPlot(2,2,0,""); gr->Title("Legend (default)");
  gr->Box();  gr->Legend();

  gr->Legend(3,"A#");
  gr->Puts(mglPoint(0.75,0.65),"Absolute position","A");
```

```
gr->SubPlot(2,2,2,"");  gr->Title("coloring");  gr->Box();
gr->Legend(0,"r#"); gr->Legend(1,"Wb#");  gr->Legend(2,"ygr#");

gr->SubPlot(2,2,3,"");  gr->Title("manual position"); gr->Box();
gr->Legend(0.5,1);  gr->Puts(mglPoint(0.5,0.55),"at x=0.5, y=1","a");
gr->Legend(1,"#-"); gr->Puts(mglPoint(0.75,0.25),"Horizontal legend","a");
return 0;
}
```


2.2.9 Cutting sample

The last common thing which I want to show in this section is how one can cut off points from plot. There are 4 mechanism for that.

- You can set one of coordinate to NAN value. All points with NAN values will be omitted.

- You can enable cutting at edges by `SetCut` function. As result all points out of bounding box will be omitted.

- You can set cutting box by `SetCutBox` function. All points inside this box will be omitted.

- You can define cutting formula by `SetCutOff` function. All points for which the value of formula is nonzero will be omitted. Note, that this is the slowest variant.

Below I place the code which demonstrate last 3 possibilities:

```
int sample(mglGraph *gr)
{
  mglData a,c,v(1); mgls_prepare2d(&a); mgls_prepare3d(&c); v.a[0]=0.5;
  gr->SubPlot(2,2,0); gr->Title("Cut on (default)");
  gr->Rotate(50,60);  gr->Light(true);
```

```
gr->Box();  gr->Surf(a,"","zrange -1 0.5");

gr->SubPlot(2,2,1); gr->Title("Cut off");   gr->Rotate(50,60);
gr->Box();  gr->Surf(a,"","zrange -1 0.5; cut off");

gr->SubPlot(2,2,2); gr->Title("Cut in box");  gr->Rotate(50,60);
gr->SetCutBox(mglPoint(0,-1,-1), mglPoint(1,0,1.1));
gr->Alpha(true);  gr->Box();  gr->Surf3(c);
gr->SetCutBox(mglPoint(0), mglPoint(0));  // switch it off

gr->SubPlot(2,2,3); gr->Title("Cut by formula");  gr->Rotate(50,60);
gr->CutOff("(z>(x+0.5*y-1)^2-1) & (z>(x-0.5*y-1)^2-1)");
gr->Box();  gr->Surf3(c); gr->CutOff(""); // switch it off
return 0;
}
```


Cut on (default)   Cut off

Cut in box   Cut by formula

2.3 Data handling

Class `mglData` contains all functions for the data handling in MathGL (see Chapter 6 [Data processing], page 214). There are several matters why I use class `mglData` but not a single array: it does not depend on type of data (mreal or double), sizes of data arrays are kept with data, memory working is simpler and safer.

2.3.1 Array creation

There are many ways in MathGL how data arrays can be created and filled.

One can put the data in `mglData` instance by several ways. Let us do it for sinus function:

- one can create external array, fill it and put to `mglData` variable

```
double *a = new double[50];
for(int i=0;i<50;i++)    a[i] = sin(M_PI*i/49.);

mglData y;
y.Set(a,50);
```
- another way is to create `mglData` instance of the desired size and then to work directly with data in this variable
```
mglData y(50);
for(int i=0;i<50;i++)    y.a[i] = sin(M_PI*i/49.);
```
- next way is to fill the data in `mglData` instance by textual formula with the help of `Modify()` function
```
mglData y(50);
y.Modify("sin(pi*x)");
```
- or one may fill the array in some interval and modify it later
```
mglData y(50);
y.Fill(0,M_PI);
y.Modify("sin(u)");
```
- finally it can be loaded from file
```
FILE *fp=fopen("sin.dat","wt");   // create file first
for(int i=0;i<50;i++)    fprintf(fp,"%g\n",sin(M_PI*i/49.));
fclose(fp);

mglData y("sin.dat");             // load it
```
  At this you can use textual or HDF files, as well as import values from bitmap image (PNG is supported right now).
- at this one can read only part of data
```
FILE *fp=fopen("sin.dat","wt");   // create large file first
for(int i=0;i<70;i++)    fprintf(fp,"%g\n",sin(M_PI*i/49.));
fclose(fp);

mglData y;
y.Read("sin.dat",50);             // load it
```
Creation of 2d- and 3d-arrays is mostly the same. But one should keep in mind that class `mglData` uses flat data representation. For example, matrix 30*40 is presented as flat (1d-) array with length 30*40=1200 (nx=30, ny=40). The element with indexes {i,j} is a[i+nx*j]. So for 2d array we have:
```
mglData z(30,40);
for(int i=0;i<30;i++)    for(int j=0;j<40;j++)
  z.a[i+30*j] = sin(M_PI*i/29.)*sin(M_PI*j/39.);
 or by using Modify() function
mglData z(30,40);
z.Modify("sin(pi*x)*cos(pi*y)");
```
The only non-obvious thing here is using multidimensional arrays in C/C++, i.e. arrays defined like `mreal dat[40][30];`. Since, formally these elements `dat[i]` can address the

memory in arbitrary place you should use the proper function to convert such arrays to `mglData` object. For C++ this is functions like `mglData::Set(mreal **dat, int N1, int N2);`. For C this is functions like `mgl_data_set_mreal2(HMDT d, const mreal **dat, int N1, int N2);`. At this, you should keep in mind that `nx=N2` and `ny=N1` after conversion.

2.3.2 Linking array

Sometimes the data arrays are so large, that one couldn't' copy its values to another array (i.e. into mglData). In this case, he can define its own class derived from `mglDataA` (see Section 9.2 [mglDataA class], page 261) or can use `Link` function.

In last case, MathGL just save the link to an external data array, but not copy it. You should provide the existence of this data array for whole time during which MathGL can use it. Another point is that MathGL will automatically create new array if you'll try to modify data values by any of `mglData` functions. So, you should use only function with `const` modifier if you want still using link to the original data array.

Creating the link is rather simple – just the same as using `Set` function

```
double *a = new double[50];
for(int i=0;i<50;i++)   a[i] = sin(M_PI*i/49.);

mglData y;
y.Link(a,50);
```

2.3.3 Change data

MathGL has functions for data processing: differentiating, integrating, smoothing and so on (for more detail, see Chapter 6 [Data processing], page 214). Let us consider some examples. The simplest ones are integration and differentiation. The direction in which operation will be performed is specified by textual string, which may contain symbols 'x', 'y' or 'z'. For example, the call of `Diff("x")` will differentiate data along 'x' direction; the call of `Integral("xy")` perform the double integration of data along 'x' and 'y' directions; the call of `Diff2("xyz")` will apply 3d Laplace operator to data and so on. Example of this operations on 2d array a=x*y is presented in code:

```
int sample(mglGraph *gr)
{
  gr->SetRanges(0,1,0,1,0,1);
  mglData a(30,40); a.Modify("x*y");
  gr->SubPlot(2,2,0); gr->Rotate(60,40);
  gr->Surf(a);    gr->Box();
  gr->Puts(mglPoint(0.7,1,1.2),"a(x,y)");
  gr->SubPlot(2,2,1); gr->Rotate(60,40);
  a.Diff("x");    gr->Surf(a);  gr->Box();
  gr->Puts(mglPoint(0.7,1,1.2),"da/dx");
  gr->SubPlot(2,2,2); gr->Rotate(60,40);
  a.Integral("xy"); gr->Surf(a);  gr->Box();
  gr->Puts(mglPoint(0.7,1,1.2),"\\int da/dx dxdy");
  gr->SubPlot(2,2,3); gr->Rotate(60,40);
  a.Diff2("y"); gr->Surf(a);  gr->Box();
  gr->Puts(mglPoint(0.7,1,1.2),"\\int {d^2}a/dxdy dx");
```

```
    return 0;
}
```


Data smoothing (function [smooth], page 230) is more interesting and important. This function has single argument which define type of smoothing and its direction. Now 3 methods are supported: '3' – linear averaging by 3 points, '5' – linear averaging by 5 points, and default one – quadratic averaging by 5 points.

MathGL also have some amazing functions which is not so important for data processing as useful for data plotting. There are functions for finding envelope (useful for plotting rapidly oscillating data), for data sewing (useful to removing jumps on the phase), for data resizing (interpolation). Let me demonstrate it:

```
int sample(mglGraph *gr)
{
  gr->SubPlot(2,2,0,"");  gr->Title("Envelop sample");
  mglData d1(1000); gr->Fill(d1,"exp(-8*x^2)*sin(10*pi*x)");
  gr->Axis();        gr->Plot(d1, "b");
  d1.Envelop('x');   gr->Plot(d1, "r");

  gr->SubPlot(2,2,1,"");  gr->Title("Smooth sample");
  mglData y0(30),y1,y2,y3;
  gr->SetRanges(0,1,0,1);
  gr->Fill(y0, "0.4*sin(pi*x) + 0.3*cos(1.5*pi*x) - 0.4*sin(2*pi*x)+0.5*rnd");

  y1=y0;  y1.Smooth("x3");
  y2=y0;  y2.Smooth("x5");
  y3=y0;  y3.Smooth("x");

  gr->Plot(y0,"{m7}:s", "legend 'none'"); //gr->AddLegend("none","k");
```

```
gr->Plot(y1,"r", "legend ''3' style'");
gr->Plot(y2,"g", "legend ''5' style'");
gr->Plot(y3,"b", "legend 'default'");
gr->Legend();   gr->Box();

gr->SubPlot(2,2,2);   gr->Title("Sew sample");
mglData d2(100, 100); gr->Fill(d2, "mod((y^2-(1-x)^2)/2,0.1)");
gr->Rotate(50, 60);   gr->Light(true);  gr->Alpha(true);
gr->Box();            gr->Surf(d2, "b");
d2.Sew("xy", 0.1);  gr->Surf(d2, "r");

gr->SubPlot(2,2,3);   gr->Title("Resize sample (interpolation)");
mglData x0(10), v0(10), x1, v1;
gr->Fill(x0,"rnd");       gr->Fill(v0,"rnd");
x1 = x0.Resize(100);     v1 = v0.Resize(100);
gr->Plot(x0,v0,"b+ ");  gr->Plot(x1,v1,"r-");
gr->Label(x0,v0,"%n");
return 0;
}
```


Also one can create new data arrays on base of the existing one: extract slice, row or column of data ([subdata], page 225), summarize along a direction(s) ([sum], page 227), find distribution of data elements ([hist], page 227) and so on.

Another interesting feature of MathGL is interpolation and root-finding. There are several functions for linear and cubic spline interpolation (see Section 6.8 [Interpolation], page 231). Also there is a function [evaluate], page 226 which do interpolation of data array for values of each data element of index data. It look as indirect access to the data elements.

This function have inverse function [solve], page 226 which find array of indexes at which data array is equal to given value (i.e. work as root finding). But [solve], page 226 function have the issue – usually multidimensional data (2d and 3d ones) have an infinite number of indexes which give some value. This is contour lines for 2d data, or isosurface(s) for 3d data. So, [solve], page 226 function will return index only in given direction, assuming that other index(es) are the same as equidistant index(es) of original data. If data have multiple roots then second (and later) branches can be found by consecutive call(s) of [solve], page 226 function. Let me demonstrate this on the following sample.

```
int sample(mglGraph *gr)
{
  gr->SetRange('z',0,1);
  mglData x(20,30), y(20,30), z(20,30), xx,yy,zz;
  gr->Fill(x,"(x+2)/3*cos(pi*y)");
  gr->Fill(y,"(x+2)/3*sin(pi*y)");
  gr->Fill(z,"exp(-6*x^2-2*sin(pi*y)^2)");

  gr->SubPlot(2,1,0); gr->Title("Cartesian space");   gr->Rotate(30,-40);
  gr->Axis("xyzU");   gr->Box();  gr->Label('x',"x"); gr->Label('y',"y");
  gr->SetOrigin(1,1); gr->Grid("xy");
  gr->Mesh(x,y,z);

  // section along 'x' direction
  mglData u = x.Solve(0.5,'x');
  mglData v(u.nx);  v.Fill(0,1);
  xx = x.Evaluate(u,v);   yy = y.Evaluate(u,v);   zz = z.Evaluate(u,v);
  gr->Plot(xx,yy,zz,"k2o");

  // 1st section along 'y' direction
  mglData u1 = x.Solve(-0.5,'y');
  mglData v1(u1.nx);  v1.Fill(0,1);
  xx = x.Evaluate(v1,u1); yy = y.Evaluate(v1,u1); zz = z.Evaluate(v1,u1);
  gr->Plot(xx,yy,zz,"b2^");

  // 2nd section along 'y' direction
  mglData u2 = x.Solve(-0.5,'y',u1);
  xx = x.Evaluate(v1,u2); yy = y.Evaluate(v1,u2); zz = z.Evaluate(v1,u2);
  gr->Plot(xx,yy,zz,"r2v");

  gr->SubPlot(2,1,1); gr->Title("Accompanied space");
  gr->SetRanges(0,1,0,1); gr->SetOrigin(0,0);
  gr->Axis(); gr->Box();  gr->Label('x',"i"); gr->Label('y',"j");
  gr->Grid(z,"h");

  gr->Plot(u,v,"k2o");    gr->Line(mglPoint(0.4,0.5),mglPoint(0.8,0.5),"kA");
  gr->Plot(v1,u1,"b2^");  gr->Line(mglPoint(0.5,0.15),mglPoint(0.5,0.3),"bA");
  gr->Plot(v1,u2,"r2v");  gr->Line(mglPoint(0.5,0.7),mglPoint(0.5,0.85),"rA");
```

}

2.4 Data plotting

Let me now show how to plot the data. Next section will give much more examples for all plotting functions. Here I just show some basics. MathGL generally has 2 types of plotting functions. Simple variant requires a single data array for plotting, other data (coordinates) are considered uniformly distributed in axis range. Second variant requires data arrays for all coordinates. It allows one to plot rather complex multivalent curves and surfaces (in case of parametric dependencies). Usually each function have one textual argument for plot style and another textual argument for options (see Section 3.7 [Command options], page 132).

Note, that the call of drawing function adds something to picture but does not clear the previous plots (as it does in Matlab). Another difference from Matlab is that all setup (like transparency, lightning, axis borders and so on) must be specified **before** plotting functions.

Let start for plots for 1D data. Term "1D data" means that data depend on single index (parameter) like curve in parametric form {x(i),y(i),z(i)}, i=1...n. The textual argument allow you specify styles of line and marks (see Section 3.3 [Line styles], page 127). If this parameter is NULL or empty then solid line with color from palette is used (see Section 4.2.7 [Palette and colors], page 140).

Below I shall show the features of 1D plotting on base of [plot], page 167 function. Let us start from sinus plot:

```
int sample(mglGraph *gr)
{
  mglData y0(50);        y0.Modify("sin(pi*(2*x-1))");
  gr->SubPlot(2,2,0);
  gr->Plot(y0);          gr->Box();
```

Style of line is not specified in [plot], page 167 function. So MathGL uses the solid line with first color of palette (this is blue). Next subplot shows array *y1* with 2 rows:

```
gr->SubPlot(2,2,1);
mglData y1(50,2);
y1.Modify("sin(pi*2*x-pi)");
y1.Modify("cos(pi*2*x-pi)/2",1);
gr->Plot(y1);          gr->Box();
```

As previously I did not specify the style of lines. As a result, MathGL again uses solid line with next colors in palette (there are green and red). Now let us plot a circle on the same subplot. The circle is parametric curve $x = cos(\pi t), y = sin(\pi t)$. I will set the color of the circle (dark yellow, 'Y') and put marks '+' at point position:

```
mglData x(50);          x.Modify("cos(pi*2*x-pi)");
gr->Plot(x,y0,"Y+");
```

Note that solid line is used because I did not specify the type of line. The same picture can be achieved by [plot], page 167 and [subdata], page 225 functions. Let us draw ellipse by orange dash line:

```
gr->Plot(y1.SubData(-1,0),y1.SubData(-1,1),"q|");
```

Drawing in 3D space is mostly the same. Let us draw spiral with default line style. Now its color is 4-th color from palette (this is cyan):

```
gr->SubPlot(2,2,2);     gr->Rotate(60,40);
mglData z(50);          z.Modify("2*x-1");
gr->Plot(x,y0,z);       gr->Box();
```

Functions [plot], page 167 and [subdata], page 225 make 3D curve plot but for single array. Use it to put circle marks on the previous plot:

```
mglData y2(10,3);       y2.Modify("cos(pi*(2*x-1+y))");
y2.Modify("2*x-1",2);
gr->Plot(y2.SubData(-1,0),y2.SubData(-1,1),y2.SubData(-1,2),"bo ");
```

Note that line style is empty ' ' here. Usage of other 1D plotting functions looks similar:

```
gr->SubPlot(2,2,3);    gr->Rotate(60,40);
gr->Bars(x,y0,z,"r"); gr->Box();
return 0;
}
```

Surfaces [surf], page 177 and other 2D plots (see Section 4.11 [2D plotting], page 177) are drown the same simpler as 1D one. The difference is that the string parameter specifies not the line style but the color scheme of the plot (see Section 3.4 [Color scheme], page 128). Here I draw attention on 4 most interesting color schemes. There is gray scheme where color is changed from black to white (string 'kw') or from white to black (string 'wk'). Another scheme is useful for accentuation of negative (by blue color) and positive (by red color) regions on plot (string '"BbwrR"'). Last one is the popular "jet" scheme (string '"BbcyrR"').

Now I shall show the example of a surface drawing. At first let us switch lightning on

```
int sample(mglGraph *gr)
{
  gr->Light(true);      gr->Light(0,mglPoint(0,0,1));
```

and draw the surface, considering coordinates x,y to be uniformly distributed in interval *Min*Max*

```
mglData a0(50,40);
a0.Modify("0.6*sin(2*pi*x)*sin(3*pi*y)+0.4*cos(3*pi*(x*y))");
gr->SubPlot(2,2,0);   gr->Rotate(60,40);
gr->Surf(a0);         gr->Box();
```

Color scheme was not specified. So previous color scheme is used. In this case it is default color scheme ("jet") for the first plot. Next example is a sphere. The sphere is parametrically specified surface:

```
mglData x(50,40),y(50,40),z(50,40);
x.Modify("0.8*sin(2*pi*x)*sin(pi*y)");
y.Modify("0.8*cos(2*pi*x)*sin(pi*y)");
z.Modify("0.8*cos(pi*y)");
gr->SubPlot(2,2,1);   gr->Rotate(60,40);
gr->Surf(x,y,z,"BbwrR");gr->Box();
```

I set color scheme to `"BbwrR"` that corresponds to red top and blue bottom of the sphere.

Surfaces will be plotted for each of slice of the data if *nz*>1. Next example draws surfaces for data arrays with *nz*=3:

```
mglData a1(50,40,3);
a1.Modify("0.6*sin(2*pi*x)*sin(3*pi*y)+0.4*cos(3*pi*(x*y))");
a1.Modify("0.6*cos(2*pi*x)*cos(3*pi*y)+0.4*sin(3*pi*(x*y))",1);
a1.Modify("0.6*cos(2*pi*x)*cos(3*pi*y)+0.4*cos(3*pi*(x*y))",2);
gr->SubPlot(2,2,2);   gr->Rotate(60,40);
gr->Alpha(true);
gr->Surf(a1);         gr->Box();
```

Note, that it may entail a confusion. However, if one will use density plot then the picture will look better:

```
gr->SubPlot(2,2,3);   gr->Rotate(60,40);
gr->Dens(a1);         gr->Box();
return 0;
}
```

Drawing of other 2D plots is analogous. The only peculiarity is the usage of flag '`#`'. By default this flag switches on the drawing of a grid on plot ([grid], page 164 or [mesh], page 177 for plots in plain or in volume). However, for isosurfaces (including surfaces of rotation [axial], page 182) this flag switches the face drawing off and figure becomes wired. The following code gives example of flag '`#`' using (compare with normal function drawing as in its description):

```
int sample(mglGraph *gr)
{
  gr->Alpha(true);      gr->Light(true);          gr->Light(0,mglPoint(0,0,1));
  mglData a(30,20);
  a.Modify("0.6*sin(2*pi*x)*sin(3*pi*y) + 0.4*cos(3*pi*(x*y))");

  gr->SubPlot(2,2,0);   gr->Rotate(40,60);
  gr->Surf(a,"BbcyrR#");                  gr->Box();
```

```
  gr->SubPlot(2,2,1);   gr->Rotate(40,60);
  gr->Dens(a,"BbcyrR#");                      gr->Box();
  gr->SubPlot(2,2,2);   gr->Rotate(40,60);
  gr->Cont(a,"BbcyrR#");                       gr->Box();
  gr->SubPlot(2,2,3);   gr->Rotate(40,60);
  gr->Axial(a,"BbcyrR#");                      gr->Box();
  return 0;
}
```

2.5 1D samples

This section is devoted to visualization of 1D data arrays. 1D means the data which depend on single index (parameter) like curve in parametric form $\{x(i),y(i),z(i)\}$, i=1...n. Most of samples will use the same data for plotting. So, I put its initialization in separate function

```
void mgls_prepare1d(mglData *y, mglData *y1=0, mglData *y2=0, mglData *x1=0, mglData *x2=0)
{
  register long i,n=50;
  if(y) y->Create(n,3);
  if(x1)  x1->Create(n);    if(x2)  x2->Create(n);
  if(y1)  y1->Create(n);    if(y2)  y2->Create(n);
  mreal xx;
  for(i=0;i<n;i++)
  {
    xx = i/(n-1.);
    if(y)
    {
      y->a[i] = 0.7*sin(2*M_PI*xx) + 0.5*cos(3*M_PI*xx) + 0.2*sin(M_PI*xx);
      y->a[i+n] = sin(2*M_PI*xx);
      y->a[i+2*n] = cos(2*M_PI*xx);
    }
    if(y1)  y1->a[i] = 0.5+0.3*cos(2*M_PI*xx);
    if(y2)  y2->a[i] = 0.3*sin(2*M_PI*xx);
    if(x1)  x1->a[i] = xx*2-1;
    if(x2)  x2->a[i] = 0.05+0.03*cos(2*M_PI*xx);
  }
}
```

   or using C functions

```
void mgls_prepare1d(HMDT y, HMDT y1=0, HMDT y2=0, HMDT x1=0, HMDT x2=0)
{
  register long i,n=50;
  if(y)   mgl_data_create(y,n,3,1);
  if(x1)  mgl_data_create(x1,n,1,1);
  if(x2)  mgl_data_create(x2,n,1,1);
  if(y1)  mgl_data_create(y1,n,1,1);
  if(y2)  mgl_data_create(y2,n,1,1);
  mreal xx;
  for(i=0;i<n;i++)
```

```
  {
    xx = i/(n-1.);
    if(y)
    {
      mgl_data_set_value(y, 0.7*sin(2*M_PI*xx) + 0.5*cos(3*M_PI*xx) + 0.2*sin(M_PI*xx), i,0
      mgl_data_set_value(y, sin(2*M_PI*xx), i,1,0);
      mgl_data_set_value(y, cos(2*M_PI*xx), i,2,0);
    }
    if(y1)  mgl_data_set_value(y1, 0.5+0.3*cos(2*M_PI*xx), i,0,0);
    if(y2)  mgl_data_set_value(y2, 0.3*sin(2*M_PI*xx), i,0,0);
    if(x1)  mgl_data_set_value(x1, xx*2-1, i,0,0);
    if(x2)  mgl_data_set_value(x2, 0.05+0.03*cos(2*M_PI*xx), i,0,0);
  }
}
```

2.5.1 Plot sample

Function [plot], page 167 is most standard way to visualize 1D data array. By default, `Plot` use colors from palette. However, you can specify manual color/palette, and even set to use new color for each points by using '!' style. Another feature is ' ' style which draw only markers without line between points. The sample code is:

```
int sample(mglGraph *gr)
{
  mglData y;  mgls_prepare1d(&y); gr->SetOrigin(0,0,0);
  gr->SubPlot(2,2,0,"");  gr->Title("Plot plot (default)");
  gr->Box();  gr->Plot(y);

  gr->SubPlot(2,2,2,"");  gr->Title("'!' style; 'rgb' palette");
  gr->Box();  gr->Plot(y,"o!rgb");

  gr->SubPlot(2,2,3,"");  gr->Title("just markers");
  gr->Box();  gr->Plot(y," +");

  gr->SubPlot(2,2,1); gr->Title("3d variant");
  gr->Rotate(50,60);  gr->Box();
  mglData yc(30), xc(30), z(30);  z.Modify("2*x-1");
  yc.Modify("sin(pi*(2*x-1))"); xc.Modify("cos(pi*2*x-pi)");
  gr->Plot(xc,yc,z,"rs");
  return 0;
}
```

Plot plot (default)   3d variant

'!' style; 'rgb' palette   just markers

2.5.2 Radar sample

Function [radar], page 167 plot is variant of `Plot` one, which make plot in polar coordinates and draw radial rays in point directions. If you just need a plot in polar coordinates then I recommend to use Section 2.2.3 [Curvilinear coordinates], page 23 or `Plot` in parabolic form with `x=r*cos(fi); y=r*sin(fi);`. The sample code is:

```
int sample(mglGraph *gr)
{
  mglData yr(10,3); yr.Modify("0.4*sin(pi*(2*x+y))+0.1*rnd");
  gr->SubPlot(1,1,0,"");  gr->Title("Radar plot (with grid, '\\#')");
  gr->Radar(yr,"#");
  return 0;
}
```

Radar plot (with grid, '#')

2.5.3 Step sample

Function [step], page 167 plot data as stairs. It have the same options as `Plot`. The sample code is:

```
int sample(mglGraph *gr)
{
  mglData y;  mgls_prepare1d(&y); gr->SetOrigin(0,0,0);
  mglData yc(30), xc(30), z(30);  z.Modify("2*x-1");
  yc.Modify("sin(pi*(2*x-1))"); xc.Modify("cos(pi*2*x-pi)");

  gr->SubPlot(2,2,0,"");  gr->Title("Step plot (default)");
  gr->Box();  gr->Step(y);

  gr->SubPlot(2,2,1); gr->Title("3d variant");  gr->Rotate(50,60);
  gr->Box();  gr->Step(xc,yc,z,"r");

  gr->SubPlot(2,2,2,"");  gr->Title("'!' style");
  gr->Box();  gr->Step(y,"s!rgb");
  return 0;
}
```

Step plot (default)

3d variant

'!' style

2.5.4 Tens sample

Function [tens], page 168 is variant of [plot], page 167 with smooth coloring along the curves. At this, color is determined as for surfaces (see Section 3.4 [Color scheme], page 128). The sample code is:

```
int sample(mglGraph *gr)
{
  mglData y;  mgls_prepare1d(&y); gr->SetOrigin(0,0,0);
  gr->SubPlot(2,2,0,"");  gr->Title("Tens plot (default)");
  gr->Box();  gr->Tens(y.SubData(-1,0), y.SubData(-1,1));

  gr->SubPlot(2,2,2,"");  gr->Title("' ' style");
  gr->Box();  gr->Tens(y.SubData(-1,0), y.SubData(-1,1),"o ");

  gr->SubPlot(2,2,1); gr->Title("3d variant");  gr->Rotate(50,60);  gr->Box();
  mglData yc(30), xc(30), z(30);  z.Modify("2*x-1");
  yc.Modify("sin(pi*(2*x-1))"); xc.Modify("cos(pi*2*x-pi)");
  gr->Tens(xc,yc,z,z,"s");
  return 0;
}
```

Tens plot (default)   3d variant

' ' style

2.5.5 Area sample

Function [area], page 169 fill the area between curve and axis plane. It support gradient filling if 2 colors per curve is specified. The sample code is:

```
int sample(mglGraph *gr)
{
  mglData y;  mgls_prepare1d(&y); gr->SetOrigin(0,0,0);
  gr->SubPlot(2,2,0,"");  gr->Title("Area plot (default)");
  gr->Box();  gr->Area(y);

  gr->SubPlot(2,2,1,"");  gr->Title("2 colors");
  gr->Box();  gr->Area(y,"cbgGyr");

  gr->SubPlot(2,2,2,"");  gr->Title("'!' style");
  gr->Box();  gr->Area(y,"!");

  gr->SubPlot(2,2,3); gr->Title("3d variant");
  gr->Rotate(50,60);  gr->Box();
  mglData yc(30), xc(30), z(30);  z.Modify("2*x-1");
  yc.Modify("sin(pi*(2*x-1))"); xc.Modify("cos(pi*2*x-pi)");
  gr->Area(xc,yc,z,"r");
  yc.Modify("-sin(pi*(2*x-1))");  gr->Area(xc,yc,z,"b#");
  return 0;
}
```

Area plot (default)

2 colors

'!' style

3d variant

2.5.6 Region sample

Function [region], page 169 fill the area between 2 curves. It support gradient filling if 2 colors per curve is specified. Also it can fill only the region y1<y<y2 if style 'i' is used. The sample code is:

```
int sample(mglGraph *gr)
{
  mglData y;  mgls_prepare1d(&y);
  mglData y1 = y.SubData(-1,1), y2 = y.SubData(-1,2); gr->SetOrigin(0,0,0);
  gr->SubPlot(2,2,0,"");  gr->Title("Region plot (default)");
  gr->Box();  gr->Region(y1,y2);  gr->Plot(y1,"k2");  gr->Plot(y2,"k2");

  gr->SubPlot(2,2,1,"");  gr->Title("2 colors");
  gr->Box();  gr->Region(y1,y2,"yr"); gr->Plot(y1,"k2");  gr->Plot(y2,"k2");

  gr->SubPlot(2,2,2,"");  gr->Title("'!' style");
  gr->Box();  gr->Region(y1,y2,"!");  gr->Plot(y1,"k2");  gr->Plot(y2,"k2");

  gr->SubPlot(2,2,3,"");  gr->Title("'i' style");
  gr->Box();  gr->Region(y1,y2,"ir"); gr->Plot(y1,"k2");  gr->Plot(y2,"k2");
  return 0;
}
```

2.5.7 Stem sample

Function [stem], page 170 draw vertical bars. It is most attractive if markers are drawn too. The sample code is:

```
int sample(mglGraph *gr)
{
  mglData y;  mgls_prepare1d(&y); gr->SetOrigin(0,0,0);
  mglData yc(30), xc(30), z(30);  z.Modify("2*x-1");
  yc.Modify("sin(pi*(2*x-1))"); xc.Modify("cos(pi*2*x-pi)");
  gr->SubPlot(2,2,0,"");  gr->Title("Stem plot (default)");
  gr->Box();  gr->Stem(y);

  gr->SubPlot(2,2,1); gr->Title("3d variant");  gr->Rotate(50,60);
  gr->Box();  gr->Stem(xc,yc,z,"rx");

  gr->SubPlot(2,2,2,"");  gr->Title("'!' style");
  gr->Box();  gr->Stem(y,"o!rgb");
  return 0;
}
```

2.5.8 Bars sample

Function [bars], page 170 draw vertical bars. It have a lot of options: bar-above-bar ('a' style), fall like ('f' style), 2 colors for positive and negative values, wired bars ('#' style), 3D variant. The sample code is:

```
int sample(mglGraph *gr)
{
  mglData ys(10,3); ys.Modify("0.8*sin(pi*(2*x+y/2))+0.2*rnd");
  gr->SetOrigin(0,0,0);
  gr->SubPlot(3,2,0,"");  gr->Title("Bars plot (default)");
  gr->Box();  gr->Bars(ys);

  gr->SubPlot(3,2,1,"");  gr->Title("2 colors");
  gr->Box();  gr->Bars(ys,"cbgGyr");

  gr->SubPlot(3,2,4,"");  gr->Title("'\\#' style");
  gr->Box();  gr->Bars(ys,"#");

  gr->SubPlot(3,2,5); gr->Title("3d variant");
  gr->Rotate(50,60);  gr->Box();
  mglData yc(30), xc(30), z(30);  z.Modify("2*x-1");
  yc.Modify("sin(pi*(2*x-1))"); xc.Modify("cos(pi*2*x-pi)");
  gr->Bars(xc,yc,z,"r");

  gr->SetRanges(-1,1,-3,3);
  gr->SubPlot(3,2,2,"");  gr->Title("'a' style");
  gr->Box();  gr->Bars(ys,"a");

  gr->SubPlot(3,2,3,"");  gr->Title("'f' style");
```

```
  gr->Box();  gr->Bars(ys,"f");
  return 0;
}
```

Bars plot (default)   2 colors   'a' style

'f' style   '#' style   3d variant

2.5.9 Barh sample

Function [barh], page 170 is the similar to `Bars` but draw horizontal bars. The sample code is:

```
int sample(mglGraph *gr)
{
  mglData ys(10,3); ys.Modify("0.8*sin(pi*(2*x+y/2))+0.2*rnd");
  gr->SetOrigin(0,0,0);
  gr->SubPlot(2,2,0,"");  gr->Title("Barh plot (default)");
  gr->Box();  gr->Barh(ys);

  gr->SubPlot(2,2,1,"");  gr->Title("2 colors");
  gr->Box();  gr->Barh(ys,"cbgGyr");

  gr->SetRanges(-3,3,-1,1);
  gr->SubPlot(2,2,2,"");  gr->Title("'a' style");
  gr->Box();  gr->Barh(ys,"a");

  gr->SubPlot(2,2,3,"");  gr->Title("'f' style");
  gr->Box();  gr->Barh(ys,"f");
  return 0;
}
```

Barh plot (default)

2 colors

'a' style

'f' style

2.5.10 Cones sample

Function [cones], page 171 is similar to `Bars` but draw cones. The sample code is:

```
int sample(mglGraph *gr)
{
  mglData ys(10,3);    ys.Modify("0.8*sin(pi*(2*x+y/2))+0.2*rnd");
  gr->Light(true);     gr->SetOrigin(0,0,0);
  gr->SubPlot(2,2,0); gr->Title("Cones plot");
  gr->Rotate(50,60);  gr->Box();  gr->Cones(ys);

  gr->SubPlot(2,2,1); gr->Title("2 colors");
  gr->Rotate(50,60);  gr->Box();  gr->Cones(ys,"cbgGyr");

  gr->SubPlot(2,2,2); gr->Title("'#' style");
  gr->Rotate(50,60);  gr->Box();  gr->Cones(ys,"#");

  gr->SubPlot(2,2,3); gr->Title("'a' style");
  gr->SetRange('z',-2,2); // increase range since summation can exceed [-1,1]
  gr->Rotate(50,60);  gr->Box();  gr->Cones(ys,"a");
  return 0;
}
```

2.5.11 Chart sample

Function [chart], page 171 draw colored boxes with width proportional to data values. Use
' ' for empty box. Plot looks most attractive in polar coordinates – well known pie chart.
The sample code is:

```
int sample(mglGraph *gr)
{
  mglData ch(7,2);  for(int i=0;i<7*2;i++)  ch.a[i]=mgl_rnd()+0.1;
  gr->SubPlot(2,2,0); gr->Title("Chart plot (default)");
  gr->Light(true);  gr->Rotate(50,60);  gr->Box();  gr->Chart(ch);

  gr->SubPlot(2,2,1); gr->Title("'\\#' style");
  gr->Rotate(50,60);  gr->Box();  gr->Chart(ch,"#");

  gr->SubPlot(2,2,2); gr->Title("Pie chart; ' ' color");
  gr->SetFunc("(y+1)/2*cos(pi*x)","(y+1)/2*sin(pi*x)","");
  gr->Rotate(50,60);  gr->Box();  gr->Chart(ch,"bgr cmy#");

  gr->SubPlot(2,2,3); gr->Title("Ring chart; ' ' color");
  gr->SetFunc("(y+2)/3*cos(pi*x)","(y+2)/3*sin(pi*x)","");
  gr->Rotate(50,60);  gr->Box();  gr->Chart(ch,"bgr cmy#");
  return 0;
}
```

Chart plot (default)   '#' style

Pie chart; ' ' color   Ring chart; ' ' color

2.5.12 BoxPlot sample

Function [boxplot], page 172 draw box-and-whisker diagram. The sample code is:

```
int sample(mglGraph *gr)
{
  mglData a(10,7);  a.Modify("(2*rnd-1)^3/2");
  gr->SubPlot(1,1,0,"");  gr->Title("Boxplot plot");
  gr->Box();  gr->BoxPlot(a);
  return 0;
}
```

Boxplot plot

2.5.13 Candle sample

Function [candle], page 172 draw candlestick chart. This is a combination of a line-chart and a bar-chart, in that each bar represents the range of price movement over a given time interval. The sample code is:

```
int sample(mglGraph *gr)
{
  mglData y(30);  gr->Fill(y,"sin(pi*x/2)^2");
  mglData y1(30); gr->Fill(y1,"v/2",y);
  mglData y2(30); gr->Fill(y2,"(1+v)/2",y);
  gr->SubPlot(1,1,0,"");  gr->Title("Candle plot (default)");
  gr->SetRange('y',0,1);  gr->Box();  gr->Candle(y,y1,y2);
  return 0;
}
```


Candle plot (default)

2.5.14 Error sample

Function [error], page 173 draw error boxes around the points. You can draw default boxes or semi-transparent symbol (like marker, see Section 3.3 [Line styles], page 127). Also you can set individual color for each box. The sample code is:

```
int sample(mglGraph *gr)
{
  mglData y;  mgls_prepare1d(&y);
  mglData x0(10), y0(10), ex0(10), ey0(10);
  mreal x;
  for(int i=0;i<10;i++)
  {
    x = i/9.;
    x0.a[i] = 2*x-1 + 0.1*mgl_rnd()-0.05;
```

```
    y0.a[i] = 0.7*sin(2*M_PI*x)+0.5*cos(3*M_PI*x)+0.2*sin(M_PI*x)+0.2*mgl_rnd()-0.1;█
    ey0.a[i]=0.2; ex0.a[i]=0.1;
  }

  gr->SubPlot(2,2,0,"");  gr->Title("Error plot (default)");
  gr->Box();  gr->Plot(y.SubData(-1,0));  gr->Error(x0,y0,ex0,ey0,"ko");

  gr->SubPlot(2,2,1,"");  gr->Title("'!' style; no e_x");
  gr->Box();  gr->Plot(y.SubData(-1,0));  gr->Error(x0,y0,ey0,"o!rgb");

  gr->SubPlot(2,2,2,"");  gr->Title("'\\@' style");
  gr->Box();  gr->Plot(y.SubData(-1,0));  gr->Error(x0,y0,ex0,ey0,"@","alpha 0.5");█

  gr->SubPlot(2,2,3); gr->Title("3d variant");  gr->Rotate(50,60);
  for(int i=0;i<10;i++)
    gr->Error(mglPoint(2*mgl_rnd()-1,2*mgl_rnd()-1,2*mgl_rnd()-1),
              mglPoint(0.2,0.2,0.2),"bo");
  gr->Axis();
  return 0;
}
```


2.5.15 Mark sample

Function [mark], page 173 draw markers at points. It is mostly the same as Plot but marker size can be variable. The sample code is:

```
int sample(mglGraph *gr)
{
  mglData y,y1; mgls_prepare1d(&y,&y1);
```

```
  gr->SubPlot(1,1,0,"");  gr->Title("Mark plot (default)");
  gr->Box();  gr->Mark(y,y1,"s");
  return 0;
}
```

Mark plot (default)

2.5.16 TextMark sample

Function [textmark], page 174 like `Mark` but draw text instead of markers. The sample code
is:

```
int sample(mglGraph *gr)
{
  mglData y,y1; mgls_prepare1d(&y,&y1);
  gr->SubPlot(1,1,0,"");  gr->Title("TextMark plot (default)");
  gr->Box();  gr->TextMark(y,y1,"\\gamma","r");
  return 0;
}
```

TextMark plot (default)

2.5.17 Label sample

Function [label], page 174 print text at data points. The string may contain '%x', '%y', '%z' for x-, y-, z-coordinates of points, '%n' for point index. The sample code is:

```
int sample(mglGraph *gr)
{
  mglData ys(10); ys.Modify("0.8*sin(pi*2*x)+0.2*rnd");
  gr->SubPlot(1,1,0,"");  gr->Title("Label plot");
  gr->Box();  gr->Plot(ys," *");  gr->Label(ys,"y=%y");
  return 0;
}
```

Label plot

2.5.18 Table sample

Function [table], page 175 draw table with data values. The sample code is:

```
int sample(mglGraph *gr)
{
  mglData ys(10,3); ys.Modify("0.8*sin(pi*(2*x+y/2))+0.2*rnd");
  gr->SubPlot(2,2,0);  gr->Title("Table plot");
  gr->Table(ys,"y_1\ny_2\ny_3");    gr->Box();
  gr->SubPlot(2,2,1);  gr->Title("no borders, colored");
  gr->Table(ys,"y_1\ny_2\ny_3","r|");
  gr->SubPlot(2,2,2);  gr->Title("no font decrease");
  gr->Table(ys,"y_1\ny_2\ny_3","#");
  gr->SubPlot(2,2,3);  gr->Title("manual width, position");
  gr->Table(0.5, 0.95, ys,"y_1\ny_2\ny_3","#", "value 0.7");  gr->Box();
  return 0;
}
```

Table plot **no borders, colored**

y_1	0.0229	0.693	0.855	0.705	0.379	-0.114	-0.505	-0.673	-0.457	0.185
y_2	0.65	0.992	0.824	0.336	-0.177	-0.567	-0.748	-0.399	0.1	0.727
y_3	0.994	0.722	0.183	-0.254	-0.572	-0.584	-0.298	0.213	0.787	0.855

y_1	0.0229	0.693	0.855	0.705	0.379	-0.114	-0.505	-0.673	-0.457	0.185
y_2	0.65	0.992	0.824	0.336	-0.177	-0.567	-0.748	-0.399	0.1	0.727
y_3	0.994	0.722	0.183	-0.254	-0.572	-0.584	-0.298	0.213	0.787	0.855

no font decrease **manual width, position**

y_1	0.0229	0.693	0.855	0.705	0.379	-0.114	-0.505	-0.673	-0.457	0.185
y_2	0.65	0.992	0.824	0.336	-0.177	-0.567	-0.748	-0.399	0.1	0.727
y_3	0.994	0.722	0.183	-0.254	-0.572	-0.584	-0.298	0.213	0.787	0.855

y_1	0.0229	0.693	0.855	0.705	0.379	-0.114	-0.505	-0.673	-0.457	0.185
y_2	0.65	0.992	0.824	0.336	-0.177	-0.567	-0.748	-0.399	0.1	0.727
y_3	0.994	0.722	0.183	-0.254	-0.572	-0.584	-0.298	0.213	0.787	0.855

2.5.19 Tube sample

Function [tube], page 176 draw tube with variable radius. The sample code is:

```
int sample(mglGraph *gr)
{
  mglData y,y1,y2;  mgls_prepare1d(&y,&y1,&y2); y1/=20;
  gr->SubPlot(2,2,0,"");  gr->Title("Tube plot (default)");
  gr->Light(true);  gr->Box();  gr->Tube(y,0.05);

  gr->SubPlot(2,2,1,"");  gr->Title("variable radius");
  gr->Box();  gr->Tube(y,y1);

  gr->SubPlot(2,2,2,"");  gr->Title("'\\#' style");
  gr->Box();  gr->Tube(y,0.05,"#");
  mglData yc(50), xc(50), z(50);  z.Modify("2*x-1");
  yc.Modify("sin(pi*(2*x-1))"); xc.Modify("cos(pi*2*x-pi)");

  gr->SubPlot(2,2,3); gr->Title("3d variant");  gr->Rotate(50,60);
  gr->Box();  gr->Tube(xc,yc,z,y2,"r");
  return 0;
}
```

2.5.20 Tape sample

Function [tape], page 168 draw tapes which rotate around the curve as normal and binormal.
The sample code is:

```
int sample(mglGraph *gr)
{
  mglData y;  mgls_prepare1d(&y);
  mglData xc(50), yc(50), z(50);
  yc.Modify("sin(pi*(2*x-1))");
  xc.Modify("cos(pi*2*x-pi)");  z.Fill(-1,1);
  gr->SubPlot(2,2,0,"");  gr->Title("Tape plot (default)");
  gr->Box();  gr->Tape(y);  gr->Plot(y,"k");

  gr->SubPlot(2,2,1); gr->Title("3d variant, 2 colors");
  gr->Rotate(50,60);  gr->Light(true);
  gr->Box();  gr->Plot(xc,yc,z,"k");  gr->Tape(xc,yc,z,"rg");

  gr->SubPlot(2,2,2); gr->Title("3d variant, x only");  gr->Rotate(50,60);
  gr->Box();  gr->Plot(xc,yc,z,"k");
  gr->Tape(xc,yc,z,"xr"); gr->Tape(xc,yc,z,"xr#");

  gr->SubPlot(2,2,3); gr->Title("3d variant, z only");  gr->Rotate(50,60);
  gr->Box();  gr->Plot(xc,yc,z,"k");
  gr->Tape(xc,yc,z,"zg"); gr->Tape(xc,yc,z,"zg#");
  return 0;
}
```

2.5.21 Torus sample

Function [torus], page 176 draw surface of the curve rotation. The sample code is:

```
int sample(mglGraph *gr)
{
  mglData y1,y2;  mgls_prepare1d(0,&y1,&y2);
  gr->SubPlot(2,2,0); gr->Title("Torus plot (default)");
  gr->Light(true);  gr->Rotate(50,60);  gr->Box();  gr->Torus(y1,y2);
  if(mini)  return;

  gr->SubPlot(2,2,1); gr->Title("'x' style"); gr->Rotate(50,60);
  gr->Box();  gr->Torus(y1,y2,"x");

  gr->SubPlot(2,2,2); gr->Title("'z' style"); gr->Rotate(50,60);
  gr->Box();  gr->Torus(y1,y2,"z");

  gr->SubPlot(2,2,3); gr->Title("'\\#' style"); gr->Rotate(50,60);
  gr->Box();  gr->Torus(y1,y2,"#");
  return 0;
}
```

Torus plot (default)   'x' style

'z' style   '#' style

2.6 2D samples

This section is devoted to visualization of 2D data arrays. 2D means the data which depend
on 2 indexes (parameters) like matrix z(i,j)=z(x(i),y(j)), i=1...n, j=1...m or in parametric
form {x(i,j),y(i,j),z(i,j)}. Most of samples will use the same data for plotting. So, I put its
initialization in separate function

```
void mgls_prepare2d(mglData *a, mglData *b=0, mglData *v=0)
{
  register long i,j,n=50,m=40,i0;
  if(a) a->Create(n,m);    if(b) b->Create(n,m);
  if(v) { v->Create(9); v->Fill(-1,1);   }
  mreal x,y;
  for(i=0;i<n;i++)  for(j=0;j<m;j++)
  {
    x = i/(n-1.); y = j/(m-1.); i0 = i+n*j;
    if(a) a->a[i0] = 0.6*sin(2*M_PI*x)*sin(3*M_PI*y)+0.4*cos(3*M_PI*x*y);
    if(b) b->a[i0] = 0.6*cos(2*M_PI*x)*cos(3*M_PI*y)+0.4*cos(3*M_PI*x*y);
  }
}
```

 or using C functions

```
void mgls_prepare2d(HMDT a, HMDT b=0, HMDT v=0)
{
  register long i,j,n=50,m=40,i0;
  if(a) mgl_data_create(a,n,m,1);
  if(b) mgl_data_create(b,n,m,1);
  if(v) { mgl_data_create(v,9,1,1); mgl_data_fill(v,-1,1,'x');   }
  mreal x,y;
  for(i=0;i<n;i++)  for(j=0;j<m;j++)
```

```
  {
    x = i/(n-1.); y = j/(m-1.); i0 = i+n*j;
    if(a) mgl_data_set_value(a, 0.6*sin(2*M_PI*x)*sin(3*M_PI*y)+0.4*cos(3*M_PI*x*y), i,j,0)
    if(b) mgl_data_set_value(b, 0.6*cos(2*M_PI*x)*cos(3*M_PI*y)+0.4*cos(3*M_PI*x*y), i,j,0)
  }
}
```

2.6.1 Surf sample

Function [surf], page 177 is most standard way to visualize 2D data array. `Surf` use color
scheme for coloring (see Section 3.4 [Color scheme], page 128). You can use '#' style for
drawing black meshes on the surface. The sample code is:

```
int sample(mglGraph *gr)
{
  mglData a;  mgls_prepare2d(&a);
  gr->SubPlot(2,2,0); gr->Title("Surf plot (default)");
  gr->Light(true);  gr->Rotate(50,60);  gr->Box();  gr->Surf(a);

  gr->SubPlot(2,2,1); gr->Title("'\\#' style; meshnum 10");
  gr->Rotate(50,60);  gr->Box();  gr->Surf(a,"#","meshnum 10");

  gr->SubPlot(2,2,2); gr->Title("'.' style");
  gr->Rotate(50,60);  gr->Box();  gr->Surf(a,".");

  gr->SubPlot(2,2,3); gr->Title("parametric form");
  mglData x(50,40),y(50,40),z(50,40);
  gr->Fill(x,"0.8*sin(pi*x)*sin(pi*(y+1)/2)");
  gr->Fill(y,"0.8*cos(pi*x)*sin(pi*(y+1)/2)");
  gr->Fill(z,"0.8*cos(pi*(y+1)/2)");
  gr->Rotate(50,60);  gr->Box();  gr->Surf(x,y,z,"BbwrR");
  return 0;
}
```

Surf plot (default)   '#' style; meshnum 10

'.' style   parametric form

2.6.2 SurfC sample

Function [surfc], page 187 is similar to [surf], page 177 but its coloring is determined by another data. The sample code is:

```
int sample(mglGraph *gr)
{
  mglData a,b;  mgls_prepare2d(&a,&b);
  gr->Title("SurfC plot");  gr->Rotate(50,60);
  gr->Light(true);  gr->Box();  gr->SurfC(a,b);
  return 0;
}
```

SurfC plot

2.6.3 SurfA sample

Function [surfa], page 188 is similar to [surf], page 177 but its transparency is determined
by another data. The sample code is:

```
int sample(mglGraph *gr)
{
  mglData a,b;  mgls_prepare2d(&a,&b);
  gr->Title("SurfA plot");  gr->Rotate(50,60);
  gr->Alpha(true);  gr->Light(true);
  gr->Box();  gr->SurfA(a,b);
  return 0;
}
```

SurfA plot

2.6.4 Mesh sample

Function [mesh], page 177 draw wired surface. You can use [meshnum], page 138 for chang-
ing number of lines to be drawn. The sample code is:

```
int sample(mglGraph *gr)
{
  mglData a;  mgls_prepare2d(&a);
  gr->Title("Mesh plot"); gr->Rotate(50,60);
  gr->Box();  gr->Mesh(a);
  return 0;
}
```

Mesh plot

2.6.5 Fall sample

Function [fall], page 177 draw waterfall surface. You can use [meshnum], page 138 for changing number of lines to be drawn. Also you can use 'x' style for drawing lines in other direction. The sample code is:

```
int sample(mglGraph *gr)
{
  mglData a;  mgls_prepare2d(&a);
  gr->Title("Fall plot"); gr->Rotate(50,60);
  gr->Box();  gr->Fall(a);
  return 0;
}
```

Fall plot

2.6.6 Belt sample

Function [belt], page 178 draw surface by belts. You can use 'x' style for drawing lines in other direction. The sample code is:

```
int sample(mglGraph *gr)
{
  mglData a;  mgls_prepare2d(&a);
  gr->Title("Belt plot"); gr->Rotate(50,60);
  gr->Box();  gr->Belt(a);
  return 0;
}
```

Belt plot

2.6.7 Boxs sample

Function [boxs], page 178 draw surface by boxes. You can use '**#**' for drawing wire plot. The sample code is:

```
int sample(mglGraph *gr)
{
  mglData a;  mgls_prepare2d(&a);
  gr->SetOrigin(0,0,0); gr->Light(true);
  gr->SubPlot(2,2,0);  gr->Title("Boxs plot (default)");
  gr->Rotate(40,60);  gr->Box();  gr->Boxs(a);

  gr->SubPlot(2,2,1); gr->Title("'\\@' style");
  gr->Rotate(50,60);  gr->Box();  gr->Boxs(a,"@");

  gr->SubPlot(2,2,2); gr->Title("'\\#' style");
  gr->Rotate(50,60);  gr->Box();  gr->Boxs(a,"#");

  gr->SubPlot(2,2,3); gr->Title("compare with Tile");
  gr->Rotate(50,60);  gr->Box();  gr->Tile(a);
  return 0;
}
```

Boxs plot (default)   '@' style

'#' style   compare with Tile

2.6.8 Tile sample

Function [tile], page 178 draw surface by tiles. The sample code is:

```
int sample(mglGraph *gr)
{
  mglData a;  mgls_prepare2d(&a);
  gr->Title("Tile plot");
  gr->Rotate(40,60);  gr->Box();  gr->Tile(a);
  return 0;
}
```

Tile plot

2.6.9 TileS sample

Function [tiles], page 189 is similar to [tile], page 178 but tile sizes is determined by another data. This allows one to simulate transparency of the plot. The sample code is:

```
int sample(mglGraph *gr)
{
  mglData a,b;  mgls_prepare2d(&a,&b);
  gr->SubPlot(1,1,0,""); gr->Title("TileS plot");
  gr->Box();  gr->TileS(a,b);
  return 0;
}
```


TileS plot

2.6.10 Dens sample

Function [dens], page 179 draw density plot for surface. The sample code is:

```
int sample(mglGraph *gr)
{
  mglData a,a1(30,40,3);  mgls_prepare2d(&a);
  gr->Fill(a1,"0.6*sin(2*pi*x+pi*(z+1)/2)*sin(3*pi*y+pi*z) + 0.4*cos(3*pi*(x*y)+pi*(z+1)^2/
  gr->SubPlot(2,2,0,""); gr->Title("Dens plot (default)");
  gr->Box();  gr->Dens(a);

  gr->SubPlot(2,2,1); gr->Title("3d variant");
  gr->Rotate(50,60);  gr->Box();  gr->Dens(a);

  gr->SubPlot(2,2,2,"");  gr->Title("'\\#' style; meshnum 10");
  gr->Box();  gr->Dens(a,"#","meshnum 10");

  gr->SubPlot(2,2,3); gr->Title("several slices");
```

```
gr->Rotate(50,60);     gr->Box();  gr->Dens(a1);
return 0;
}
```


Dens plot (default)   3d variant

'#' style; meshnum 10   several slices

2.6.11 Cont sample

Function [cont], page 179 draw contour lines for surface. You can select automatic (default) or manual levels for contours, print contour labels, draw it on the surface (default) or at plane (as `Dens`). The sample code is:

```
int sample(mglGraph *gr)
{
  mglData a,v(5); mgls_prepare2d(&a); v.a[0]=-0.5;  v.a[1]=-0.15; v.a[2]=0; v.a[3]=0.15;  v
  gr->SubPlot(2,2,0); gr->Title("Cont plot (default)");
  gr->Rotate(50,60);  gr->Box();  gr->Cont(a);

  gr->SubPlot(2,2,1); gr->Title("manual levels");
  gr->Rotate(50,60);  gr->Box();  gr->Cont(v,a);

  gr->SubPlot(2,2,2); gr->Title("'\\_' style");
  gr->Rotate(50,60);  gr->Box();  gr->Cont(a,"_");

  gr->SubPlot(2,2,3,"");  gr->Title("'t' style");
  gr->Box();  gr->Cont(a,"t");
  return 0;
}
```

Cont plot (default)   manual levels

'_' style   't' style

2.6.12 ContF sample

Function [contf], page 180 draw filled contours. You can select automatic (default) or manual levels for contours. The sample code is:

```
int sample(mglGraph *gr)
{
  mglData a,v(5),a1(30,40,3); mgls_prepare2d(&a); v.a[0]=-0.5;
  v.a[1]=-0.15; v.a[2]=0; v.a[3]=0.15;  v.a[4]=0.5;
  gr->SubPlot(2,2,0); gr->Title("ContF plot (default)");
  gr->Rotate(50,60);  gr->Box();  gr->ContF(a);

  gr->SubPlot(2,2,1); gr->Title("manual levels");
  gr->Rotate(50,60);  gr->Box();  gr->ContF(v,a);

  gr->SubPlot(2,2,2); gr->Title("'\\_' style");
  gr->Rotate(50,60);  gr->Box();  gr->ContF(a,"_");

  gr->Fill(a1,"0.6*sin(2*pi*x+pi*(z+1)/2)*sin(3*pi*y+pi*z) + 0.4*cos(3*pi*(x*y)+pi*(z+1)^2/
  gr->SubPlot(2,2,3); gr->Title("several slices");
  gr->Rotate(50,60);  gr->Box();  gr->ContF(a1);
  return 0;
}
```

ContF plot (default)   manual levels

'_' style   several slices

2.6.13 ContD sample

Function [contd], page 180 is similar to `ContF` but with manual contour colors. The sample code is:

```
int sample(mglGraph *gr)
{
  mglData a,v(5),a1(30,40,3); mgls_prepare2d(&a); v.a[0]=-0.5;
  v.a[1]=-0.15; v.a[2]=0; v.a[3]=0.15;  v.a[4]=0.5;
  gr->SubPlot(2,2,0); gr->Title("ContD plot (default)");
  gr->Rotate(50,60);  gr->Box();  gr->ContD(a);

  gr->SubPlot(2,2,1); gr->Title("manual levels");
  gr->Rotate(50,60);  gr->Box();  gr->ContD(v,a);

  gr->SubPlot(2,2,2); gr->Title("'\\_' style");
  gr->Rotate(50,60);  gr->Box();  gr->ContD(a,"_");

  gr->Fill(a1,"0.6*sin(2*pi*x+pi*(z+1)/2)*sin(3*pi*y+pi*z) + 0.4*cos(3*pi*(x*y)+pi*(z+1)^2/
  gr->SubPlot(2,2,3); gr->Title("several slices");
  gr->Rotate(50,60);  gr->Box();  gr->ContD(a1);
  return 0;
}
```

ContD plot (default)   manual levels

'_' style   several slices

2.6.14 ContV sample

Function [contv], page 181 draw vertical cylinders (belts) at contour lines. The sample code is:

```
int sample(mglGraph *gr)
{
  mglData a,v(5); mgls_prepare2d(&a); v.a[0]=-0.5;
  v.a[1]=-0.15; v.a[2]=0; v.a[3]=0.15;  v.a[4]=0.5;
  gr->SubPlot(2,2,0); gr->Title("ContV plot (default)");
  gr->Rotate(50,60);  gr->Box();  gr->ContV(a);

  gr->SubPlot(2,2,1); gr->Title("manual levels");
  gr->Rotate(50,60);  gr->Box();  gr->ContV(v,a);

  gr->SubPlot(2,2,2); gr->Title("'\\_' style");
  gr->Rotate(50,60);  gr->Box();  gr->ContV(a,"_");

  gr->SubPlot(2,2,3); gr->Title("ContV and ContF");
  gr->Rotate(50,60);  gr->Box();  gr->Light(true);
  gr->ContV(a); gr->ContF(a); gr->Cont(a,"k");
  return 0;
}
```

ContV plot (default)   manual levels

'_' style   ContV and ContF

2.6.15 Axial sample

Function [axial], page 182 draw surfaces of rotation for contour lines. You can draw wire
surfaces ('#' style) or ones rotated in other directions ('x', 'z' styles). The sample code is:

```
int sample(mglGraph *gr)
{
  mglData a;  mgls_prepare2d(&a);
  gr->SubPlot(2,2,0); gr->Title("Axial plot (default)");
  gr->Light(true);  gr->Alpha(true);  gr->Rotate(50,60);
  gr->Box();  gr->Axial(a);

  gr->SubPlot(2,2,1); gr->Title("'x' style;'.' style"); gr->Rotate(50,60);
  gr->Box();  gr->Axial(a,"x.");

  gr->SubPlot(2,2,2); gr->Title("'z' style"); gr->Rotate(50,60);
  gr->Box();  gr->Axial(a,"z");

  gr->SubPlot(2,2,3); gr->Title("'\\#' style"); gr->Rotate(50,60);
  gr->Box();  gr->Axial(a,"#");
  return 0;
}
```

Axial plot (default)

'x' style; '.'style

'z' style

'#' style

2.6.16 Grad sample

Function [grad], page 194 draw gradient lines for matrix. The sample code is:

```
int sample(mglGraph *gr)
{
  mglData a;  mgls_prepare2d(&a);
  gr->SubPlot(1,1,0,""); gr->Title("Grad plot");
  gr->Box();  gr->Grad(a);  gr->Dens(a,"{u8}w{q8}");
  return 0;
}
```


Grad plot

2.7 3D samples

This section is devoted to visualization of 3D data arrays. 3D means the data which depend
on 3 indexes (parameters) like tensor a(i,j,k)=a(x(i),y(j),x(k)), i=1...n, j=1...m, k=1...l or
in parametric form {x(i,j,k),y(i,j,k),z(i,j,k),a(i,j,k)}. Most of samples will use the same data
for plotting. So, I put its initialization in separate function

```
void mgls_prepare3d(mglData *a, mglData *b=0)
{
  register long i,j,k,n=61,m=50,l=40,i0;
  if(a) a->Create(n,m,l);   if(b) b->Create(n,m,l);
  mreal x,y,z;
  for(i=0;i<n;i++)  for(j=0;j<m;j++)  for(k=0;k<l;k++)
  {
    x=2*i/(n-1.)-1; y=2*j/(m-1.)-1; z=2*k/(l-1.)-1; i0 = i+n*(j+m*k);
    if(a) a->a[i0] = -2*(x*x + y*y + z*z*z*z - z*z - 0.1);
    if(b) b->a[i0] = 1-2*tanh((x+y)*(x+y));
  }
}
```

or using C functions

```
void mgls_prepare3d(HMDT a, HMDT b=0)
{
  register long i,j,k,n=61,m=50,l=40,i0;
  if(a) mgl_data_create(a,n,m,l);
  if(b) mgl_data_create(b,n,m,l);
  mreal x,y,z;
  for(i=0;i<n;i++)  for(j=0;j<m;j++)  for(k=0;k<l;k++)
  {
    x=2*i/(n-1.)-1; y=2*j/(m-1.)-1; z=2*k/(l-1.)-1; i0 = i+n*(j+m*k);
    if(a) mgl_data_set_value(a, -2*(x*x + y*y + z*z*z*z - z*z - 0.1), i,j,k);
    if(b) mgl_data_set_value(b, 1-2*tanh((x+y)*(x+y)), i,j,k);
  }
}
```

2.7.1 Surf3 sample

Function [surf3], page 183 is one of most suitable (for my opinion) functions to visualize 3D
data. It draw the isosurface(s) – surface(s) of constant amplitude (3D analogue of contour
lines). You can draw wired isosurfaces if specify '#' style. The sample code is:

```
int sample(mglGraph *gr)
{
  mglData c;  mgls_prepare3d(&c);
  gr->Light(true);    gr->Alpha(true);
  gr->SubPlot(2,2,0); gr->Title("Surf3 plot (default)");
  gr->Rotate(50,60);  gr->Box();  gr->Surf3(c);

  gr->SubPlot(2,2,1); gr->Title("'\\#' style");
  gr->Rotate(50,60);  gr->Box();  gr->Surf3(c,"#");
```

```
gr->SubPlot(2,2,2); gr->Title("'.' style");
gr->Rotate(50,60);  gr->Box();  gr->Surf3(c,".");
return 0;
}
```


Surf3 plot (default)

'#' style

'.' style

2.7.2 Surf3C sample

Function [surf3c], page 187 is similar to [surf3], page 183 but its coloring is determined by another data. The sample code is:

```
int sample(mglGraph *gr)
{
  mglData c,d;  mgls_prepare3d(&c,&d);
  gr->Title("Surf3C plot"); gr->Rotate(50,60);
  gr->Light(true);  gr->Alpha(true);
  gr->Box();  gr->Surf3C(c,d);
  return 0;
}
```

Surf3C plot

2.7.3 Surf3A sample

Function [surf3a], page 188 is similar to [surf3], page 183 but its transparency is determined
by another data. The sample code is:

```
int sample(mglGraph *gr)
{
  mglData c,d;  mgls_prepare3d(&c,&d);
  gr->Title("Surf3A plot"); gr->Rotate(50,60);
  gr->Light(true);  gr->Alpha(true);
  gr->Box();  gr->Surf3A(c,d);
  return 0;
}
```

Surf3A plot

2.7.4 Cloud sample

Function [cloud], page 184 draw cloud-like object which is less transparent for higher data
values. Similar plot can be created using many (about 10-20) `Surf3A(a,a)` isosurfaces. The
sample code is:

```
int sample(mglGraph *gr)
{
  mglData c;  mgls_prepare3d(&c);
  gr->SubPlot(2,2,0); gr->Title("Cloud plot");
  gr->Rotate(50,60);  gr->Alpha(true);
  gr->Box();  gr->Cloud(c,"wyrRk");

  gr->SubPlot(2,2,1); gr->Title("'!' style");
  gr->Rotate(50,60);  gr->Box();  gr->Cloud(c,"!wyrRk");

  gr->SubPlot(2,2,2); gr->Title("'.' style");
  gr->Rotate(50,60);  gr->Box();  gr->Cloud(c,".wyrRk");

  gr->SubPlot(2,2,3); gr->Title("meshnum 10");
  gr->Rotate(50,60);  gr->Box();  gr->Cloud(c,"wyrRk","meshnum 10");
  return 0;
}
```

Cloud plot   '!' style

'.' style   meshnum 10

2.7.5 Dens3 sample

Function [dens3], page 184 draw just usual density plot but at slices of 3D data. The sample
code is:

```
int sample(mglGraph *gr)
{
  mglData c;  mgls_prepare3d(&c);
  gr->Title("Dens3 sample");  gr->Rotate(50,60);
  gr->Alpha(true);  gr->SetAlphaDef(0.7);
  gr->SetOrigin(0,0,0); gr->Axis("_xyz"); gr->Box();
  gr->Dens3(c,"x"); gr->Dens3(c); gr->Dens3(c,"z");
  return 0;
}
```

Dens3 sample

2.7.6 Cont3 sample

Function [cont3], page 184 draw just usual contour lines but at slices of 3D data. The sample code is:

```
int sample(mglGraph *gr)
{
  mglData c;  mgls_prepare3d(&c);
  gr->Title("Cont3 sample");  gr->Rotate(50,60);
  gr->Alpha(true);  gr->SetAlphaDef(0.7);
  gr->SetOrigin(0,0,0); gr->Axis("_xyz"); gr->Box();
  gr->Cont3(c,"x"); gr->Cont3(c); gr->Cont3(c,"z");
  return 0;
}
```

Cont3 sample

2.7.7 ContF3 sample

Function [contf3], page 185 draw just usual filled contours but at slices of 3D data. The sample code is:

```
int sample(mglGraph *gr)
{
  mglData c;  mgls_prepare3d(&c);
  gr->Title("ContF3 sample");  gr->Rotate(50,60);
  gr->Alpha(true);  gr->SetAlphaDef(0.7);
  gr->SetOrigin(0,0,0); gr->Axis("_xyz"); gr->Box();
  gr->ContF3(c,"x");  gr->ContF3(c);     gr->ContF3(c,"z");
  gr->Cont3(c,"kx");  gr->Cont3(c,"k"); gr->Cont3(c,"kz");
  return 0;
}
```

ContF3 sample

2.7.8 Dens projection sample

Functions [DensXYZ], page 195 draw density plot on plane perpendicular to corresponding
axis. One of possible application is drawing projections of 3D field. The sample code is:

```
int sample(mglGraph *gr)
{
  mglData c;  mgls_prepare3d(&c);
  gr->Title("Dens[XYZ] sample");  gr->Rotate(50,60);
  gr->Box();  gr->DensX(c.Sum("x"),0,-1);
  gr->DensY(c.Sum("y"),0,1);  gr->DensZ(c.Sum("z"),0,-1);
  return 0;
}
```

Dens[XYZ] sample

2.7.9 Cont projection sample

Functions [ContXYZ], page 196 draw contour lines on plane perpendicular to corresponding axis. One of possible application is drawing projections of 3D field. The sample code is:

```
int sample(mglGraph *gr)
{
  mglData c;  mgls_prepare3d(&c);
  gr->Title("Cont[XYZ] sample");  gr->Rotate(50,60);
  gr->Box();  gr->ContX(c.Sum("x"),"",-1);
  gr->ContY(c.Sum("y"),"",1); gr->ContZ(c.Sum("z"),"",-1);
  return 0;
}
```

Cont[XYZ] sample

2.7.10 ContF projection sample

Functions `ContFXYZ` draw filled contours on plane perpendicular to corresponding axis. One
of possible application is drawing projections of 3D field. The sample code is:

```
int sample(mglGraph *gr)
{
  mglData c;  mgls_prepare3d(&c);
  gr->Title("Cont[XYZ] sample");  gr->Rotate(50,60);
  gr->Box();  gr->ContFX(c.Sum("x"),"",-1);
  gr->ContFY(c.Sum("y"),"",1);  gr->ContFZ(c.Sum("z"),"",-1);
  return 0;
}
```

2.7.11 TriPlot and QuadPlot

Function [triplot], page 198 and [quadplot], page 199 draw set of triangles (or quadrangles for `QuadPlot`) for irregular data arrays. Note, that you have to provide not only vertexes, but also the indexes of triangles or quadrangles. I.e. perform triangulation by some other library. The sample code is:

```
int sample(mglGraph *gr)
{
  mreal q[] = {0,1,2,3, 4,5,6,7, 0,2,4,6, 1,3,5,7, 0,4,1,5, 2,6,3,7};
  mreal xc[] = {-1,1,-1,1,-1,1,-1,1}, yc[] = {-1,-1,1,1,-1,-1,1,1}, zc[] = {-1,-1,-1,-1,1,1,1
  mglData qq(6,4,q), xx(8,xc), yy(8,yc), zz(8,zc);
  gr->Light(true);  //gr->Alpha(true);
  gr->SubPlot(2,2,0); gr->Title("QuadPlot sample"); gr->Rotate(50,60);
  gr->QuadPlot(qq,xx,yy,zz,"yr");
  gr->QuadPlot(qq,xx,yy,zz,"k#");
  gr->SubPlot(2,2,2); gr->Title("QuadPlot coloring"); gr->Rotate(50,60);
  gr->QuadPlot(qq,xx,yy,zz,yy,"yr");
  gr->QuadPlot(qq,xx,yy,zz,"k#");

  mreal t[] = {0,1,2, 0,1,3, 0,2,3, 1,2,3};
  mreal xt[] = {-1,1,0,0}, yt[] = {-1,-1,1,0}, zt[] = {-1,-1,-1,1};
  mglData tt(4,3,t), uu(4,xt), vv(4,yt), ww(4,zt);
  gr->SubPlot(2,2,1); gr->Title("TriPlot sample");  gr->Rotate(50,60);
  gr->TriPlot(tt,uu,vv,ww,"b");
  gr->TriPlot(tt,uu,vv,ww,"k#");
  gr->SubPlot(2,2,3); gr->Title("TriPlot coloring");  gr->Rotate(50,60);
  gr->TriPlot(tt,uu,vv,ww,vv,"cb");
  gr->TriPlot(tt,uu,vv,ww,"k#");
  gr->TriCont(tt,uu,vv,ww,"B");
```

```
    return 0;
}
```

QuadPlot sample   TriPlot sample

QuadPlot coloring   TriPlot coloring

2.7.12 Dots sample

Function [dots], page 200 is another way to draw irregular points. Dots use color scheme for coloring (see Section 3.4 [Color scheme], page 128). The sample code is:

```
int sample(mglGraph *gr)
{
  int i, n=1000;
  mglData x(n),y(n),z(n);
  for(i=0;i<n;i++)
  {
    mreal t=M_PI*(mgl_rnd()-0.5), f=2*M_PI*mgl_rnd();
    x.a[i] = 0.9*cos(t)*cos(f);
    y.a[i] = 0.9*cos(t)*sin(f);
    z.a[i] = 0.6*sin(t);
  }
  gr->Title("Dots sample"); gr->Rotate(50,60);
  gr->Box();  gr->Dots(x,y,z);
  return 0;
}
```

Dots sample

2.8 Vector field samples

Vector field visualization (especially in 3d case) is more or less complex task. MathGL provides 3 general types of plots: vector field itself (`Vect`), flow threads (`Flow`), and flow pipes with radius proportional to field amplitude (`Pipe`).

However, the plot may look tangly – there are too many overlapping lines. I may suggest 2 ways to solve this problem. The first one is to change `SetMeshNum` for decreasing the number of hachures. The second way is to use the flow thread chart `Flow`, or possible many flow thread from manual position (`FlowP`). Unfortunately, I don't know any other methods to visualize 3d vector field. If you know any, e-mail me and I shall add it to MathGL.

Most of samples will use the same data for plotting. So, I put its initialization in separate function

```
void mgls_prepare2v(mglData *a, mglData *b)
{
  register long i,j,n=20,m=30,i0;
  if(a) a->Create(n,m);    if(b) b->Create(n,m);
  mreal x,y;
  for(i=0;i<n;i++)  for(j=0;j<m;j++)
  {
    x=i/(n-1.); y=j/(m-1.); i0 = i+n*j;
    if(a) a->a[i0] = 0.6*sin(2*M_PI*x)*sin(3*M_PI*y)+0.4*cos(3*M_PI*x*y);
    if(b) b->a[i0] = 0.6*cos(2*M_PI*x)*cos(3*M_PI*y)+0.4*cos(3*M_PI*x*y);
  }
}
void mgls_prepare3v(mglData *ex, mglData *ey, mglData *ez)
{
  register long i,j,k,n=10,i0;
  if(!ex || !ey || !ez) return;
```

```
  ex->Create(n,n,n);  ey->Create(n,n,n);  ez->Create(n,n,n);
  mreal x,y,z, r1,r2;
  for(i=0;i<n;i++)  for(j=0;j<n;j++)  for(k=0;k<n;k++)
  {
    x=2*i/(n-1.)-1; y=2*j/(n-1.)-1; z=2*k/(n-1.)-1; i0 = i+n*(j+k*n);
    r1 = pow(x*x+y*y+(z-0.3)*(z-0.3)+0.03,1.5);
    r2 = pow(x*x+y*y+(z+0.3)*(z+0.3)+0.03,1.5);
    ex->a[i0]=0.2*x/r1 - 0.2*x/r2;
    ey->a[i0]=0.2*y/r1 - 0.2*y/r2;
    ez->a[i0]=0.2*(z-0.3)/r1 - 0.2*(z+0.3)/r2;
  }
}
```

or using C functions

```
void mgls_prepare2v(HMDT a, HMDT b)
{
  register long i,j,n=20,m=30,i0;
  if(a) mgl_data_create(a,n,m,1);
  if(b) mgl_data_create(b,n,m,1);
  mreal x,y;
  for(i=0;i<n;i++)  for(j=0;j<m;j++)
  {
    x=i/(n-1.); y=j/(m-1.); i0 = i+n*j;
    if(a) mgl_data_set_value(a, 0.6*sin(2*M_PI*x)*sin(3*M_PI*y)+0.4*cos(3*M_PI*x*y), i,j,0)
    if(b) mgl_data_set_value(b, 0.6*cos(2*M_PI*x)*cos(3*M_PI*y)+0.4*cos(3*M_PI*x*y), i,j,0)
  }
}
void mgls_prepare3v(HMDT ex, HMDT ey, HMDT ez)
{
  register long i,j,k,n=10,i0;
  if(!ex || !ey || !ez) return;
  mgl_data_create(ex,n,n,n);
  mgl_data_create(ey,n,n,n);
  mgl_data_create(ez,n,n,n);
  mreal x,y,z, r1,r2;
  for(i=0;i<n;i++)  for(j=0;j<n;j++)  for(k=0;k<n;k++)
  {
    x=2*i/(n-1.)-1; y=2*j/(n-1.)-1; z=2*k/(n-1.)-1; i0 = i+n*(j+k*n);
    r1 = pow(x*x+y*y+(z-0.3)*(z-0.3)+0.03,1.5);
    r2 = pow(x*x+y*y+(z+0.3)*(z+0.3)+0.03,1.5);
    mgl_data_set_value(ex, 0.2*x/r1 - 0.2*x/r2, i,j,k);
    mgl_data_set_value(ey, 0.2*y/r1 - 0.2*y/r2, i,j,k);
    mgl_data_set_value(ez, 0.2*(z-0.3)/r1 - 0.2*(z+0.3)/r2, i,j,k);
  }
}
```

2.8.1 Vect sample

Function [vect], page 191 is most standard way to visualize vector fields – it draw a lot of arrows or hachures for each data cell. It have a lot of options which can be seen on the figure (and in the sample code). Vect use color scheme for coloring (see Section 3.4 [Color scheme], page 128). The sample code is:

```
int sample(mglGraph *gr)
{
  mglData a,b;  mgls_prepare2v(&a,&b);
  gr->SubPlot(3,2,0,""); gr->Title("Vect plot (default)");
  gr->Box();  gr->Vect(a,b);

  gr->SubPlot(3,2,1,"");  gr->Title("'.' style; '=' style");
  gr->Box();  gr->Vect(a,b,"=.");

  gr->SubPlot(3,2,2,"");  gr->Title("'f' style");
  gr->Box();  gr->Vect(a,b,"f");

  gr->SubPlot(3,2,3,"");  gr->Title("'>' style");
  gr->Box();  gr->Vect(a,b,">");

  gr->SubPlot(3,2,4,"");  gr->Title("'<' style");
  gr->Box();  gr->Vect(a,b,"<");

  mglData ex,ey,ez; mgls_prepare3v(&ex,&ey,&ez);
  gr->SubPlot(3,2,5); gr->Title("3d variant");  gr->Rotate(50,60);
  gr->Box();  gr->Vect(ex,ey,ez);
  return 0;
}
```

2.8.2 Vect3 sample

Function [vect3], page 191 draw just usual vector field plot but at slices of 3D data. The sample code is:

```
int sample(mglGraph *gr)
{
  mglData ex,ey,ez; mgls_prepare3v(&ex,&ey,&ez);
  gr->SubPlot(2,1,0); gr->Title("Vect3 sample");    gr->SetOrigin(0,0,0);
  gr->Rotate(50,60);    gr->Axis("_xyz");   gr->Box();
  gr->Vect3(ex,ey,ez,"x");  gr->Vect3(ex,ey,ez);    gr->Vect3(ex,ey,ez,"z");

  gr->SubPlot(2,1,1);   gr->Title("'f' style");
  gr->Rotate(50,60);    gr->Axis("_xyz");   gr->Box();
  gr->Vect3(ex,ey,ez,"fx"); gr->Vect3(ex,ey,ez,"f");gr->Vect3(ex,ey,ez,"fz");
  gr->Grid3(ex,"Wx");   gr->Grid3(ex,"W");  gr->Grid3(ex,"Wz");
  return 0;
}
```

Vect3 sample   'f' style

2.8.3 Traj sample

Function [traj], page 190 is 1D analogue of `Vect`. It draw vectors from specified points. The
sample code is:

```
int sample(mglGraph *gr)
{
  mglData x,y,y1,y2;  mgls_prepare1d(&y,&y1,&y2,&x);
  gr->SubPlot(1,1,0,""); gr->Title("Traj plot");
  gr->Box();  gr->Plot(x,y);  gr->Traj(x,y,y1,y2);
  return 0;
}
```

Traj plot

2.8.4 Flow sample

Function [flow], page 192 is another standard way to visualize vector fields – it draw lines
(threads) which is tangent to local vector field direction. MathGL draw threads from edges
of bounding box and from central slices. Sometimes it is not most appropriate variant –
you may want to use `FlowP` to specify manual position of threads. `Flow` use color scheme
for coloring (see Section 3.4 [Color scheme], page 128). At this warm color corresponds to
normal flow (like attractor), cold one corresponds to inverse flow (like source). The sample
code is:

```
int sample(mglGraph *gr)
{
  mglData a,b;  mgls_prepare2v(&a,&b);
  gr->SubPlot(2,2,0,""); gr->Title("Flow plot (default)");
  gr->Box();  gr->Flow(a,b);

  gr->SubPlot(2,2,1,"");  gr->Title("'v' style");
  gr->Box();  gr->Flow(a,b,"v");

  gr->SubPlot(2,2,2,"");  gr->Title("'\\#' style");
  gr->Box();  gr->Flow(a,b,"#");

  mglData ex,ey,ez; mgls_prepare3v(&ex,&ey,&ez);
  gr->SubPlot(2,2,3); gr->Title("3d variant");  gr->Rotate(50,60);
  gr->Box();  gr->Flow(ex,ey,ez);
  return 0;
}
```

Flow plot (default)   'v' style

'#' style   3d variant

2.8.5 Pipe sample

Function [pipe], page 194 is similar to [flow], page 192 but draw pipes (tubes) which radius is proportional to the amplitude of vector field. `Pipe` use color scheme for coloring (see Section 3.4 [Color scheme], page 128). At this warm color corresponds to normal flow (like attractor), cold one corresponds to inverse flow (like source). The sample code is:

```
int sample(mglGraph *gr)
{
  mglData a,b;  mgls_prepare2v(&a,&b);
  gr->SubPlot(2,2,0,""); gr->Title("Pipe plot (default)");
  gr->Light(true);  gr->Box();  gr->Pipe(a,b);

  gr->SubPlot(2,2,1,"");  gr->Title("'i' style");
  gr->Box();  gr->Pipe(a,b,"i");

  gr->SubPlot(2,2,2,"");  gr->Title("'\\#' style");
  gr->Box();  gr->Pipe(a,b,"#");

  mglData ex,ey,ez; mgls_prepare3v(&ex,&ey,&ez);
  gr->SubPlot(2,2,3); gr->Title("3d variant");  gr->Rotate(50,60);
  gr->Box();  gr->Pipe(ex,ey,ez,"",0.1);
  return 0;
}
```

Pipe plot (default)   'i' style

'#' style   3d variant

2.8.6 Dew sample

Function [dew], page 192 is similar to `Vect` but use drops instead of arrows. The sample code is:

```
int sample(mglGraph *gr)
{
  mglData a,b;  mgls_prepare2v(&a,&b);
  gr->SubPlot(1,1,0,""); gr->Title("Dew plot");
  gr->Box();  gr->Light(true);  gr->Dew(a,b);
  return 0;
}
```

Dew plot

2.9 Hints

In this section I've included some small hints and advices for the improving of the quality of plots and for the demonstration of some non-trivial features of MathGL library. In contrast to previous examples I showed mostly the idea but not the whole drawing function.

2.9.1 "Compound" graphics

As I noted above, MathGL functions (except the special one, like Clf()) do not erase the previous plotting but just add the new one. It allows one to draw "compound" plots easily. For example, popular Matlab command `surfc` can be emulated in MathGL by 2 calls:

```
Surf(a);
Cont(a, "_");      // draw contours at bottom
```

Here a is 2-dimensional data for the plotting, `-1` is the value of z-coordinate at which the contour should be plotted (at the bottom in this example). Analogously, one can draw density plot instead of contour lines and so on.

Another nice plot is contour lines plotted directly on the surface:

```
Light(true);         // switch on light for the surface
Surf(a, "BbcyrR");   // select 'jet' colormap for the surface
Cont(a, "y");        // and yellow color for contours
```

The possible difficulties arise in black&white case, when the color of the surface can be close to the color of a contour line. In that case I may suggest the following code:

```
Light(true);    // switch on light for the surface
Surf(a, "kw");  // select 'gray' colormap for the surface
CAxis(-1,0);    // first draw for darker surface colors
Cont(a, "w");   // white contours
CAxis(0,1);     // now draw for brighter surface colors
Cont(a, "k");   // black contours
CAxis(-1,1);    // return color range to original state
```

The idea is to divide the color range on 2 parts (dark and bright) and to select the contrasting color for contour lines for each of part.

Similarly, one can plot flow thread over density plot of vector field amplitude (this is another amusing plot from Matlab) and so on. The list of compound graphics can be prolonged but I hope that the general idea is clear.

Just for illustration I put here following sample code:

```
int sample(mglGraph *gr)
{
  mglData a,b,d;  mgls_prepare2v(&a,&b);   d = a;
  for(int i=0;i<a.nx*a.ny;i++)  d.a[i] = hypot(a.a[i],b.a[i]);
  mglData c;  mgls_prepare3d(&c);
  mglData v(10);  v.Fill(-0.5,1);

  gr->SubPlot(2,2,1,"");  gr->Title("Flow + Dens");
  gr->Flow(a,b,"br"); gr->Dens(d,"BbcyrR"); gr->Box();

  gr->SubPlot(2,2,0); gr->Title("Surf + Cont"); gr->Rotate(50,60);
  gr->Light(true);  gr->Surf(a);  gr->Cont(a,"y");  gr->Box();

  gr->SubPlot(2,2,2); gr->Title("Mesh + Cont"); gr->Rotate(50,60);
  gr->Box();  gr->Mesh(a);  gr->Cont(a,"_");

  gr->SubPlot(2,2,3); gr->Title("Surf3 + ContF3");gr->Rotate(50,60);
  gr->Box();  gr->ContF3(v,c,"z",0);  gr->ContF3(v,c,"x");  gr->ContF3(v,c);
  gr->SetCutBox(mglPoint(0,-1,-1), mglPoint(1,0,1.1));
  gr->ContF3(v,c,"z",c.nz-1); gr->Surf3(-0.5,c);
  return 0;
}
```

Surf + Cont

Flow + Dens

Mesh + Cont

Surf3 + ContF3

2.9.2 Transparency and lighting

Here I want to show how transparency and lighting both and separately change the look of
a surface. So, there is code and picture for that:

```
int sample(mglGraph *gr)
{
  mglData a;  mgls_prepare2d(&a);
  gr->SubPlot(2,2,0); gr->Title("default"); gr->Rotate(50,60);
  gr->Box();  gr->Surf(a);

  gr->SubPlot(2,2,1); gr->Title("light on");  gr->Rotate(50,60);
  gr->Box();  gr->Light(true);  gr->Surf(a);

  gr->SubPlot(2,2,3); gr->Title("alpha on; light on");  gr->Rotate(50,60);
  gr->Box();  gr->Alpha(true);  gr->Surf(a);

  gr->SubPlot(2,2,2); gr->Title("alpha on");  gr->Rotate(50,60);
  gr->Box();  gr->Light(false); gr->Surf(a);
  return 0;
}
```

2.9.3 Types of transparency

MathGL library has advanced features for setting and handling the surface transparency. The simplest way to add transparency is the using of function [alpha], page 135. As a result, all further surfaces (and isosurfaces, density plots and so on) become transparent. However, their look can be additionally improved.

The value of transparency can be different from surface to surface. To do it just use `SetAlphaDef` before the drawing of the surface, or use option `alpha` (see Section 3.7 [Command options], page 132). If its value is close to 0 then the surface becomes more and more transparent. Contrary, if its value is close to 1 then the surface becomes practically non-transparent.

Also you can change the way how the light goes through overlapped surfaces. The function `SetTranspType` defines it. By default the usual transparency is used ('0') – surfaces below is less visible than the upper ones. A "glass-like" transparency ('1') has a different look – each surface just decreases the background light (the surfaces are commutable in this case).

A "neon-like" transparency ('2') has more interesting look. In this case a surface is the light source (like a lamp on the dark background) and just adds some intensity to the color. At this, the library sets automatically the black color for the background and changes the default line color to white.

As example I shall show several plots for different types of transparency. The code is the same except the values of `SetTranspType` function:

```
int sample(mglGraph *gr)
{
  gr->Alpha(true);  gr->Light(true);
  mglData a;  mgls_prepare2d(&a);
  gr->SetTranspType(0); gr->Clf();
  gr->SubPlot(2,2,0); gr->Rotate(50,60);  gr->Surf(a);  gr->Box();
```

```
gr->SubPlot(2,2,1); gr->Rotate(50,60);  gr->Dens(a);  gr->Box();
gr->SubPlot(2,2,2); gr->Rotate(50,60);  gr->Cont(a);  gr->Box();
gr->SubPlot(2,2,3); gr->Rotate(50,60);  gr->Axial(a); gr->Box();
return 0;
}
```

2.9.4 Axis projection

You can easily make 3D plot and draw its x-,y-,z-projections (like in CAD) by using [ternary], page 144 function with arguments: 4 for Cartesian, 5 for Ternary and 6 for Quaternary coordinates. The sample code is:

```
int sample(mglGraph *gr)
{
  gr->SetRanges(0,1,0,1,0,1);
  mglData x(50),y(50),z(50),rx(10),ry(10), a(20,30);
  a.Modify("30*x*y*(1-x-y)^2*(x+y<1)");
  x.Modify("0.25*(1+cos(2*pi*x))");
  y.Modify("0.25*(1+sin(2*pi*x))");
  rx.Modify("rnd"); ry.Modify("(1-v)*rnd",rx);
  z.Modify("x");

  gr->Title("Projection sample");
  gr->Ternary(4);
  gr->Rotate(50,60);      gr->Light(true);
  gr->Plot(x,y,z,"r2");   gr->Surf(a,"#");
  gr->Axis(); gr->Grid(); gr->Box();
  gr->Label('x',"X",1);   gr->Label('y',"Y",1);   gr->Label('z',"Z",1);
}
```

Projection sample

Projection sample (ternary)

2.9.5 Adding fog

MathGL can add a fog to the image. Its switching on is rather simple – just use [fog], page 137 function. There is the only feature – fog is applied for whole image. Not to particular subplot. The sample code is:

```
int sample(mglGraph *gr)
{
  mglData a;  mgls_prepare2d(&a);
  gr->Title("Fog sample");
  gr->Light(true);  gr->Rotate(50,60);  gr->Fog(1); gr->Box();
```

```
  gr->Surf(a);
  return 0;
}
```

Fog sample

2.9.6 Several light sources

In contrast to the most of other programs, MathGL supports several (up to 10) light sources. Moreover, the color each of them can be different: white (this is usual), yellow, red, cyan, green and so on. The use of several light sources may be interesting for the highlighting of some peculiarities of the plot or just to make an amusing picture. Note, each light source can be switched on/off individually. The sample code is:

```
int sample(mglGraph *gr)
{
  mglData a;  mgls_prepare2d(&a);
  gr->Title("Several light sources");
  gr->Rotate(50,60);  gr->Light(true);
  gr->AddLight(1,mglPoint(0,1,0),'c');
  gr->AddLight(2,mglPoint(1,0,0),'y');
  gr->AddLight(3,mglPoint(0,-1,0),'m');
  gr->Box();  gr->Surf(a,"h");
  return 0;
}
```

Several light sources

2.9.7 Using primitives

MathGL provide a set of functions for drawing primitives (see Section 4.6 [Primitives], page 158). Primitives are low level object, which used by most of plotting functions. Picture below demonstrate some of commonly used primitives.

Generally, you can create arbitrary new kind of plot using primitives. For example, MathGL don't provide any special functions for drawing molecules. However, you can do it using only one type of primitives [drop], page 160. The sample code is:

```
int sample(mglGraph *gr)
{
```

```
gr->Alpha(true);  gr->Light(true);

gr->SubPlot(2,2,0,"");  gr->Title("Methane, CH_4");
gr->StartGroup("Methane");
gr->Rotate(60,120);
gr->Sphere(mglPoint(0,0,0),0.25,"k");
gr->Drop(mglPoint(0,0,0),mglPoint(0,0,1),0.35,"h",1,2);
gr->Sphere(mglPoint(0,0,0.7),0.25,"g");
gr->Drop(mglPoint(0,0,0),mglPoint(-0.94,0,-0.33),0.35,"h",1,2);
gr->Sphere(mglPoint(-0.66,0,-0.23),0.25,"g");
gr->Drop(mglPoint(0,0,0),mglPoint(0.47,0.82,-0.33),0.35,"h",1,2);
gr->Sphere(mglPoint(0.33,0.57,-0.23),0.25,"g");
gr->Drop(mglPoint(0,0,0),mglPoint(0.47,-0.82,-0.33),0.35,"h",1,2);
gr->Sphere(mglPoint(0.33,-0.57,-0.23),0.25,"g");
gr->EndGroup();

gr->SubPlot(2,2,1,"");  gr->Title("Water, H_{2}O");
gr->StartGroup("Water");
gr->Rotate(60,100);
gr->StartGroup("Water_O");
gr->Sphere(mglPoint(0,0,0),0.25,"r");
gr->EndGroup();
gr->StartGroup("Water_Bond_1");
gr->Drop(mglPoint(0,0,0),mglPoint(0.3,0.5,0),0.3,"m",1,2);
gr->EndGroup();
gr->StartGroup("Water_H_1");
gr->Sphere(mglPoint(0.3,0.5,0),0.25,"g");
gr->EndGroup();
gr->StartGroup("Water_Bond_2");
gr->Drop(mglPoint(0,0,0),mglPoint(0.3,-0.5,0),0.3,"m",1,2);
gr->EndGroup();
gr->StartGroup("Water_H_2");
gr->Sphere(mglPoint(0.3,-0.5,0),0.25,"g");
gr->EndGroup();
gr->EndGroup();

gr->SubPlot(2,2,2,"");  gr->Title("Oxygen, O_2");
gr->StartGroup("Oxygen");
gr->Rotate(60,120);
gr->Drop(mglPoint(0,0.5,0),mglPoint(0,-0.3,0),0.3,"m",1,2);
gr->Sphere(mglPoint(0,0.5,0),0.25,"r");
gr->Drop(mglPoint(0,-0.5,0),mglPoint(0,0.3,0),0.3,"m",1,2);
gr->Sphere(mglPoint(0,-0.5,0),0.25,"r");
gr->EndGroup();

gr->SubPlot(2,2,3,"");  gr->Title("Ammonia, NH_3");
gr->StartGroup("Ammonia");
```

```
  gr->Rotate(60,120);
  gr->Sphere(mglPoint(0,0,0),0.25,"b");
  gr->Drop(mglPoint(0,0,0),mglPoint(0.33,0.57,0),0.32,"n",1,2);
  gr->Sphere(mglPoint(0.33,0.57,0),0.25,"g");
  gr->Drop(mglPoint(0,0,0),mglPoint(0.33,-0.57,0),0.32,"n",1,2);
  gr->Sphere(mglPoint(0.33,-0.57,0),0.25,"g");
  gr->Drop(mglPoint(0,0,0),mglPoint(-0.65,0,0),0.32,"n",1,2);
  gr->Sphere(mglPoint(-0.65,0,0),0.25,"g");
  gr->EndGroup();
  return 0;
}
```

<div align="center">

Methane, CH$_4$ **Water, H$_2$O**

Oxygen, O$_2$ **Ammonia, NH$_3$**

</div>

Moreover, some of special plots can be more easily produced by primitives rather than by specialized function. For example, Venn diagram can be produced by `Error` plot:

```
int sample(mglGraph *gr)
{
  double xx[3]={-0.3,0,0.3}, yy[3]={0.3,-0.3,0.3}, ee[3]={0.7,0.7,0.7};
  mglData x(3,xx), y(3,yy), e(3,ee);
  gr->Title("Venn-like diagram"); gr->Alpha(true);
  gr->Error(x,y,e,e,"!rgb@#o");
  return 0;
}
```

You see that you have to specify and fill 3 data arrays. The same picture can be produced by just 3 calls of [circle], page 160 function:

```
int sample(mglGraph *gr)
{
  gr->Title("Venn-like diagram"); gr->Alpha(true);
  gr->Circle(mglPoint(-0.3,0.3),0.7,"rr@");
```

```
  gr->Circle(mglPoint(0,-0.3),0.7,"gg@");
  gr->Circle(mglPoint( 0.3,0.3),0.7,"bb@");
  return 0;
}
```

Of course, the first variant is more suitable if you need to plot a lot of circles. But for few ones the usage of primitives looks easy.

Venn-like diagram

2.9.8 STFA sample

Short-time Fourier Analysis ([stfa], page 190) is one of informative method for analyzing long rapidly oscillating 1D data arrays. It is used to determine the sinusoidal frequency and phase content of local sections of a signal as it changes over time.

MathGL can find and draw STFA result. Just to show this feature I give following sample. Initial data arrays is 1D arrays with step-like frequency. Exactly this you can see at bottom on the STFA plot. The sample code is:

```
int sample(mglGraph *gr)
{
  mglData a(2000), b(2000);
  gr->Fill(a,"cos(50*pi*x)*(x<-.5)+cos(100*pi*x)*(x<0)*(x>-.5)+\
  cos(200*pi*x)*(x<.5)*(x>0)+cos(400*pi*x)*(x>.5)");
  gr->SubPlot(1, 2, 0,"<_");  gr->Title("Initial signal");
  gr->Plot(a);
  gr->Axis();
  gr->Label('x', "\\i t");

  gr->SubPlot(1, 2, 1,"<_");  gr->Title("STFA plot");
  gr->STFA(a, b, 64);
  gr->Axis();
```

```
  gr->Label('x', "\\i t");
  gr->Label('y', "\\omega", 0);
  return 0;
}
```

Initial signal

STFA plot

2.9.9 Mapping visualization

Sometime ago I worked with mapping and have a question about its visualization. Let me remember you that mapping is some transformation rule for one set of number to another one. The 1d mapping is just an ordinary function – it takes a number and transforms it to another one. The 2d mapping (which I used) is a pair of functions which take 2 numbers and transform them to another 2 ones. Except general plots (like [surfc], page 187, [surfa], page 188) there is a special plot – Arnold diagram. It shows the area which is the result of mapping of some initial area (usually square).

I tried to make such plot in [map], page 189. It shows the set of points or set of faces, which final position is the result of mapping. At this, the color gives information about their initial position and the height describes Jacobian value of the transformation. Unfortunately, it looks good only for the simplest mapping but for the real multivalent quasi-chaotic mapping it produces a confusion. So, use it if you like :).

The sample code for mapping visualization is:

```
int sample(mglGraph *gr)
{
  mglData a(50, 40), b(50, 40);
  gr->Puts(mglPoint(0, 0), "\\to", ":C", -1.4);
  gr->SetRanges(-1,1,-1,1,-2,2);

  gr->SubPlot(2, 1, 0);
  gr->Fill(a,"x");  gr->Fill(b,"y");
```

```
gr->Puts(mglPoint(0, 1.1), "\\{x, y\\}", ":C", -2);   gr->Box();
gr->Map(a, b, "brgk");

gr->SubPlot(2, 1, 1);
gr->Fill(a,"(x^3+y^3)/2");  gr->Fill(b,"(x-y)/2");
gr->Puts(mglPoint(0, 1.1), "\\{\\frac{x^3+y^3}{2}, \\frac{x-y}{2}\\}", ":C", -2);
gr->Box();
gr->Map(a, b, "brgk");
return 0;
}
```


2.9.10 Making histogram

Using the [hist], page 227 function(s) for making regular distributions is one of useful fast methods to process and plot irregular data. Hist can be used to find some momentum of set of points by specifying weight function. It is possible to create not only 1D distributions but also 2D and 3D ones. Below I place the simplest sample code which demonstrate [hist], page 227 usage:

```
int sample(mglGraph *gr)
{
  mglData x(10000), y(10000), z(10000);  gr->Fill(x,"2*rnd-1");
  gr->Fill(y,"2*rnd-1"); gr->Fill(z,"exp(-6*(v^2+w^2))",x,y);
  mglData xx=gr->Hist(x,z), yy=gr->Hist(y,z);   xx.Norm(0,1);
  yy.Norm(0,1);
  gr->MultiPlot(3,3,3,2,2,"");   gr->SetRanges(-1,1,-1,1,0,1);
  gr->Box();  gr->Dots(x,y,z,"wyrRk");
  gr->MultiPlot(3,3,0,2,1,"");   gr->SetRanges(-1,1,0,1);
  gr->Box();  gr->Bars(xx);
```

```
gr->MultiPlot(3,3,5,1,2,"");   gr->SetRanges(0,1,-1,1);
gr->Box();  gr->Barh(yy);
gr->SubPlot(3,3,2);
gr->Puts(mglPoint(0.5,0.5),"Hist and\nMultiPlot\nsample","a",-6);
return 0;
}
```


2.9.11 Nonlinear fitting hints

Nonlinear fitting is rather simple. All that you need is the data to fit, the approximation formula and the list of coefficients to fit (better with its initial guess values). Let me demonstrate it on the following simple example. First, let us use sin function with some random noise:

```
mglData rnd(100), in(100); //data to be fitted and ideal data
gr->Fill(rnd,"0.4*rnd+0.1+sin(2*pi*x)");
gr->Fill(in,"0.3+sin(2*pi*x)");
```

and plot it to see that data we will fit

```
gr->Title("Fitting sample");
gr->SetRange('y',-2,2); gr->Box();  gr->Plot(rnd, ". ");
gr->Axis(); gr->Plot(in, "b");
gr->Puts(mglPoint(0, 2.2), "initial: y = 0.3+sin(2\\pi x)", "b");
```

The next step is the fitting itself. For that let me specify an initial values *ini* for coefficients 'abc' and do the fitting for approximation formula 'a+b*sin(c*x)'

```
mreal ini[3] = {1,1,3};
mglData Ini(3,ini);
mglData res = gr->Fit(rnd, "a+b*sin(c*x)", "abc", Ini);
```

Now display it

```
gr->Plot(res, "r");
gr->Puts(mglPoint(-0.9, -1.3), "fitted:", "r:L");
gr->PutsFit(mglPoint(0, -1.8), "y = ", "r");
```

NOTE! the fitting results may have strong dependence on initial values for coefficients due to algorithm features. The problem is that in general case there are several local "optimums" for coefficients and the program returns only first found one! There are no guaranties that it will be the best. Try for example to set ini[3] = {0, 0, 0} in the code above.

The full sample code for nonlinear fitting is:

```
int sample(mglGraph *gr)
{
  mglData rnd(100), in(100);
  gr->Fill(rnd,"0.4*rnd+0.1+sin(2*pi*x)");
  gr->Fill(in,"0.3+sin(2*pi*x)");
  mreal ini[3] = {1,1,3};
  mglData Ini(3,ini);

  mglData res = gr->Fit(rnd, "a+b*sin(c*x)", "abc", Ini);

  gr->Title("Fitting sample");
  gr->SetRange('y',-2,2); gr->Box();  gr->Plot(rnd, ". ");
  gr->Axis();   gr->Plot(res, "r"); gr->Plot(in, "b");
  gr->Puts(mglPoint(-0.9, -1.3), "fitted:", "r:L");
  gr->PutsFit(mglPoint(0, -1.8), "y = ", "r");
  gr->Puts(mglPoint(0, 2.2), "initial: y = 0.3+sin(2\\pi x)", "b");
  return 0;
}
```

Fitting sample

2.9.12 PDE solving hints

Solving of Partial Differential Equations (PDE, including beam tracing) and ray tracing (or finding particle trajectory) are more or less common task. So, MathGL have several functions for that. There are `mglRay()` for ray tracing, `mglPDE()` for PDE solving, `mglQO2d()` for beam tracing in 2D case (see Section 6.11 [Global functions], page 237). Note, that these functions take "Hamiltonian" or equations as string values. And I don't plan now to allow one to use user-defined functions. There are 2 reasons: the complexity of corresponding interface; and the basic nature of used methods which are good for samples but may not good for serious scientific calculations.

The ray tracing can be done by `mglRay()` function. Really ray tracing equation is Hamiltonian equation for 3D space. So, the function can be also used for finding a particle trajectory (i.e. solve Hamiltonian ODE) for 1D, 2D or 3D cases. The function have a set of arguments. First of all, it is Hamiltonian which defined the media (or the equation) you are planning to use. The Hamiltonian is defined by string which may depend on coordinates 'x', 'y', 'z', time 't' (for particle dynamics) and momentums 'p'=p_x, 'q'=p_y, 'v'=p_z. Next, you have to define the initial conditions for coordinates and momentums at 't'=0 and set the integrations step (default is 0.1) and its duration (default is 10). The Runge-Kutta method of 4-th order is used for integration.

```
const char *ham = "p^2+q^2-x-1+i*0.5*(y+x)*(y>-x)";
mglData r = mglRay(ham, mglPoint(-0.7, -1), mglPoint(0, 0.5), 0.02, 2);
```

This example calculate the reflection from linear layer (media with Hamiltonian 'p^2+q^2-x-1'=$p_x^2 + p_y^2 - x - 1$). This is parabolic curve. The resulting array have 7 columns which contain data for {x,y,z,p,q,v,t}.

The solution of PDE is a bit more complicated. As previous you have to specify the equation as pseudo-differential operator $\hat H(x, \nabla)$ which is called sometime as "Hamiltonian" (for example, in beam tracing). As previously, it is defined by string which may depend on coordinates 'x', 'y', 'z' (but not time!), momentums 'p'=$(d/dx)/ik_0$, 'q'=$(d/dy)/ik_0$ and field amplitude 'u'=$|u|$. The evolutionary coordinate is 'z' in all cases. So that, the equation look like $du/dz = ik_0 H(x, y, \hat p, \hat q, |u|)[u]$. Dependence on field amplitude 'u'=$|u|$ allows one to solve nonlinear problems too. For example, for nonlinear Shrodinger equation you may set `ham="p^2 + q^2 - u^2"`. Also you may specify imaginary part for wave absorption, like `ham = "p^2 + i*x*(x>0)"`, but only if dependence on variable 'i' is linear (i.e. $H = Hre + i * Him$).

Next step is specifying the initial conditions at 'z'=`Min.z`. The function need 2 arrays for real and for imaginary part. Note, that coordinates x,y,z are supposed to be in specified range [Min, Max]. So, the data arrays should have corresponding scales. Finally, you may set the integration step and parameter k0=k_0. Also keep in mind, that internally the 2 times large box is used (for suppressing numerical reflection from boundaries) and the equation should well defined even in this extended range.

Final comment is concerning the possible form of pseudo-differential operator H. At this moment, simplified form of operator H is supported – all "mixed" terms (like 'x*p'->x*d/dx) are excluded. For example, in 2D case this operator is effectively $H = f(p, z) + g(x, z, u)$. However commutable combinations (like 'x*q'->x*d/dy) are allowed for 3D case.

So, for example let solve the equation for beam deflected from linear layer and absorbed later. The operator will have the form '`"p^2+q^2-x-1+i*0.5*(z+x)*(z>-x)"`' that corre-

spond to equation $ik_0\partial_z u + \Delta u + x \cdot u + i(x+z)/2 \cdot u = 0$. This is typical equation for Electron Cyclotron (EC) absorption in magnetized plasmas. For initial conditions let me select the beam with plane phase front $exp(-48*(x+0.7)^2)$. The corresponding code looks like this:

```
int sample(mglGraph *gr)
{
  mglData a,re(128),im(128);
  gr->Fill(re,"exp(-48*(x+0.7)^2)");
  a = gr->PDE("p^2+q^2-x-1+i*0.5*(z+x)*(z>-x)", re, im, 0.01, 30);
  a.Transpose("yxz");
  gr->SubPlot(1,1,0,"<_"); gr->Title("PDE solver");
  gr->SetRange('c',0,1);  gr->Dens(a,"wyrRk");
  gr->Axis(); gr->Label('x', "\\i x");  gr->Label('y', "\\i z");
  gr->FPlot("-x", "k|");
  gr->Puts(mglPoint(0, 0.85), "absorption: (x+z)/2 for x+z>0");
  gr->Puts(mglPoint(0,1.1),"Equation: ik_0\\partial_zu + \\Delta u + x\\cdot u + i \\frac{x
  return 0;
}
```


The last example is example of beam tracing. Beam tracing equation is special kind of PDE equation written in coordinates accompanied to a ray. Generally this is the same parameters and limitation as for PDE solving but the coordinates are defined by the ray and by parameter of grid width w in direction transverse the ray. So, you don't need to specify the range of coordinates. **BUT** there is limitation. The accompanied coordinates are well defined only for smooth enough rays, i.e. then the ray curvature K (which is defined as $1/K^2 = (|\ddot{r}|^2|\dot{r}|^2 - (\ddot{r},\dot{r})^2)/|\dot{r}|^6$) is much large then the grid width: $K \gg w$. So, you may receive incorrect results if this condition will be broken.

You may use following code for obtaining the same solution as in previous example:

```
int sample(mglGraph *gr)
{
  mglData r, xx, yy, a, im(128), re(128);
  const char *ham = "p^2+q^2-x-1+i*0.5*(y+x)*(y>-x)";
  r = mglRay(ham, mglPoint(-0.7, -1), mglPoint(0, 0.5), 0.02, 2);
  gr->SubPlot(1,1,0,"<_"); gr->Title("Beam and ray tracing");
  gr->Plot(r.SubData(0), r.SubData(1), "k");
  gr->Axis(); gr->Label('x', "\\i x");  gr->Label('y', "\\i z");

  // now start beam tracing
  gr->Fill(re,"exp(-48*x^2)");
  a = mglQO2d(ham, re, im, r, xx, yy, 1, 30);
  gr->SetRange('c',0, 1);
  gr->Dens(xx, yy, a, "wyrRk");
  gr->FPlot("-x", "k|");
  gr->Puts(mglPoint(0, 0.85), "absorption: (x+y)/2 for x+y>0");
  gr->Puts(mglPoint(0.7, -0.05), "central ray");
  return 0;
}
```


2.9.13 MGL parser using

Sometimes you may prefer to use MGL scripts in yours code. It is simpler (especially in comparison with C/Fortran interfaces) and provide faster way to plot the data with annotations, labels and so on. Class `mglParse` (see Section 7.3 [mglParse class], page 244 parse MGL scripts in C++. It have also the corresponding interface for C/Fortran.

The key function here is `mglParse::Parse()` (or `mgl_parse()` for C/Fortran) which execute one command per string. At this the detailed information about the possible errors

or warnings is passed as function value. Or you may execute the whole script as long string with lines separated by '\n'. Functions `mglParse::Execute()` and `mgl_parse_text()` perform it. Also you may set the values of parameters '$0'...'$9' for the script by functions `mglParse::AddParam()` or `mgl_add_param()`, allow/disable picture resizing, check "once" status and so on. The usage is rather straight-forward.

The only non-obvious thing is data transition between script and yours program. There are 2 stages: add or find variable; and set data to variable. In C++ you may use functions `mglParse::AddVar()` and `mglParse::FindVar()` which return pointer to `mglData`. In C/Fortran the corresponding functions are `mgl_add_var()`, `mgl_find_var()`. This data pointer is valid until next `Parse()` or `Execute()` call. Note, you **must not delete or free** the data obtained from these functions!

So, some simple example at the end. Here I define a data array, create variable, put data into it and plot it. The C++ code looks like this:

```
int sample(mglGraph *gr)
{
  gr->Title("MGL parser sample");
  mreal a[100];    // let a_i = sin(4*pi*x), x=0...1
  for(int i=0;i<100;i++)a[i]=sin(4*M_PI*i/99);
  mglParse *parser = new mglParse;
  mglData *d = parser->AddVar("dat");
  d->Set(a,100); // set data to variable
  parser->Execute(gr, "plot dat; xrange 0 1\nbox\naxis");
  // you may break script at any line do something
  // and continue after that
  parser->Execute(gr, "xlabel 'x'\nylabel 'y'\nbox");
  // also you may use cycles or conditions in script
  parser->Execute(gr, "for $0 -1 1 0.1\nif $0<0\n"
    "line 0 0 -1 $0 'r':else:line 0 0 -1 $0 'g'\n"
    "endif\nnext");
  delete parser;
  return 0;
}
```

The code in C/Fortran looks practically the same:

```
int sample(HMGL gr)
{
  mgl_title(gr, "MGL parser sample", "", -2);
  double a[100];    // let a_i = sin(4*pi*x), x=0...1
  int i;
  for(i=0;i<100;i++)  a[i]=sin(4*M_PI*i/99);
  HMPR parser = mgl_create_parser();
  HMDT d = mgl_parser_add_var(parser, "dat");
  mgl_data_set_double(d,a,100,1,1);     // set data to variable
  mgl_parse_text(gr, parser, "plot dat; xrange 0 1\nbox\naxis");
  // you may break script at any line do something
  // and continue after that
  mgl_parse_text(gr, parser, "xlabel 'x'\nylabel 'y'");
```

```
  // also you may use cycles or conditions in script
  mgl_parse_text(gr, parser, "for $0 -1 1 0.1\nif $0<0\n"
    "line 0 0 -1 $0 'r':else:line 0 0 -1 $0 'g'\n"
    "endif\nnext");
  mgl_write_png(gr, "test.png", "");  // don't forgot to save picture
  return 0;
}
```


MGL parser sample

2.9.14 Using options

allow the easy setup of the selected plot by changing global settings only for this plot. Often, options are used for specifying the range of automatic variables (coordinates). However, options allows easily change plot transparency, numbers of line or faces to be drawn, or add legend entries. The sample function for options usage is:

```
void template(mglGraph *gr)
{
  mglData a(31,41);
  gr->Fill(a,"-pi*x*exp(-(y+1)^2-4*x^2)");

  gr->SubPlot(2,2,0);    gr->Title("Options for coordinates");
  gr->Alpha(true);       gr->Light(true);
  gr->Rotate(40,60);     gr->Box();
  gr->Surf(a,"r","yrange 0 1"); gr->Surf(a,"b","yrange 0 -1");
  if(mini)       return;
  gr->SubPlot(2,2,1);    gr->Title("Option 'meshnum'");
  gr->Rotate(40,60);     gr->Box();
  gr->Mesh(a,"r","yrange 0 1"); gr->Mesh(a,"b","yrange 0 -1; meshnum 5");
```

```
gr->SubPlot(2,2,2);    gr->Title("Option 'alpha'");
gr->Rotate(40,60);     gr->Box();
gr->Surf(a,"r","yrange 0 1; alpha 0.7");
gr->Surf(a,"b","yrange 0 -1; alpha 0.3");
gr->SubPlot(2,2,3,"<_");  gr->Title("Option 'legend'");
gr->FPlot("x^3","r","legend 'y = x^3'");
gr->FPlot("cos(pi*x)","b","legend 'y = cos \\pi x'");
gr->Box();     gr->Axis(); gr->Legend(2,"");
}
```


2.9.15 "Templates"

As I have noted before, the change of settings will influence only for the further plotting commands. This allows one to create "template" function which will contain settings and primitive drawing for often used plots. Correspondingly one may call this template-function for drawing simplification.

For example, let one has a set of points (experimental or numerical) and wants to compare it with theoretical law (for example, with exponent law $\exp(-x/2), x \in [0, 20]$). The template-function for this task is:

```
void template(mglGraph *gr)
{
  mglData  law(100);      // create the law
  law.Modify("exp(-10*x)");
  gr->SetRanges(0,20, 0.0001,1);
  gr->SetFunc(0,"lg(y)",0);
  gr->Plot(law,"r2");
  gr->Puts(mglPoint(10,0.2),"Theoretical law: e^x","r:L");
  gr->Label('x',"x val."); gr->Label('y',"y val.");
```

```
  gr->Axis(); gr->Grid("xy","g;"); gr->Box();
}
```

At this, one will only write a few lines for data drawing:

```
template(gr);       // apply settings and default drawing from template
mglData dat("fname.dat"); // load the data
// and draw it (suppose that data file have 2 columns)
gr->Plot(dat.SubData(0),dat.SubData(1),"bx ");
```

A template-function can also contain settings for font, transparency, lightning, color scheme and so on.

I understand that this is obvious thing for any professional programmer, but I several times receive suggestion about "templates" ... So, I decide to point out it here.

2.9.16 Stereo image

One can easily create stereo image in MathGL. Stereo image can be produced by making two subplots with slightly different rotation angles. The corresponding code looks like this:

```
int sample(mglGraph *gr)
{
  mglData a;  mgls_prepare2d(&a);
  gr->Light(true);

  gr->SubPlot(2,1,0); gr->Rotate(50,60+1);
  gr->Box();  gr->Surf(a);

  gr->SubPlot(2,1,1); gr->Rotate(50,60-1);
  gr->Box();  gr->Surf(a);
  return 0;
}
```

2.9.17 Reduce memory usage

By default MathGL save all primitives in memory, rearrange it and only later draw them on bitmaps. Usually, this speed up drawing, but may require a lot of memory for plots which contain a lot of faces (like [cloud], page 184, [dew], page 192). You can use [quality], page 150 function for setting to use direct drawing on bitmap and bypassing keeping any primitives in memory. This function also allow you to decrease the quality of the resulting image but increase the speed of the drawing.

The code for lowest memory usage looks like this:

```
int sample(mglGraph *gr)
{
  gr->SetQuality(6);   // firstly, set to draw directly on bitmap
  for(i=0;i<1000;i++)
    gr->Sphere(mglPoint(mgl_rnd()*2-1,mgl_rnd()*2-1),0.05);
  return 0;
}
```

2.10 FAQ

The plot does not appear

> Check that points of the plot are located inside the bounding box and resize the bounding box using [ranges], page 142 function. Check that the data have correct dimensions for selected type of plot. Be sure that `Finish()` is called after the plotting functions (or be sure that the plot is saved to a file). Sometimes the light reflection from flat surfaces (like, [dens], page 179) can look as if the plot were absent.

I can not find some special kind of plot.

> Most "new" types of plots can be created by using the existing drawing functions. For example, the surface of curve rotation can be created by a special function [torus], page 176, or as a parametrically specified surface by [surf], page 177. See also, Section 2.9 [Hints], page 99. If you can not find a specific type of plot, please e-mail me and this plot will appear in the next version of MathGL library.

Should I know some graphical libraries (like OpenGL) before using the MathGL library?

> No. The MathGL library is self-contained and does not require the knowledge of external libraries.

In which language is the library written? For which languages does it have an interface?

> The core of the MathGL library is written in C++. But there are interfaces for: pure C, Fortran, Pascal, Forth, and its own command language MGL. Also there is a large set of interpreted languages, which are supported (Python, Java, ALLEGROCL, CHICKEN, Lisp, CFFI, C#, Guile, Lua, Modula 3, Mzscheme, Ocaml, Octave, Perl, PHP, Pike, R, Ruby, Tcl). These interfaces are written using SWIG (both pure C functions and classes) but only the interface for Python and Octave is included in the build system. The reason is that I don't know any other interpreted languages :(. Note that most other languages can use (link to) the pure C functions.

How can I use MathGL with Fortran?

You can use MathGL as is with `gfortran` because it uses by default the AT&T notation for external functions. For other compilers (like Visual Fortran) you have to switch on the AT&T notation manually. The AT&T notation requires that the symbol '`_`' is added at the end of each function name, function argument(s) is passed by pointers and the string length(s) is passed at the end of the argument list. For example:

C function – `void mgl_fplot(HMGL graph, const char *fy, const char *stl, int n);`

AT&T function – `void mgl_fplot_(uintptr_t *graph, const char *fy, const char *stl, int *n, int ly, int ls);`

Fortran users also should add C++ library by the option `-lstdc++`. If library was built with `enable-double=ON` (this default for v.2.1 and later) then all real numbers must be `real*8`. You can make it automatic if use option `-fdefault-real-8`.

How can I print in Russian/Spanish/Arabic/Japanese, and so on?

The standard way is to use Unicode encoding for the text output. But the MathGL library also has interface for 8-bit (char *) strings with internal conversion to Unicode. This conversion depends on the current locale OS. You may change it by `setlocale()` function. For example, for Russian text in CP1251 encoding you may use `setlocale(LC_CTYPE, "ru_RU.cp1251");` (under MS Windows the name of locale may differ – `setlocale(LC_CTYPE, "russian_russia.1251")`). I strongly recommend not to use the constant `LC_ALL` in the conversion. Since it also changes the number format, it may lead to mistakes in formula writing and reading of the text in data files. For example, the program will await a ',' as a decimal point but the user will enter '.'.

How can I exclude a point or a region of plot from the drawing?

There are 3 general ways. First, the point with `NAN` value as one of the coordinates (including color/alpha range) will never be plotted. Second, special functions `SetCutBox()` and `CutOff()` define the condition when the points should be omitted (see Section 4.2.5 [Cutting], page 138). Last, you may change the transparency of a part of the plot by the help of functions [surfa], page 188, [surf3a], page 188 (see Section 4.13 [Dual plotting], page 187). In last case the transparency is switched on smoothly.

I use VisualStudio, CBuilder or some other compiler (not MinGW/gcc). How can I link the MathGL library?

In version 2.0, main classes (`mglGraph` and `mglData`) contains only `inline` functions and are acceptable for any compiler with the same binary files. However, if you plan to use widget classes (QMathGL, Fl_MathGL, ...) or to access low-level features (mglBase, mglCanvas, ...) then you have to recompile MathGL by yours compiler.

Note, that you have to make import library(-ies) *.lib for provided binary *.dll. This procedure depend on used compiler – please read documentation for yours compiler. For VisualStudio, it can be done by command `lib.exe /DEF:libmgl.def /OUT:libmgl.lib`.

How I can build MathGL under Windows?

Generally, it is the same procedure as for Linux or MacOS – see section Section 1.3 [Installation], page 2. The simplest way is using the combination CMake+MinGW. Also you may need some extra libraries like GSL, PNG, JPEG and so on. All of them can be found at `http: / / gnuwin32 . sourceforge.net/packages.html`. After installing all components, just run cmake-gui configurator and build the MathGL itself.

How many people write this library?

Most of the library was written by one person. This is a result of nearly a year of work (mostly in the evening and on holidays): I spent half a year to write the kernel and half a year to a year on extending, improving the library and writing documentation. This process continues now :). The build system (cmake files) was written mostly by D.Kulagin, and the export to PRC/PDF was written mostly by M.Vidassov.

How can I display a bitmap on the figure?

You can import data into a `mglData` instance by function [import], page 224 and display it by [dens], page 179 function. For example, for black-and-white bitmap you can use the code: `mglData bmp; bmp.Import("fname.png","wk"); gr->Dens(bmp,"wk");`.

How can I use MathGL in Qt, FLTK, wxWidgets etc.?

There are special classes (widgets) for these libraries: QMathGL for Qt, Fl_MathGL for FLTK and so on. If you don't find the appropriate class then you can create your own widget that displays a bitmap using mglCanvas::GetRGB().

How can I create 3D in PDF?

Just use `WritePRC()` method which also create PDF file if enable-pdf=ON at MathGL configure.

How can I create TeX figure?

Just use `WriteTEX()` method which create LaTeX files with figure itself '*fname*.tex', with MathGL colors '`mglcolors.tex`' and main file '`mglmain.tex`'. Last one can be used for viewing image by command like `pdflatex mglmain.tex`.

Can I use MathGL in JavaScript?

Yes, sample JavaScript file is located in texinfo/ folder of sources. You should provide JSON data with 3d image for it (can be created by `WriteJSON()` method). Script allows basic manipulation with plot: zoom, rotation, shift. Sample of JavaScript pictures can be found in `http://mathgl.sf.net/json.html`.

How I can change the font family?

First, you should download new font files from here or from here. Next, you should load the font files into mglGraph class instance *gr* by the following command: `gr->LoadFont(fontname,path);`. Here *fontname* is the base font name like '`STIX`' and *path* sets the location of font files. Use `gr->RestoreFont();` to start using the default font.

How can I draw tick out of a bounding box?
Just set a negative value in [ticklen], page 146. For example, use `gr->SetTickLen(-0.1);`.

How can I prevent text rotation?
Just use `SetRotatedText(false)`. Also you can use axis style 'U' for disable only tick labels rotation.

What is `*.so`? What is `gcc`? How I can use `make`?
They are standard GNU tools. There is special FAQ about its usage under Windows – `http://www.mingw.org/wiki/FAQ`.

How can I draw equal axis range even for rectangular image?
Just use `Aspect(NAN,NAN)` for each subplot, or at the beginning of the drawing.

3 General concepts

The set of MathGL features is rather rich – just the number of basic graphics types is larger than 50. Also there are functions for data handling, plot setup and so on. In spite of it I tried to keep a similar style in function names and in the order of arguments. Mostly it is used for different drawing functions.

There are six most general (base) concepts:

1. **Any picture is created in memory first.** The internal (memory) representation can be different: bitmap picture (for `SetQuality(MGL_DRAW_LMEM)`) or the list of vector primitives (default). After that the user may decide what he/she want: save to file, display on the screen, run animation, do additional editing and so on. This approach assures a high portability of the program – the source code will produce exactly the same picture in *any* OS. Another big positive consequence is the ability to create the picture in the console program (using command line, without creating a window)!

2. **Every plot settings (style of lines, font, color scheme) are specified by a string.** It provides convenience for user/programmer – short string with parameters is more comprehensible than a large set of parameters. Also it provides portability – the strings are the same in any OS so that it is not necessary to think about argument types.

3. **All functions have "simplified" and "advanced" forms.** It is done for user's convenience. One needs to specify only one data array in the "simplified" form in order to see the result. But one may set parametric dependence of coordinates and produce rather complex curves and surfaces in the "advanced" form. In both cases the order of function arguments is the same: first data arrays, second the string with style, and later string with options for additional plot tuning.

4. **All data arrays for plotting are encapsulated in mglData(A) class.** This reduces the number of errors while working with memory and provides a uniform interface for data of different types (mreal, double and so on) or for formula plotting.

5. **All plots are vector plots.** The MathGL library is intended for handling scientific data which have vector nature (lines, faces, matrices and so on). As a result, vector representation is used in all cases! In addition, the vector representation allows one to scale the plot easily – change the canvas size by a factor of 2, and the picture will be proportionally scaled.

6. **New drawing never clears things drawn already.** This, in some sense, unexpected, idea allows to create a lot of "combined" graphics. For example, to make a surface with contour lines one needs to call the function for surface plotting and the function for contour lines plotting (in any order). Thus the special functions for making this "combined" plots (as it is done in Matlab and some other plotting systems) are superfluous.

In addition to the general concepts I want to comment on some non-trivial or less commonly used general ideas – plot positioning, axis specification and curvilinear coordinates, styles for lines, text and color scheme.

3.1 Coordinate axes

Two axis representations are used in MathGL. The first one consists of normalizing coordinates of data points in a box *MinxMax* (see). If

`SetCut()` is `true` then the outlier points are omitted, otherwise they are projected to the bounding box (see Section 4.2.5 [Cutting], page 138). Also, the point will be omitted if it lies inside the box defined by `SetCutBox()` or if the value of formula `CutOff()` is nonzero for its coordinates. After that, transformation formulas defined by `SetFunc()` or `SetCoor()` are applied to the data point (see Section 4.3.2 [Curved coordinates], page 143). Finally, the data point is plotted by one of the functions.

The range of *x, y, z*-axis can be specified by `SetRange()` or `SetRanges()` functions. Its origin is specified by `SetOrigin()` function. At this you can you can use `NAN` values for selecting axis origin automatically.

There is 4-th axis *c* (color axis or colorbar) in addition to the usual axes *x, y, z*. It sets the range of values for the surface coloring. Its borders are automatically set to values of Min.z, Max.z during the call of `SetRanges()` function. Also, one can directly set it by call `SetRange('c', ...)`. Use `Colorbar()` function for drawing the colorbar.

The form (appearence) of tick labels is controlled by `SetTicks()` function (see Section 4.3.3 [Ticks], page 144). Function *SetTuneTicks* switches on/off tick enhancing by factoring out acommon multiplier (for small coordinate values, like 0.001 to 0.002, or large, like from 1000 to 2000) or common component (for narrow range, like from 0.999 to 1.000). Finally, you may use functions `SetTickTempl()` for setting templates for tick labels (it supports TeX symbols). Also, there is a possibility to print arbitrary text as tick labels the by help of `SetTicksVal()` function.

3.2 Color styles

Base colors are defined by one of symbol '`wkrgbcymhRGBCYMHWlenupqLENUPQ`'. The color types are: '`k`' – black, '`r`' – red, '`R`' – dark red, '`g`' – green, '`G`' – dark green, '`b`' – blue, '`B`' – dark blue, '`c`' – cyan, '`C`' – dark cyan, '`m`' – magenta, '`M`' – dark magenta, '`y`' – yellow, '`Y`' – dark yellow (gold), '`h`' – gray, '`H`' – dark gray, '`w`' – white, '`W`' – bright gray, '`l`' – green-blue, '`L`' – dark green-blue, '`e`' – green-yellow, '`E`' – dark green-yellow, '`n`' – sky-blue, '`N`' – dark sky-blue, '`u`' – blue-violet, '`U`' – dark blue-violet, '`p`' – purple, '`P`' – dark purple, '`q`' – orange, '`Q`' – dark orange (brown).

You can also use "bright" colors. The "bright" color contain 2 symbols in brackets '`{cN}`': first one is the usual symbol for color id, the second one is a digit for its brightness. The digit can be in range '`1`'...'`9`'. Number '`5`' corresponds to a normal color, '`1`' is a very dark version of the color (practically black), and '`9`' is a very bright version of the color (practically white). For example, the colors can be '`{b2}`' '`{b7}`' '`{r7}`' and so on.

Finally, you can specify RGB or RGBA values of a color using format '`{xRRGGBB}`' or '`{xRRGGBBAA}`' correspondingly. For example, '`{xFF9966}`' give you melone color.

3.3 Line styles

The line style is defined by the string which may contain specifications for color ('`wkrgbcymhRGBCYMHWlenupqLENUPQ`'), dashing style ('`-|;::ji=`' or space), width ('`123456789`') and marks ('`*o+xsd.^v<>`' and '`#`' modifier). If one of the type of information is omitted then default values used with next color from palette (see Section 4.2.7 [Palette and colors], page 140). Note, that internal color counter will be nullified by any change of palette. This includes even hidden change (for example, by `Box()` or `Axis()` functions). By default palette contain following colors: dark gray '`H`', blue

'b', green 'g', red 'r', cyan 'c', magenta 'm', yellow 'y', gray 'h', blue-green 'l', sky-blue 'n', orange 'q', yellow-green 'e', blue-violet 'u', purple 'p'.

Dashing style has the following meaning: space – no line (usable for plotting only marks), '-' – solid line (################), '|' – long dashed line (########--------), ';' – dashed line (####----####----), '=' – small dashed line (##--##--##--##--), ':' – dotted line (#---#---#---#---), 'j' – dash-dotted line (#######----#----), 'i' – small dash-dotted line (###--#--###--#--).

Marker types are: 'o' – circle, '+' – cross, 'x' – skew cross, 's' - square, 'd' - rhomb (or diamond), '.' – dot (point), '^' – triangle up, 'v' – triangle down, '<' – triangle left, '>' – triangle right, '#*' – Y sign, '#+' – squared cross, '#x' – squared skew cross, '#.' – circled dot. If string contain symbol '#' then the solid versions of markers are used.

One may specify to draw a special symbol (an arrow) at the beginning and at the end of line. This is done if the specification string contains one of the following symbols: 'A' – outer arrow, 'V' – inner arrow, 'I' – transverse hatches, 'K' – arrow with hatches, 'T' – triangle, 'S' – square, 'D' – rhombus, 'O' – circle, '_' – nothing (the default). The following rule applies: the first symbol specifies the arrow at the end of line, the second specifies the arrow at the beginning of the line. For example, 'r-A' defines a red solid line with usual arrow at the end, 'b|AI' defines a blue dash line with an arrow at the end and with hatches at the beginning, '_O' defines a line with the current style and with a circle at the beginning. These styles are applicable during the graphics plotting as well (for example, Section 4.10 [1D plotting], page 167).

3.4 Color scheme

The color scheme is used for determining the color of surfaces, isolines, isosurfaces and so on. The color scheme is defined by the string, which may contain several characters that are color id (see Section 3.3 [Line styles], page 127) or characters '#:|'. Symbol '#'

switches to mesh drawing or to a wire plot. Symbol '|' disables color interpolation in color scheme, which can be useful, for example, for sharp colors during matrix plotting. Symbol ':' terminate the color scheme parsing. Following it, the user may put styles for the text, rotation axis for curves/isocontours, and so on. Color scheme may contain up to 32 color values.

The final color is a linear interpolation of color array. The color array is constructed from the string ids (including "bright" colors, see Section 3.2 [Color styles], page 127). The argument is the amplitude normalized between *Cmin* – *Cmax* (see Section 4.3 [Axis settings], page 141). For example, string containing 4 characters '`bcyr`' corresponds to a colorbar from blue (lowest value) through cyan (next value) through yellow (next value) to the red (highest value). String '`kw`' corresponds to a colorbar from black (lowest value) to white (highest value). String '`m`' corresponds to a simple magenta color.

There are several useful combinations. String '`kw`' corresponds to the simplest gray color scheme where higher values are brighter. String '`wk`' presents the inverse gray color scheme where higher value is darker. Strings '`kRryw`', '`kGgw`', '`kBbcw`' present the well-known *hot*, *summer* and *winter* color schemes. Strings '`BbwrR`' and '`bBkRr`' allow to view bi-color figure on white or black background, where negative values are blue and positive values are red. String '`BbcyrR`' gives a color scheme similar to the well-known *jet* color scheme.

For more precise coloring, you can change default (equidistant) position of colors in color scheme. The format is '`{CN,pos}`', '`{CN,pos}`' or '`{xRRGGBB,pos}`'. The position value *pos* should be in range [0, 1]. Note, that alternative method for fine tuning of the color scheme is using the formula for coloring (see Section 4.3.2 [Curved coordinates], page 143).

When coloring by *coordinate* (used in [map], page 189), the final color is determined by the position of the point in 3d space and is calculated from formula c=x*c[1] + y*c[2]. Here, c[1], c[2] are the first two elements of color array; x, y are normalized to axis range coordinates of the point.

3.5 Font styles

Text style is specified by the string which may contain: color id characters
'`wkrgbcymhRGBCYMHW`' (see Section 3.2 [Color styles], page 127), and font style ('`ribwou`')
and/or alignment ('`LRC`') specifications. At this, font style and alignment begin after the
separator '`:`'. For example, '`r:iCb`' sets the bold ('`b`') italic ('`i`') font text aligned at the
center ('`C`') and with red color ('`r`').

The font styles are: '`r`' – roman (or regular) font, '`i`' – italic style, '`b`' – bold style.
By default roman roman font is used. The align types are: '`L`' – align left (default), '`C`' –
align center, '`R`' – align right. Additional font effects are: '`w`' – wired, '`o`' – over-lined, '`u`' –
underlined.

Also a parsing of the LaTeX-like syntax is provided. There are commands for the font
style changing inside the string (for example, use \b for bold font): \a or \overline – over-
lined, \b or \textbf – bold, \i or \textit – italic, \r or \textrm – roman (disable bold and
italic attributes), \u or \underline – underlined, \w or \wire – wired, \big – bigger size, @
– smaller size. The lower and upper indexes are specified by '`_`' and '`^`' symbols. At this the
changed font style is applied only on next symbol or symbols in braces {}. The text in braces
{} are treated as single symbol that allow one to print the index of index. For example,
compare the strings '`sin (x^{2^3})`' and '`sin (x^2^3)`'. You may also change text color
inside string by command #? or by \color? where '?' is symbolic id of the color (see
Section 3.2 [Color styles], page 127). For example, words '`blue`' and '`red`' will be colored
in the string '`#b{blue} and \colorr{red} text`'. The most of functions understand the
newline symbol '`\n`' and allows to print multi-line text. Finally, you can use arbitrary (if
it was defined in font-face) UTF codes by command \utf0x????. For example, \utf0x3b1
will produce α symbol.

The most of commands for special TeX or AMSTeX symbols, the commands for font
style changing (\textrm, \textbf, \textit, \textsc, \overline, \underline), accents (\hat,
\tilde, \dot, \ddot, \acute, \check, \grave, \bar, \breve) and roots (\sqrt, \sqrt3, \sqrt4)
are recognized. The full list contain approximately 2000 commands. Note that first space
symbol after the command is ignored, but second one is printed as normal symbol (space).
For example, the following strings produce the same result $\tilde{a}$: '`\tilde{a}`'; '`\tilde a`';
'`\tilde{}a`'.

In particular, the Greek letters are recognizable special symbols: α – \alpha, β – \beta,
γ – \gamma, δ – \delta, ϵ – \epsilon, η – \eta, ι – \iota, χ – \chi, κ – \kappa, λ – \lambda,
μ – \mu, ν – \nu, o – \o, ω – \omega, ϕ – \phi, π – \pi, ψ – \psi, ρ – \rho, σ – \sigma,
θ – \theta, τ – \tau, υ – \upsilon, ξ – \xi, ζ – \zeta, ς – \varsigma, ε – \varepsilon, ϑ –
\vartheta, φ – \varphi, A – \Alpha, B – \Beta, Γ – \Gamma, Δ – \Delta, E – \Epsilon,
H – \Eta, I – \Iota, C – \Chi, K – \Kappa, Λ – \Lambda, M – \Mu, N – \Nu, O – \O, Ω
– \Omega, Φ – \Phi, Π – \Pi, Ψ – \Psi, R – \Rho, Σ – \Sigma, Θ – \Theta, T – \Tau, Υ
– \Upsilon, Ξ – \Xi, Z – \Zeta.

The small part of most common special TeX symbols are: $\angle$ – \angle, $\aleph$ – \aleph, $\cdot$ –
\cdot, $\clubsuit$ – \clubsuit, $\cup$ – \cup, $\cap$ – \cap, $\diamondsuit$ – \diamondsuit, $\diamond$ – \diamond, $\div$ – \div, $\downarrow$ –
\downarrow, $\dag$ – \dag, $\ddag$ – \ddag, $\equiv$ – \equiv, $\exists$ – \exists, $\frown$ – \frown, $\flat$ – \flat, $\ge$ – \ge,
$\geq$ – \geq, $\gets$ – \gets, $\heartsuit$ – \heartsuit, ∞ – \infty, $\in$ – \in, $\int$ – \int, $\Im$ – \Im, $\langle$ – \langle, $\le$
– \le, $\leq$ – \leq, $\leftarrow$ – \leftarrow, $\mp$ – \mp, ∇ – \nabla, $\neq$ – \ne, $\neq$ – \neq, $\natural$ – \natural, $\oint$ –
\oint, $\odot$ – \odot, $\oplus$ – \oplus, ∂ – \partial, $\parallel$ – \parallel, $\perp$ – \perp, $\pm$ – \pm, $\propto$ – \propto,

$\prod$ – \prod, $\Re$ – \Re, $\rightarrow$ – \rightarrow, $\rangle$ – \rangle, ♠ – \spadesuit, $\sim$ – \sim, $\smile$ – \smile, $\subset$ – \subset, $\supset$ – \supset, $\surd$ – \sqrt or \surd, § – \S, $\sharp$ – \sharp, $\sum$ – \sum, $\times$ – \times, $\rightarrow$ – \to, $\uparrow$ – \uparrow, $\wp$ – \wp and so on.

The font size can be defined explicitly (if *size*>0) or relatively to a base font size as |*size*|*FontSize (if *size*<0). The value *size*=0 specifies that the string will not be printed. The base font size is measured in internal "MathGL" units. Special functions `SetFontSizePT()`, `SetFontSizeCM()`, `SetFontSizeIN()` (see Section 4.2.6 [Font settings], page 139) allow one to set it in more "common" variables for a given dpi value of the picture.

3.6 Textual formulas

MathGL have the fast variant of textual formula evaluation (see Section 6.12 [Evaluate expression], page 239) . There are a lot of functions and operators available. The operators are: '+' – addition, '−' – subtraction, '*' – multiplication, '/' – division, '^' – integer power. Also there are logical "operators": '<' – true if x<y, '>' – true if x>y, '=' – true if x=y, '&' – true if x and y both nonzero, '|' – true if x or y nonzero. These logical operators have lowest priority and return 1 if true or 0 if false.

The basic functions are: '`sqrt(x)`' – square root of x, '`pow(x,y)`' – power x in y, '`ln(x)`' – natural logarithm of x, '`lg(x)`' – decimal logarithm of x, '`log(a,x)`' – logarithm base a of x, '`abs(x)`' – absolute value of x, '`sign(x)`' – sign of x, '`mod(x,y)`' – x modulo y, '`step(x)`' – step function, '`int(x)`' – integer part of x, '`rnd`' – random number, '`pi`' – number $\pi = 3.1415926...$

Trigonometric functions are: '`sin(x)`', '`cos(x)`', '`tan(x)`' (or '`tg(x)`'). Inverse trigonometric functions are: '`asin(x)`', '`acos(x)`', '`atan(x)`'. Hyperbolic functions are: '`sinh(x)`' (or '`sh(x)`'), '`cosh(x)`' (or '`ch(x)`'), '`tanh(x)`' (or '`th(x)`'). Inverse hyperbolic functions are: '`asinh(x)`', '`acosh(x)`', '`atanh(x)`'.

There are a set of special functions: '`gamma(x)`' – Gamma function $\Gamma(x) = \int_0^\infty dt\, t^{\{x-1\}}\exp(-t)$, '`psi(x)`' – digamma function $\psi(x) = \Gamma'(x)/\Gamma(x)$ for x!=0, '`ai(x)`' – Airy function Ai(x), '`bi(x)`' – Airy function Bi(x), '`cl(x)`' – Clausen function, '`li2(x)`' (or '`dilog(x)`') – dilogarithm $Li_2(x) = -\Re\int_0^x ds\,\log(1-s)/s$, '`sinc(x)`' – compute $sinc(x) = \sin(\pi x)/(\pi x)$ for any value of x, '`zeta(x)`' – Riemann zeta function $\zeta(s) = \sum_\{k = 1\}^\infty k^{\{-s\}}$ for arbitrary s!=1, '`eta(x)`' – eta function $\eta(s) = (1 - 2^{\{1-s\}})\zeta(s)$ for arbitrary s, '`lp(l,x)`' – Legendre polynomial $P_l(x)$, (|x|<=1, l>=0), '`w0(x)`', '`w1(x)`' – principal branch of the Lambert W functions. Function W(x) is defined to be solution of the equation $W\exp(W) = x$.

The exponent integrals are: '`ci(x)`' – Cosine integral $Ci(x) = \int_0^x dt\,\cos(t)/t$, '`si(x)`' – Sine integral $Si(x) = \int_0^x dt\,\sin(t)/t$, '`erf(x)`' – error function $erf(x) = (2/\sqrt(\pi))\int_0^x dt\,\exp(-t^2)$, '`ei(x)`' – exponential integral $Ei(x) := -PV(\int_\{-x\}^\infty dt\,\exp(-t)/t)$ (where PV denotes the principal value of the integral), '`e1(x)`' – exponential integral $E_1(x) := Re\int_1^\infty dt\,\exp(-xt)/t$, '`e2(x)`' – exponential integral $E_2(x) := Re\int_1^\infty dt\,\exp(-xt)/t^2$, '`ei3(x)`' – exponential integral $Ei_3(x) = \int_0^x dt\,\exp(-t^3)$ for x>=0.

Bessel functions are: '`j(nu,x)`' – regular cylindrical Bessel function of fractional order *nu*, '`y(nu,x)`' – irregular cylindrical Bessel function of fractional order *nu*, '`i(nu,x)`' – regular modified Bessel function of fractional order *nu*, '`k(nu,x)`' – irregular modified Bessel function of fractional order *nu*.

Elliptic integrals are: '`ee(k)`' – complete elliptic integral is denoted by $E(k) = E(\pi/2, k)$, '`ek(k)`' – complete elliptic integral is denoted by $K(k) = F(\pi/2, k)$, '`e(phi,k)`' – elliptic integral $E(\phi, k) = \int_0^\phi dt \sqrt{((1 - k^2 \sin^2(t)))}$, '`f(phi,k)`' – elliptic integral $F(\phi, k) = \int_0^\phi dt 1/\sqrt{((1 - k^2 \sin^2(t)))}$.

Jacobi elliptic functions are: '`sn(u,m)`', '`cn(u,m)`', '`dn(u,m)`', '`sc(u,m)`', '`sd(u,m)`', '`ns(u,m)`', '`cs(u,m)`', '`cd(u,m)`', '`nc(u,m)`', '`ds(u,m)`', '`dc(u,m)`', '`nd(u,m)`'.

Note, some of these functions are unavailable if MathGL was compiled without GSL support.

There is no difference between lower or upper case in formulas. If argument value lie outside the range of function definition then function returns NaN.

3.7 Command options

Command options allow the easy setup of the selected plot by changing global settings only for this plot. Each option start from symbol ';'. Options work so that MathGL remember the current settings, change settings as it being set in the option, execute function and return the original settings back. So, the options are most usable for plotting functions.

The most useful options are `xrange`, `yrange`, `zrange`. They sets the boundaries for data change. This boundaries are used for automatically filled variables. So, these options allow one to change the position of some plots. For example, in command `Plot(y,"","xrange 0.1 0.9");` or `plot y; xrange 0.1 0.9` the x coordinate will be equidistantly distributed in range 0.1 ... 0.9. See Section 2.9.14 [Using options], page 119, for sample code and picture.

The full list of options are:

`alpha val`   [MGL option]
> Sets alpha value (transparency) of the plot. The value should be in range [0, 1]. See also [alphadef], page 136.

`xrange val1 val2`   [MGL option]
> Sets boundaries of x coordinate change for the plot. See also [xrange], page 142.

`yrange val1 val2`   [MGL option]
> Sets boundaries of y coordinate change for the plot. See also [yrange], page 142.

`zrange val1 val2`   [MGL option]
> Sets boundaries of z coordinate change for the plot. See also [zrange], page 142.

`cut val`   [MGL option]
> Sets whether to cut or to project the plot points lying outside the bounding box. See also [cut], page 138.

`size val`   [MGL option]
> Sets the size of text, marks and arrows. See also [font], page 139, [marksize], page 137, [arrowsize], page 138.

`meshnum val`   [MGL option]
> Work like [meshnum], page 138 command.

`legend` *'txt'*   [MGL option]
>   Adds string 'txt' to internal legend accumulator. The style of described line and mark
>   is taken from arguments of the last Section 4.10 [1D plotting], page 167 command.
>   See also [legend], page 166.

`value val`   [MGL option]
>   Set the value to be used as additional numeric parameter in plotting command.

3.8 Interfaces

The MathGL library has interfaces for a set of languages. Most of them are based on the C
interface via SWIG tool. There are Python, Java, Octave, Lisp, C#, Guile, Lua, Modula 3,
Ocaml, Perl, PHP, Pike, R, Ruby, and Tcl interfaces. Also there is a Fortran interface which
has a similar set of functions, but slightly different types of arguments (integers instead of
pointers). These functions are marked as [C function].

   Some of the languages listed above support classes (like C++ or Python). The name
of functions for them is the same as in C++ (see Chapter 4 [MathGL core], page 135 and
Chapter 6 [Data processing], page 214) and marked like [Method on mglGraph].

   Finally, a special command language MGL (see Chapter 7 [MGL scripts], page 241) was
written for a faster access to plotting functions. Corresponding scripts can be executed
separately (by UDAV, mglconv, mglview and so on) or from the C/C++/Python/... code
(see Section 7.3 [mglParse class], page 244).

3.8.1 C/Fortran interface

The C interface is a base for many other interfaces. It contains the pure C functions for most
of the methods of MathGL classes. In distinction to C++ classes, C functions must have an
argument HMGL (for graphics) and/or HMDT (for data arrays), which specifies the object
for drawing or manipulating (changing). So, firstly, the user has to create this object by the
function `mgl_create_*()` and has to delete it after the use by function `mgl_delete_*()`.

   All C functions are described in the header file `#include <mgl2/mgl_cf.h>` and use
variables of the following types:

- `HMGL` — Pointer to class `mglGraph` (see Chapter 4 [MathGL core], page 135).
- `HMDT` — Pointer to class `mglData` (see Chapter 6 [Data processing], page 214).
- `HMPR` — Pointer to class `mglParse` (see Section 7.3 [mglParse class], page 244).

   These variables contain identifiers for graphics drawing objects and for the data objects.

   Fortran functions/subroutines have the same names as C functions. However, there is a
difference. Variable of type `HMGL, HMDT` must be an integer with sufficient size (`integer*4`
in the 32-bit operating system or `integer*8` in the 64-bit operating system). All C functions
are subroutines in Fortran, which are called by operator `call`. The exceptions are functions,
which return variables of types `HMGL` or `HMDT`. These functions should be declared as integer
in Fortran code. Also, one should keep in mind that strings in Fortran are denoted by '
symbol, not the " symbol.

3.8.2 C++/Python interface

MathGL provides the interface to a set of languages via SWIG library. Some of these
languages support classes. The typical example is Python – which is named in this chapter's

title. Exactly the same classes are used for high-level C++ API. Its feature is using only inline member-functions what make high-level API to be independent on compiler even for binary build.

There are 3 classes in:

- `mglGraph` – provide most plotting functions (see Chapter 4 [MathGL core], page 135).
- `mglData` – provide base data processing (see Chapter 6 [Data processing], page 214). It have an additional feature to access data values. You can use a construct like this: `dat[i]=sth;` or `sth=dat[i]` where flat representation of data is used (i.e., *i* can be in range 0...nx*nx*nz-1). You can also import NumPy arrays as input arguments in Python: `mgl_dat = mglData(numpy_dat);`.
- `mglParse` – provide functions for parsing MGL scripts (see Chapter 7 [MGL scripts], page 241).

To use Python classes just execute '`import mathgl`'. The simplest example will be:

```
import mathgl
a=mathgl.mglGraph()
a.Box()
a.WritePNG("test.png")
```

Alternatively you can import all classes from `mathgl` module and easily access MathGL classes like this:

```
from mathgl import *
a=mglGraph()
a.Box()
a.WritePNG("test.png")
```

This becomes useful if you create many `mglData` objects, for example.

4 MathGL core

The core of MathGL is **mglGraph** class defined in `#include <mgl2/mgl.h>`. It contains a lot of plotting functions for 1D, 2D and 3D data. It also encapsulates parameters for axes drawing. Moreover an arbitrary coordinate transformation can be used for each axis. All plotting functions use data encapsulated in mglData class (see Chapter 6 [Data processing], page 214) that allows to check sizes of used arrays easily. Also it have many functions for data handling: modify it by formulas, find momentums and distribution (histogram), apply operator (differentiate, integrate, transpose, Fourier and so on), change data sizes (interpolate, squeeze, crop and so on). Additional information about colors, fonts, formula parsing can be found in Chapter 3 [General concepts], page 126 and Chapter 9 [Other classes], page 255.

4.1 Create and delete objects

`mglGraph (int` *kind*`=0, int` *width*`=600, int`   [Constructor on `mglGraph`]
        height`=400)`
`mglGraph (const mglGraph &`*gr*`)`   [Constructor on `mglGraph`]
`mglGraph (HMGL` *gr*`)`   [Constructor on `mglGraph`]
`HMGL mgl_create_graph (int` *width*`, int` *height*`)`   [C function]
`HMGL mgl_create_graph_gl ()`   [C function]
    Creates the instance of class mglGraph with specified sizes *width* and *height*. Parameter *kind* may have following values: '`0`' – use default plotter, '`1`' – use OpenGL plotter.

`~mglGraph ()`   [Destructor on `mglGraph`]
`HMGL mgl_delete_graph (HMGL` *gr*`)`   [C function]
    Deletes the instance of class mglGraph.

`HMGL Self ()`   [Method on `mglGraph`]
    Returns the pointer to internal object of type `HMGL`.

4.2 Graphics setup

Functions and variables in this group influences on overall graphics appearance. So all of them should be placed *before* any actual plotting function calls.

`void DefaultPlotParam ()`   [Method on `mglGraph`]
`void mgl_set_def_param (HMGL` *gr*`)`   [C function]
    Restore initial values for all of parameters.

4.2.1 Transparency

There are several functions and variables for setup transparency. The general function is [alpha], page 135 which switch on/off the transparency for overall plot. It influence only for graphics which created after [alpha], page 135 call (with one exception, OpenGL). Function [alphadef], page 136 specify the default value of alpha-channel. Finally, function [transptype], page 136 set the kind of transparency. See Section 2.9.2 [Transparency and lighting], page 101, for sample code and picture.

alpha [val=on]   [MGL command]
void Alpha (bool *enable*)   [Method on `mglGraph`]
void mgl_set_alpha (HMGL *gr*, int *enable*)   [C function]
>   Sets the transparency on/off and returns previous value of transparency. It is recom-
>   mended to call this function before any plotting command. Default value is trans-
>   parency off.

alphadef val   [MGL command]
void SetAlphaDef (mreal *val*)   [Method on `mglGraph`]
void mgl_set_alpha_default (HMGL *gr*, mreal *alpha*)   [C function]
>   Sets default value of alpha channel (transparency) for all plotting functions. Initial
>   value is 0.5.

transptype val   [MGL command]
void SetTranspType (int *type*)   [Method on `mglGraph`]
void mgl_set_transp_type (HMGL *gr*, int *type*)   [C function]
>   Set the type of transparency. Possible values are:
>
>   - Normal transparency ('0') – below things is less visible than upper ones. It does
>   not look well in OpenGL mode (mglGraphGL) for several surfaces.
>   - Glass-like transparency ('1') – below and upper things are commutable and just
>   decrease intensity of light by RGB channel.
>   - Lamp-like transparency ('2') – below and upper things are commutable and are
>   the source of some additional light. I recommend to set `SetAlphaDef(0.3)` or
>   less for lamp-like transparency.
>
>   See Section 2.9.3 [Types of transparency], page 102, for sample code and picture..

4.2.2 Lighting

There are several functions for setup lighting. The general function is [light], page 136 which
switch on/off the lighting for overall plot. It influence only for graphics which created after
[light], page 136 call (with one exception, OpenGL). Generally MathGL support up to
10 independent light sources. But in OpenGL mode only 8 of light sources is used due
to OpenGL limitations. The position, color, brightness of each light source can be set
separately. By default only one light source is active. It is source number 0 with white
color, located at top of the plot.

light [val=on]   [MGL command]
bool Light (bool *enable*)   [Method on `mglGraph`]
void mgl_set_light (HMGL *gr*, int *enable*)   [C function]
>   Sets the using of light on/off for overall plot. Function returns previous value of
>   lighting. Default value is lightning off.

light num val   [MGL command]
void Light (int *n*, bool *enable*)   [Method on `mglGraph`]
void mgl_set_light_n (HMGL *gr*, int *n*, int *enable*)   [C function]
>   Switch on/off *n*-th light source separately.

light num xdir ydir zdir ['col'='w' br=0.5]   [MGL command]
light num xdir ydir zdir xpos ypos zpos ['col'='w' br=0.5]   [MGL command]

`void AddLight (int n, mglPoint d, char c='w', mreal`   [Method on `mglGraph`]
        `bright=0.5, mreal ap=0)`
`void AddLight (int n, mglPoint r, mglPoint d, char`   [Method on `mglGraph`]
        `c='w', mreal bright=0.5, mreal ap=0)`
`void mgl_add_light (HMGL gr, int n, mreal dx, mreal dy, mreal dz)`   [C function]
`void mgl_add_light_ext (HMGL gr, int n, mreal dx, mreal dy,`   [C function]
        `mreal dz, char c, mreal bright, mreal ap)`
`void mgl_add_light_loc (HMGL gr, int n, mreal rx, mreal ry,`   [C function]
        `mreal rz, mreal dx, mreal dy, mreal dz, char c, mreal bright, mreal ap)`
    The function adds a light source with identification n in direction d with color c and with brightness *bright* (which must be in range [0,1]). If position r is specified and isn't NAN then light source is supposed to be local otherwise light source is supposed to be placed at infinity.

`void SetDifLight (bool enable)`   [Method on `mglGraph`]
`void mgl_set_light_dif (HMGL gr, int enable)`   [C function]
    Set on/off to use diffusive light (only for local light sources).

`ambient val`   [MGL command]
`void SetAmbient (mreal bright=0.5)`   [Method on `mglGraph`]
`void mgl_set_ambbr (HMGL gr, mreal bright)`   [C function]
    Sets the brightness of ambient light. The value should be in range [0,1].

4.2.3 Fog

`fog val [dz=0.25]`   [MGL command]
`void Fog (mreal d, mreal dz=0.25)`   [Method on `mglGraph`]
`void mgl_set_fog (HMGL gr, mreal d, mreal dz)`   [C function]
    Function imitate a fog in the plot. Fog start from relative distance dz from view point and its density growths exponentially in depth. So that the fog influence is determined by law ~ 1-exp(-d*z). Here z is normalized to 1 depth of the plot. If value d=0 then the fog is absent. Note, that fog was applied at stage of image creation, not at stage of drawing. See Section 2.9.5 [Adding fog], page 105, for sample code and picture.

4.2.4 Default sizes

These variables control the default (initial) values for most graphics parameters including sizes of markers, arrows, line width and so on. As any other settings these ones will influence only on plots created after the settings change.

`barwidth val`   [MGL command]
`void SetBarWidth ( mreal val)`   [Method on `mglGraph`]
`void mgl_set_bar_width (HMGL gr, mreal val)`   [C function]
    Sets relative width of rectangles in [bars], page 170, [barh], page 170, [boxplot], page 172, [candle], page 172. Default value is `0.7`.

`marksize val`   [MGL command]
`void SetMarkSize (mreal val)`   [Method on `mglGraph`]
`void mgl_set_mark_size (HMGL gr, mreal val)`   [C function]
    Sets size of marks for Section 4.10 [1D plotting], page 167. Default value is `1`.

```
arrowsize val                                                        [MGL command]
void SetArrowSize (mreal val)                                    [Method on mglGraph]
void mgl_set_arrow_size (HMGL gr, mreal val)                          [C function]
```
> Sets size of arrows for Section 4.10 [1D plotting], page 167, lines and curves (see
> Section 4.6 [Primitives], page 158). Default value is 1.

```
meshnum val                                                          [MGL command]
void SetMeshNum (int val)                                        [Method on mglGraph]
void mgl_set_meshnum (HMGL gr, int num)                              [C function]
```
> Sets approximate number of lines in [mesh], page 177, [fall], page 177, [grid], page 164
> and also the number of hachures in [vect], page 191, [dew], page 192 and the number
> of cells in [cloud], page 184. By default (=0) it draws all lines/hachures/cells.

```
facenum val                                                          [MGL command]
void SetFaceNum (int val)                                        [Method on mglGraph]
void mgl_set_facenum (HMGL gr, int num)                              [C function]
```
> Sets approximate number of visible faces. Can be used for speeding up drawing by
> cost of lower quality. By default (=0) it draws all of them.

```
plotid 'id'                                                          [MGL command]
void SetPlotId (const char *id)                                  [Method on mglGraph]
void mgl_set_plotid (HMGL gr, const char *id)                        [C function]
```
> Sets default name id as filename for saving (in FLTK window for example).

```
const char * GetPlotId ()                                        [Method on mglGraph]
const char * mgl_get_plotid (HMGL gr)                                [C function]
```
> Gets default name id as filename for saving (in FLTK window for example).

4.2.5 Cutting

These variables and functions set the condition when the points are excluded (cutted) from
the drawing. Note, that a point with NAN value(s) of coordinate or amplitude will be
automatically excluded from the drawing. See Section 2.2.9 [Cutting sample], page 32, for
sample code and picture.

```
cut val                                                              [MGL command]
void SetCut (bool val)                                           [Method on mglGraph]
void mgl_set_cut (HMGL gr, int val)                                  [C function]
```
> Flag which determines how points outside bounding box are drawn. If it is true then
> points are excluded from plot (it is default) otherwise the points are projected to
> edges of bounding box.

```
cut x1 y1 z1 x2 y2 z2                                                [MGL command]
void SetCutBox (mglPoint p1, mglPoint p1)                        [Method on mglGraph]
void mgl_set_cut_box (HMGL gr, mreal x1, mreal y1, mreal z1,          [C function]
        mreal x2, mreal y2, mreal z2)
```
> Lower and upper edge of the box in which never points are drawn. If both edges are
> the same (the variables are equal) then the cutting box is empty.

cut *'cond'*   [MGL command]
void CutOff (const char *cond)   [Method on mglGraph]
void mgl_set_cutoff (HMGL gr, const char *cond)   [C function]
> Sets the cutting off condition by formula *cond*. This condition determine will point
> be plotted or not. If value of formula is nonzero then point is omitted, otherwise it
> plotted. Set argument as "" to disable cutting off condition.

4.2.6 Font settings

font *'fnt'* [val=6]   [MGL command]
> Font style for text and labels (see text). Initial style is 'fnt'=':rC' give Roman font
> with centering. Parameter val sets the size of font for tick and axis labels. Default
> font size of axis labels is 1.4 times large than for tick labels. For more detail, see
> Section 3.5 [Font styles], page 130.

rotatetext val   [MGL command]
void SetRotatedText (bool val)   [Method on mglGraph]
void mgl_set_rotated_text (HMGL gr, int val)   [C function]
> Sets to use or not text rotation.

loadfont [*'name'=*"]   [MGL command]
void LoadFont (const char *name, const char   [Method on mglGraph]
       *path="")
void mgl_load_font (HMGL gr, const char *name, const char   [C function]
       *path)
> Load font typeface from *path/name*. Empty name will load default font.

void SetFontDef (const char *fnt)   [Method on mglGraph]
void mgl_set_font_def (HMGL gr, const char * val)   [C function]
> Sets the font specification (see Section 4.7 [Text printing], page 161). Default is 'rC'
> – Roman font centering.

void SetFontSize (mreal val)   [Method on mglGraph]
void mgl_set_font_size (HMGL gr, mreal val)   [C function]
> Sets the size of font for tick and axis labels. Default font size of axis labels is 1.4
> times large than for tick labels.

void SetFontSizePT (mreal cm, int dpi=72)   [Method on mglGraph]
> Set FontSize by size in pt and picture DPI (default is 16 pt for dpi=72).

inline void SetFontSizeCM (mreal cm, int dpi=72)   [Method on mglGraph]
> Set FontSize by size in centimeters and picture DPI (default is 0.56 cm = 16 pt).

inline void SetFontSizeIN (mreal cm, int dpi=72)   [Method on mglGraph]
> Set FontSize by size in inch and picture DPI (default is 0.22 in = 16 pt).

void LoadFont (const char *name, const char   [Method on mglGraph]
       *path="")
void mgl_load_font (HMGL gr, const char *name, const char   [C function]
       *path)
> Load font typeface from *path/name*.

void CopyFont (mglGraph * *from*)   [Method on mglGraph]
void mgl_copy_font (HMGL *gr*, HMGL *gr_from*)   [C function]
    Copy font data from another mglGraph object.

void RestoreFont ()   [Method on mglGraph]
void mgl_restore_font (HMGL *gr*)   [C function]
    Restore font data to default typeface.

void mgl_def_font (const char **name, const char **path)   [ ]
    Load default font typeface (for all newly created HMGL/mglGraph objects) from
    path/*name*.

4.2.7 Palette and colors

palette *'colors'*   [MGL command]
void SetPalette (const char **colors)   [Method on mglGraph]
void mgl_set_palette (HMGL *gr*, const char **colors)   [C function]
    Sets the palette as selected colors. Default value is "Hbgrcmyhlnqeup" that corre-
    sponds to colors: dark gray 'H', blue 'b', green 'g', red 'r', cyan 'c', magenta 'm', yellow
    'y', gray 'h', blue-green 'l', sky-blue 'n', orange 'q', yellow-green 'e', blue-violet 'u',
    purple 'p'. The palette is used mostly in 1D plots (see Section 4.10 [1D plotting],
    page 167) for curves which styles are not specified. Internal color counter will be
    nullified by any change of palette. This includes even hidden change (for example, by
    [box], page 165 or [axis], page 163 functions).

void SetDefScheme (const char **sch)   [Method on mglGraph]
void mgl_set_def_sch (HMGL *gr*, const char **sch)   [C function]
    Sets the *sch* as default color scheme. Default value is "BbcyrR".

void mgl_set_color (char *id*, mreal *r*, mreal *g*, mreal *b*)   [C function]
    Sets RGB values for color with given *id*.

4.2.8 Error handling

Normally user should set it to zero by SetWarn(0); before plotting and check if
GetWarnCode() or Message() return non zero after plotting. Only last warning will be
saved. All warnings/errors produced by MathGL is not critical – the plot just will not be
drawn.

void SetWarn (int *code*, const char **info="")   [Method on mglGraph]
void mgl_set_warn (HMGL *gr*, int *code*, const char **info)   [C function]
    Set warning code. Normally you should call this function only for clearing the warning
    state, i.e. call SetWarn(0);. Text *info* will be printed as is if *code*<0.

const char *Message ()   [Method on mglGraph]
const char *mgl_get_mess (HMGL *gr*)   [C function]
    Return messages about matters why some plot are not drawn. If returned string is
    empty then there are no messages.

int GetWarnCode ()   [Method on `mglGraph`]
int mgl_get_warn_code (HMGL *gr*)   [C function]
    Return the numerical ID of warning about the not drawn plot. Possible values are:

mglWarnNone=0
        Everything OK

mglWarnDim
        Data dimension(s) is incompatible

mglWarnLow
        Data dimension(s) is too small

mglWarnNeg
        Minimal data value is negative

mglWarnFile
        No file or wrong data dimensions

mglWarnMem
        Not enough memory

mglWarnZero
        Data values are zero

mglWarnLegA
        Too many legend entries

mglWarnLeg
        No legend entries

mglWarnSlc
        Slice value is out of range

mglWarnCnt
        Number of contours is zero or negative

mglWarnOpen
        Couldn't open file

mglWarnLId
        Light: ID is out of range

mglWarnSize
        Setsize: size(s) is zero or negative

mglWarnFmt
        Format is not supported for that build

4.3 Axis settings

These large set of variables and functions control how the axis and ticks will be drawn. Note that there is 3-step transformation of data coordinates are performed. Firstly, coordinates are projected if Cut=true (see Section 4.2.5 [Cutting], page 138), after it transformation formulas are applied, and finally the data was normalized in bounding box.

4.3.1 Ranges (bounding box)

xrange v1 v2   [MGL command]
yrange v1 v2   [MGL command]
zrange v1 v2   [MGL command]
crange v1 v2   [MGL command]
void SetRange (char *dir*, mreal *v1*, mreal *v2*)   [Method on `mglGraph`]
void mgl_set_range_val (HMGL *gr*, char *dir*, mreal *v1*, mreal *v2*)   [C function]
    Sets the range for 'x'-,'y'-,'z'- coordinate or coloring ('c'). See also [ranges], page 142.

xrange *dat* [add=off]   [MGL command]
yrange *dat* [add=off]   [MGL command]
zrange *dat* [add=off]   [MGL command]
crange *dat* [add=off]   [MGL command]
void SetRange (char *dir*, const mglDataA &*dat*, bool   [Method on `mglGraph`]
     add=false)
void mgl_set_range_dat (HMGL *gr*, char *dir*, const HCDT *a*, int   [C function]
     add)
    Sets the range for 'x'-,'y'-,'z'- coordinate or coloring ('c') as minimal and maximal
    values of data *dat*. Parameter `add=on` shows that the new range will be joined to
    existed one (not replace it).

ranges x1 x2 y1 y2 [z1=0 z2=0]   [MGL command]
void SetRanges (mglPoint *p1*, mglPoint *p2*)   [Method on `mglGraph`]
void SetRanges (double *x1*, double *x2*, double *y1*,   [Method on `mglGraph`]
     double *y2*, double *z1*=0, double *z2*=0)
void mgl_set_ranges (HMGL *gr*, double *x1*, double *x2*, double *y1*,   [C function]
     double *y2*, double *z1*, double *z2*)
    Sets the ranges of coordinates. If minimal and maximal values of the coordinate are
    the same then they are ignored. Also it sets the range for coloring (analogous to
    `crange z1 z2`). This is default color range for 2d plots. Initial ranges are [-1, 1].

void SetRanges (const mglDataA &*xx*, const mglDataA   [Method on `mglGraph`]
     &*yy*)
void SetRanges (const mglDataA &*xx*, const mglDataA   [Method on `mglGraph`]
     &*yy*, const mglDataA &*zz*)
void SetRanges (const mglDataA &*xx*, const mglDataA   [Method on `mglGraph`]
     &*yy*, const mglDataA &*zz*, const mglDataA &*cc*)
    Sets the ranges of 'x'-,'y'-,'z'-coordinates and coloring as minimal and maximal values
    of data *xx*, *yy*, *zz*, *cc* correspondingly.

void SetAutoRanges (mglPoint *p1*, mglPoint *p2*)   [Method on `mglGraph`]
void SetAutoRanges (double *x1*, double *x2*, double *y1*,   [Method on `mglGraph`]
     double *y2*, double *z1*=0, double *z2*=0, double *c1*=0, double *c2*=0)
void mgl_set_auto_ranges (HMGL *gr*, double *x1*, double *x2*,   [C function]
     double *y1*, double *y2*, double *z1*, double *z2*, double *z1*, double *z2*)
    Sets the ranges for automatic coordinates. If minimal and maximal values of the
    coordinate are the same then they are ignored.

```
origin x0 y0 [z0=nan]                                          [MGL command]
void SetOrigin (mglPoint p0)                            [Method on mglGraph]
void SetOrigin (mreal x0, mreal y0, mreal z0=NAN)       [Method on mglGraph]
void mgl_set_origin (HMGL gr, mreal x0, mreal y0, mreal z0)     [C function]
```
Sets center of axis cross section. If one of values is NAN then MathGL try to select optimal axis position.

```
zoomaxis x1 x2                                                 [MGL command]
zoomaxis x1 y1 x2 y2                                           [MGL command]
zoomaxis x1 y1 z1 x2 y2 z2                                     [MGL command]
zoomaxis x1 y1 z1 c1 x2 y2 z2 c2                               [MGL command]
void ZoomAxis (mglPoint p1, mglPoint p2)                [Method on mglGraph]
void mgl_zoom_axis (HMGL gr, mreal x1, mreal y1, mreal z1, mreal   [C function]
      c1, mreal x2, mreal y2, mreal z2, mreal c2)
```
Additionally extend axis range for any settings made by `SetRange` or `SetRanges` functions according the formula $min+ = (max - min) * p1$ and $max+ = (max - min) * p1$ (or $min* = (max/min)^p1$ and $max* = (max/min)^p1$ for log-axis range when $inf > max/min > 100$ or $0 < max/min < 0.01$). Initial ranges are $[0, 1]$. Attention! this settings can not be overwritten by any other functions, including `DefaultPlotParam()`.

4.3.2 Curved coordinates

```
axis 'fx' 'fy' 'fz' ['fa'=""]                                 [MGL command]
void SetFunc (const char *EqX, const char *EqY,         [Method on mglGraph]
      const char *EqZ="", const char *EqA="")
void mgl_set_func (HMGL gr, const char *EqX, const char *EqY,   [C function]
      const char *EqZ, const char *EqA)
```
Sets transformation formulas for curvilinear coordinate. Each string should contain mathematical expression for real coordinate depending on internal coordinates 'x', 'y', 'z' and 'a' or 'c' for colorbar. For example, the cylindrical coordinates are introduced as `SetFunc("x*cos(y)", "x*sin(y)", "z");`. For removing of formulas the corresponding parameter should be empty or `NULL`. Using transformation formulas will slightly slowing the program. Parameter *EqA* set the similar transformation formula for color scheme. See Section 3.6 [Textual formulas], page 131.

```
axis how                                                      [MGL command]
void SetCoor (int how)                                  [Method on mglGraph]
void mgl_set_coor (HMGL gr, int how)                           [C function]
```
Sets one of the predefined transformation formulas for curvilinear coordinate. Paramater *how* define the coordinates: `mglCartesian=0` – Cartesian coordinates (no transformation); `mglPolar=1` – Polar coordinates $x_n = x * cos(y), y_n = x * sin(y), z_n = z$; `mglSpherical=2` – Sperical coordinates $x_n = x * sin(y) * cos(z), y_n = x * sin(y) * sin(z), z_n = x * cos(y)$; `mglParabolic=3` – Parabolic coordinates $x_n = x * y, y_n = (x * x - y * y)/2, z_n = z$; `mglParaboloidal=4` – Paraboloidal coordinates $x_n = (x * x - y * y) * cos(z)/2, y_n = (x * x - y * y) * sin(z)/2, z_n = x * y$; `mglOblate=5` – Oblate coordinates $x_n = cosh(x) * cos(y) * cos(z), y_n = cosh(x) * cos(y) * sin(z), z_n = sinh(x) * sin(y)$;

`mglProlate=6` – Prolate coordinates $x_n = sinh(x) * sin(y) * cos(z), y_n = sinh(x) * sin(y) * sin(z), z_n = cosh(x) * cos(y)$; `mglElliptic=7` – Elliptic coordinates $x_n = cosh(x) * cos(y), y_n = sinh(x) * sin(y), z_n = z$; `mglToroidal=8` – Toroidal coordinates $x_n = sinh(x)*cos(z)/(cosh(x)-cos(y)), y_n = sinh(x)*sin(z)/(cosh(x)-cos(y)), z_n = sin(y)/(cosh(x)-cos(y))$; `mglBispherical=9` – Bispherical coordinates $x_n = sin(y)*cos(z)/(cosh(x)-cos(y)), y_n = sin(y)*sin(z)/(cosh(x)-cos(y)), z_n = sinh(x)/(cosh(x) - cos(y))$; `mglBipolar=10` – Bipolar coordinates $x_n = sinh(x)/(cosh(x) - cos(y)), y_n = sin(y)/(cosh(x) - cos(y)), z_n = z$; `mglLogLog=11` – log-log coordinates $x_n = lg(x), y_n = lg(y), z_n = lg(z)$; `mglLogX=12` – log-x coordinates $x_n = lg(x), y_n = y, z_n = z$; `mglLogY=13` – log-y coordinates $x_n = x, y_n = lg(y), z_n = z$.

`ternary val`	[MGL command]
`void Ternary (int `*tern*`)`	[Method on `mglGraph`]
`void mgl_set_ternary (HMGL `*gr*`, int `*tern*`)`	[C function]

The function sets to draws Ternary (*tern*=1), Quaternary (*tern*=2) plot or projections (*tern*=4,5,6).

Ternary plot is special plot for 3 dependent coordinates (components) a, b, c so that a+b+c=1. MathGL uses only 2 independent coordinates a=x and b=y since it is enough to plot everything. At this third coordinate z act as another parameter to produce contour lines, surfaces and so on.

Correspondingly, Quaternary plot is plot for 4 dependent coordinates a, b, c and d so that a+b+c+d=1. MathGL uses only 3 independent coordinates a=x, b=y and d=z since it is enough to plot everything.

Projections can be obtained by adding value 4 to *tern* argument. So, that *tern*=4 will draw projections in Cartesian coordinates, *tern*=5 will draw projections in Ternary coordinates, *tern*=6 will draw projections in Quaternary coordinates.

Use `Ternary(0)` for returning to usual axis. See Section 2.2.6 [Ternary axis], page 27, for sample code and picture. See Section 2.9.4 [Axis projection], page 104, for sample code and picture.

4.3.3 Ticks

`adjust [`'*dir*'='*xyzc*'`]`	[MGL command]
`void Adjust (const char *`*dir*`="xyzc")`	[Method on `mglGraph`]
`void mgl_adjust_ticks (HMGL `*gr*`, const char *`*dir*`)`	[C function]

Set the ticks step, number of sub-ticks and initial ticks position to be the most human readable for the axis along direction(s) *dir*. Also set `SetTuneTicks(true)`. Usually you don't need to call this function except the case of returning to default settings.

`xtick val [sub=0 org=nan]`	[MGL command]
`ytick val [sub=0 org=nan]`	[MGL command]
`ztick val [sub=0 org=nan]`	[MGL command]
`ctick val [sub=0 org=nan]`	[MGL command]
`void SetTicks (char `*dir*`, mreal `*d*`=0, int `*ns*`=0, mreal `*org*`=NAN)`	[Method on `mglGraph`]

void `mgl_set_ticks` (HMGL *gr*, char *dir*, mreal *d*, int *ns*, mreal *org*)   [C function]
>   Set the ticks step *d*, number of sub-ticks *ns* (used for positive *d*) and initial ticks
>   position *org* for the axis along direction *dir* (use 'c' for colorbar ticks). Variable *d*
>   set step for axis ticks (if positive) or it's number on the axis range (if negative). Zero
>   value set automatic ticks. If *org* value is NAN then axis origin is used.

xtick val1 *'lbl1'* [val2 *'lbl2'* ...]   [MGL command]
ytick val1 *'lbl1'* [val2 *'lbl2'* ...]   [MGL command]
ztick val1 *'lbl1'* [val2 *'lbl2'* ...]   [MGL command]
void `SetTicksVal` (char *dir*, const char **lbl*, bool   [Method on `mglGraph`]
>   *add*=`false`)
void `SetTicksVal` (char *dir*, const wchar_t **lbl*, bool   [Method on `mglGraph`]
>   *add*=`false`)
void `SetTicksVal` (char *dir*, const mglDataA &*val*, const   [Method on `mglGraph`]
>   char **lbl*, bool *add*=`false`)
void `SetTicksVal` (char *dir*, const mglDataA &*val*, const   [Method on `mglGraph`]
>   wchar_t **lbl*, bool *add*=`false`)
void `mgl_set_ticks_str` (HMGL *gr*, char *dir*, const char **lbl*, bool   [C function]
>   *add*)
void `mgl_set_ticks_wcs` (HMGL *gr*, char *dir*, const wchar_t **lbl*,   [C function]
>   bool *add*)
void `mgl_set_ticks_val` (HMGL *gr*, char *dir*, HCDT *val*, const char   [C function]
>   **lbl*, bool *add*)
void `mgl_set_ticks_valw` (HMGL *gr*, char *dir*, HCDT *val*, const   [C function]
>   wchar_t **lbl*, bool *add*)
>   Set the manual positions *val* and its labels *lbl* for ticks along axis *dir*. If array *val*
>   is absent then values equidistantly distributed in interval [*Min*.x, *Max*.x] are used.
>   Labels are separated by '\n' symbol. Use `SetTicks()` to restore automatic ticks.

xtick *'templ'*   [MGL command]
ytick *'templ'*   [MGL command]
ztick *'templ'*   [MGL command]
ctick *'templ'*   [MGL command]
void `SetTickTempl` (char *dir*, const char **templ*)   [Method on `mglGraph`]
void `SetTickTempl` (char *dir*, const wchar_t **templ*)   [Method on `mglGraph`]
void `mgl_set_tick_templ` (HMGL *gr*, const char **templ*)   [C function]
void `mgl_set_tick_templw` (HMGL *gr*, const wchar_t **templ*)   [C function]
>   Set template *templ* for x-,y-,z-axis ticks or colorbar ticks. It may contain TeX symbols
>   also. If *templ*=`""` then default template is used (in simplest case it is '`%.2g`'). Setting
>   on template switch off automatic ticks tuning.

ticktime *'dir'* [dv *'tmpl'*]   [MGL command]
void `SetTicksTime` (char *dir*, mreal *val*, const char   [Method on `mglGraph`]
>   **templ*)
void `mgl_set_ticks_time` (HMGL *gr*, mreal *val*, const char **templ*)   [C function]
>   Sets time labels with step *val* and template *templ* for x-,y-,z-axis ticks or colorbar
>   ticks. It may contain TeX symbols also. The format of template *templ* is the same as
>   described in <http://www.manpagez.com/man/3/strftime/>. Most common variants

are '%X' for national representation of time, '%x' for national representation of date, '%Y' for year with century. If *val*=0 and/or *templ*="" then automatic tick step and/or template will be selected. You can use `mgl_get_time`() function for obtaining number of second for given date/time string. Note, that MS Visual Studio couldn't handle date before 1970.

double mgl_get_time (const char*str, const char *templ)   [C function]
    Gets number of seconds from 1970 year to specified date/time *str*. The format of string is specified by *templ*, which is the same as described in http://www.manpagez.com/ man/3/strftime/. Most common variants are '%X' for national representation of time, '%x' for national representation of date, '%Y' for year with century. Note, that MS Visual Studio couldn't handle date before 1970.

tuneticks val [pos=1.15]   [MGL command]
void SetTuneTicks (int *tune*, mreal *pos*=1.15)   [Method on mglGraph]
void mgl_tune_ticks (HMGL *gr*, int *tune*, mreal *pos*)   [C function]
    Switch on/off ticks enhancing by factoring common multiplier (for small, like from 0.001 to 0.002, or large, like from 1000 to 2000, coordinate values – enabled if *tune*&1 is nonzero) or common component (for narrow range, like from 0.999 to 1.000 – enabled if *tune*&2 is nonzero). Also set the position *pos* of common multiplier/component on the axis: =0 at minimal axis value, =1 at maximal axis value. Default value is 1.15.

tickshift dx [dy=0 dz=0 dc=0]   [MGL command]
void SetTickShift (mglPoint *d*)   [Method on mglGraph]
void mgl_set_tick_shift (HMGL *gr*, mreal *dx*, mreal *dy*, mreal *dz*,   [C function]
        mreal *dc*)
    Set value of additional shift for ticks labels.

void SetTickRotate (bool *val*)   [Method on mglGraph]
void mgl_set_tick_rotate (HMGL *gr*, bool *val*)   [C function]
    Enable/disable ticks rotation if there are too many ticks or ticks labels are too long.

void SetTickSkip (bool *val*)   [Method on mglGraph]
void mgl_set_tick_skip (HMGL *gr*, bool *val*)   [C function]
    Enable/disable ticks skipping if there are too many ticks or ticks labels are too long.

void SetTimeUTC (bool *val*)   [Method on mglGraph]
    Enable/disable using UTC time for ticks labels. In C/Fortran you can use `mgl_set_` `flag(gr,val, MGL_USE_GMTIME);`.

origintick val   [MGL command]
void SetOriginTick (bool *val*=true)   [Method on mglGraph]
    Enable/disable drawing of ticks labels at axis origin. In C/Fortran you can use `mgl_` `set_flag(gr,val, MGL_NO_ORIGIN);`.

ticklen val [stt=1]   [MGL command]
void SetTickLen (mreal *val*, mreal *stt*=1)   [Method on mglGraph]
void mgl_set_tick_len (HMGL *gr*, mreal *val*, mreal *stt*)   [C function]
    The relative length of axis ticks. Default value is `0.1`. Parameter *stt*>0 set relative length of subticks which is in `sqrt(1+stt)` times smaller.

axisstl *'stl'* [*'tck'=" 'sub'="*]   [MGL command]
void SetAxisStl (const char **stl*="k"**, const char**   [Method on `mglGraph`]
        *tck=0**, const char** **sub*=0**)**
void mgl_set_axis_stl (HMGL *gr***, const char** **stl***, const char**   [C function]
        tck*, const char** **sub***)**
> The line style of axis (*stl*), ticks (*tck*) and subticks (*sub*). If *stl* is empty then default
> style is used ('k' or 'w' depending on transparency type). If *tck* or *sub* is empty then
> axis style is used (i.e. *stl*).

4.4 Subplots and rotation

These functions control how and where further plotting will be placed. There is a certain
calling order of these functions for the better plot appearance. First one should be [subplot],
page 147, [multiplot], page 147 or [inplot], page 148 for specifying the place. Second one can
be [title], page 148 for adding title for the subplot. After it a [rotate], page 149 and [aspect],
page 149. And finally any other plotting functions may be called. Alternatively you can
use [columnplot], page 148, [gridplot], page 148, [stickplot], page 148 or relative [inplot],
page 148 for positioning plots in the column (or grid, or stick) one by another without gap
between plot axis (bounding boxes). See Section 2.2.1 [Subplots], page 18, for sample code
and picture.

subplot *nx ny m* [*'stl'=*'<>_^' *dx*=0 *dy*=0]   [MGL command]
void SubPlot (int *nx***, int** *ny***, int** *m***, const char**   [Method on `mglGraph`]
        *stl="<>_^"**, mreal** *dx*=0**, mreal** *dy*=0**)**
void mgl_subplot (HMGL *gr***, int** *nx***, int** *ny***, int** *m***, const char** **stl***)**   [C function]
void mgl_subplot_d (HMGL *gr***, int** *nx***, int** *ny***, int** *m***, const char**   [C function]
        stl*, mreal** *dx***, mreal** *dy***)**
> Puts further plotting in a *m*-th cell of *nx*ny* grid of the whole frame area. This
> function set off any aspects or rotations. So it should be used first for creating the
> subplot. Extra space will be reserved for axis/colorbar if *stl* contain:
> - 'L' or '<' – at left side,
> - 'R' or '>' – at right side,
> - 'A' or '^' – at top side,
> - 'U' or '_' – at bottom side,
> - '#' – reserve none space (use whole region for axis range).
>
> From the aesthetical point of view it is not recommended to use this function with
> different matrices in the same frame. The position of the cell can be shifted from its
> default position by relative size *dx*, *dy*.

multiplot *nx ny m dx dy* [*'style'=*'<>_^']   [MGL command]
void MultiPlot (int *nx***, int** *ny***, int** *m***, int** *dx***, int** *dy***,**   [Method on `mglGraph`]
        const char **stl*="<>_^"**)**
void mgl_multiplot (HMGL *gr***, int** *nx***, int** *ny***, int** *m***, int** *dx***, int**   [C function]
        *dy***, const char** **stl***)**
> Puts further plotting in a rectangle of *dx*dy* cells starting from *m*-th cell of *nx*ny*
> grid of the whole frame area. This function set off any aspects or rotations. So it

should be used first for creating subplot. Extra space will be reserved for axis/colorbar if *stl* contain:

- 'L' or '<' – at left side,
- 'R' or '>' – at right side,
- 'A' or '^' – at top side,
- 'U' or '_' – at bottom side.

inplot x1 x2 y1 y2 [rel=on]   [MGL command]
void InPlot (mreal *x1*, mreal *x2*, mreal *y1*, mreal *y2*,   [Method on `mglGraph`]
     bool *rel*=`true`)
void mgl_inplot (HMGL *gr*, mreal *x1*, mreal *x2*, mreal *y1*, mreal *y2*)   [C function]
void mgl_relplot (HMGL *gr*, mreal *x1*, mreal *x2*, mreal *y1*, mreal   [C function]
     y2)
    Puts further plotting in some region of the whole frame surface. This function allows one to create a plot in arbitrary place of the screen. The position is defined by rectangular coordinates [*x1*, *x2*]*[*y1*, *y2*]. The coordinates *x1*, *x2*, *y1*, *y2* are normalized to interval [0, 1]. If parameter *rel*=`true` then the relative position to current (or with *rel*=`false`) is used. This function set off any aspects or rotations. So it should be used first for creating subplot.

columnplot num ind [d=0]   [MGL command]
void ColumnPlot (int *num*, int *ind*, mreal *d*=0)   [Method on `mglGraph`]
void mgl_columnplot (HMGL *gr*, int *num*, int *ind*)   [C function]
void mgl_columnplot_d (HMGL *gr*, int *num*, int *ind*, mreal *d*)   [C function]
    Puts further plotting in *ind*-th cell of column with *num* cells. The position is relative to previous (or with *rel*=`false`). Parameter *d* set extra gap between cells.

gridplot nx ny ind [d=0]   [MGL command]
void GridPlot (int *nx*, int *ny*, int *ind*, mreal *d*=0)   [Method on `mglGraph`]
void mgl_gridplot (HMGL *gr*, int *nx*, int *ny*, int *ind*)   [C function]
void mgl_gridplot_d (HMGL *gr*, int *nx*, int *ny*, int *ind*, mreal *d*)   [C function]
    Puts further plotting in *ind*-th cell of *nx**ny grid. The position is relative to previous (or with *rel*=`false`). Parameter *d* set extra gap between cells.

stickplot num ind tet phi   [MGL command]
void StickPlot (int *num*, int *ind*, mreal *tet*, mreal *phi*)   [Method on `mglGraph`]
void mgl_stickplot (HMGL *gr*, int *num*, int *ind*, mreal *tet*, mreal   [C function]
     phi)
    Puts further plotting in *ind*-th cell of stick with *num* cells. At this, stick is rotated on angles *tet*, *phi*. The position is relative to previous (or with *rel*=`false`).

title *'title'* [*'stl'*=" size=-2]   [MGL command]
void Title (const char *txt, const char *stl="", mreal   [Method on `mglGraph`]
    size=-2)

void Title (const wchar_t *txt, const char *stl="",   [Method on mglGraph]
    mreal size=-2)
void mgl_title (HMGL gr, const char *txt, const char *stl, mreal   [C function]
    size)
void mgl_titlew (HMGL gr, const wchar_t *txt, const char *stl,   [C function]
    mreal size)
    Add text *title* for current subplot/inplot. Paramater *stl* can contain:

- font style (see, Section 3.5 [Font styles], page 130);
- '#' for box around the title.

    Parameter *size* set font size. This function set off any aspects or rotations. So it
    should be used just after creating subplot.

rotate tetz tetx [tety=0]   [MGL command]
void Rotate (mreal *TetX*, mreal *TetZ*, mreal *TetY*=0)   [Method on mglGraph]
void mgl_rotate (HMGL gr, mreal *TetX*, mreal *TetZ*, mreal *TetY*)   [C function]
    Rotates a further plotting relative to each axis {x, z, y} consecutively on angles *TetX*,
    TetZ, *TetY*.

rotate tet x y z   [MGL command]
void RotateN (mreal *Tet*, mreal *x*, mreal *y*, mreal *z*)   [Method on mglGraph]
void mgl_rotate_vector (HMGL gr, mreal Tet, mreal x, mreal y,   [C function]
    mreal z)
    Rotates a further plotting around vector {x, y, z} on angle *Tet*.

aspect ax ay [az=1]   [MGL command]
void Aspect (mreal *Ax*, mreal *Ay*, mreal *Az*=1)   [Method on mglGraph]
void mgl_aspect (HMGL gr, mreal *Ax*, mreal *Ay*, mreal *Az*)   [C function]
    Defines aspect ratio for the plot. The viewable axes will be related one to another
    as the ratio *Ax:Ay:Az*. For the best effect it should be used after [rotate], page 149
    function. If *Ax* is NAN then function try to select optimal aspect ratio to keep equal
    ranges for x-y axis. At this, *Ay* will specify proportionality factor, or set to use
    automatic one if *Ay*=NAN.

perspective val   [MGL command]
void Perspective (mreal *a*)   [Method on mglGraph]
void mgl_perspective (HMGL gr, mreal *a*)   [C function]
    Add (switch on) the perspective to plot. The parameter a $1/z_{\{}eff\}$ $\in [0,1)$. By
    default (a=0) the perspective is off.

void Push ()   [Method on mglGraph]
void mgl_mat_push (HMGL gr)   [C function]
    Push transformation matrix into stack. Later you can restore its current state by
    Pop() function.

void Pop ()   [Method on mglGraph]
void mgl_mat_pop (HMGL gr)   [C function]
    Pop (restore last 'pushed') transformation matrix into stack.

`void SetPlotFactor (mreal val)`   [Method on `mglGraph`]
`void mgl_set_plotfactor (HMGL gr, mreal val)`   [C function]
>   Sets the factor of plot size. It is not recommended to set it lower then 1.5. This
>   is some analogue of function Zoom() but applied not to overall image but for each
>   InPlot. Use negative value or zero to enable automatic selection.

There are 2 functions `View()` and `Zoom()` which transform whole image. I.e. they act
as secondary transformation matrix. They were introduced for rotating/zooming the whole
plot by mouse. It is not recommended to call them for picture drawning.

`view tetx tetz [tety=0]`   [MGL command]
`void View (mreal TetX, mreal TetZ, mreal TetY=0)`   [Method on `mglGraph`]
`void mgl_view (HMGL gr, mreal TetX, mreal TetZ, mreal TetY)`   [C function]
>   Rotates a further plotting relative to each axis {x, z, y} consecutively on angles *TetX*,
>   *TetZ*, *TetY*. Rotation is done independently on [rotate], page 149. Attention! this
>   settings can not be overwritten by `DefaultPlotParam()`. Use `Zoom(0,0,1,1)` to
>   return default view.

`zoom x1 y1 x2 y2`   [MGL command]
`void Zoom (mreal x1, mreal y1, mreal x2,`   [Method on `mglGraph` (C++, Python)]
`        mreal y2)`
`void mgl_set_zoom (HMGL gr, mreal x1, mreal y1, mreal x2, mreal`   [C function]
`        y2)`
>   The function changes the scale of graphics that correspond to zoom in/out of the
>   picture. After function call the current plot will be cleared and further the picture
>   will contain plotting from its part [x1,x2]*[y1,y2]. Here picture coordinates *x1*, *x2*,
>   *y1*, *y2* changes from 0 to 1. Attention! this settings can not be overwritten by
>   any other functions, including `DefaultPlotParam()`. Use `Zoom(0,0,1,1)` to return
>   default view.

4.5 Export picture

Functions in this group save or give access to produced picture. So, usually they should be
called after plotting is done.

`setsize w h`   [MGL command]
`void SetSize (int width, int height)`   [Method on `mglGraph`]
`void mgl_set_size (HMGL gr, int width, int height)`   [C function]
>   Sets size of picture in pixels. This function **must be** called before any other plotting
>   because it completely remove picture contents.

`quality [val=2]`   [MGL command]
`void SetQuality (int val=MGL_DRAW_NORM)`   [Method on `mglGraph`]
`void mgl_set_quality (HMGL gr, int val)`   [C function]
>   Sets quality of the plot depending on value *val*: `MGL_DRAW_WIRE=0` – no face drawing
>   (fastest), `MGL_DRAW_FAST=1` – no color interpolation (fast), `MGL_DRAW_NORM=2` – high
>   quality (normal), `MGL_DRAW_HIGH=3` – high quality with 3d primitives (arrows and
>   marks). If `MGL_DRAW_LMEM=0x4` is set then direct bitmap drawing is used (low memory
>   usage).

`int GetQuality ()`   [Method on `mglGraph`]
`int mgl_get_quality (HMGL `*gr*`)`   [C function]
>   Gets quality of the plot: `MGL_DRAW_WIRE=0` – no face drawing (fastest), `MGL_DRAW_`
>   `FAST=1` – no color interpolation (fast), `MGL_DRAW_NORM=2` – high quality (normal),
>   `MGL_DRAW_HIGH=3` – high quality with 3d primitives (arrows and marks). If `MGL_`
>   `DRAW_LMEM=0x4` is set then direct bitmap drawing is used (low memory usage).

`void StartGroup (`*const char *name*`)`   [Method on `mglGraph`]
`void mgl_start_group (HMGL `*gr*`, const char *`*name*`)`   [C function]
>   Starts group definition. Groups contain objects and other groups, they are used to
>   select a part of a model to zoom to or to make invizible or to make semitransparent
>   and so on.

`void EndGroup ()`   [Method on `mglGraph`]
`void mgl_end_group (HMGL `*gr*`)`   [C function]
>   Ends group definition.

4.5.1 Export to file

These functions export current view to a graphic file. The filename *fname* should have
appropriate extension. Parameter *descr* gives the short description of the picture. Just now
the transparency is supported in PNG, SVG, OBJ and PRC files.

`write [`*'fname'=*`"]`   [MGL command]
`void WriteFrame (const char *`*fname*`="", const char`   [Method on `mglGraph`]
>   `*`*descr*`="")`
`void mgl_write_frame (HMGL `*gr*`, const char *`*fname*`, const char`   [C function]
>   `*`*descr*`)`
>   Exports current frame to a file *fname* which type is determined by the extension.
>   Parameter *descr* adds description to file (can be `""`). If *fname*`=""` then the file
>   '`frame####.jpg`' is used, where '`####`' is current frame id and name '`frame`' is defined
>   by [plotid], page 138 class property.

`void WritePNG (const char *`*fname*`, const char`   [Method on `mglGraph`]
>   `*`*descr*`="", int `*compr*`="", bool `*alpha*`=true)`
`void mgl_write_png (HMGL `*gr*`, const char *`*fname*`, const char`   [C function]
>   `*`*descr*`)`
`void mgl_write_png_solid (HMGL `*gr*`, const char *`*fname*`, const`   [C function]
>   `char *`*descr*`)`
>   Exports current frame to PNG file. Parameter *fname* specifies the file name, *descr*
>   adds description to file, *alpha* gives the transparency type. By default there are no
>   description added and semitransparent image used. This function does nothing if
>   HAVE_PNG isn't defined during compilation of MathGL library.

void **WriteJPEG** (const char **fname*, const char   [Method on `mglGraph`]
    **descr="")
void **mgl_write_jpg** (HMGL *gr*, const char **fname*, const char   [C function]
    **descr)

> Exports current frame to JPEG file. Parameter *fname* specifies the file name, *descr* adds description to file. By default there is no description added. This function does nothing if HAVE_JPEG isn't defined during compilation of MathGL library.

void **WriteGIF** (const char **fname*, const char   [Method on `mglGraph`]
    **descr="")
void **mgl_write_gif** (HMGL *gr*, const char **fname*, const char   [C function]
    **descr)

> Exports current frame to GIF file. Parameter *fname* specifies the file name, *descr* adds description to file. By default there is no description added. This function does nothing if HAVE_GIF isn't defined during compilation of MathGL library.

void **WriteBMP** (const char **fname*, const char   [Method on `mglGraph`]
    **descr="")
void **mgl_write_bmp** (HMGL *gr*, const char **fname*, const char   [C function]
    **descr)

> Exports current frame to BMP file. Parameter *fname* specifies the file name, *descr* adds description to file. There is no compression used.

void **WriteTGA** (const char **fname*, const char   [Method on `mglGraph`]
    **descr="")
void **mgl_write_tga** (HMGL *gr*, const char **fname*, const char   [C function]
    **descr)

> Exports current frame to TGA file. Parameter *fname* specifies the file name, *descr* adds description to file. There is no compression used.

void **WriteEPS** (const char **fname*, const char   [Method on `mglGraph`]
    **descr="")
void **mgl_write_eps** (HMGL *gr*, const char **fname*, const char   [C function]
    **descr)

> Exports current frame to EPS file using vector representation. So it is not recommended for the export of large data plot. It is better to use bitmap format (for example PNG or JPEG). However, program has no internal limitations for size of output file. Parameter *fname* specifies the file name, *descr* adds description to file. By default there is no description added. If file name is terminated by 'z' (for example, 'fname.eps.gz') then file will be compressed in gzip format.

void **WriteBPS** (const char **fname*, const char   [Method on `mglGraph`]
    **descr="")
void **mgl_write_eps** (HMGL *gr*, const char **fname*, const char   [C function]
    **descr)

> Exports current frame to EPS file using bitmap representation. Parameter *fname* specifies the file name, *descr* adds description to file. By default there is no description added. If file name is terminated by 'z' (for example, 'fname.eps.gz') then file will be compressed in gzip format.

void **WriteSVG** (const char *fname, const char   [Method on `mglGraph`]
        *descr="")
void **mgl_write_svg** (HMGL *gr*, const char *fname, const char   [C function]
        *descr)

> Exports current frame to SVG (Scalable Vector Graphics) file using vector represen-
> tation. In difference of EPS format, SVG format support transparency that allows
> to correctly draw semitransparent plot (like [surfa], page 188, [surf3a], page 188 or
> [cloud], page 184). Note, the output file may be too large for graphic of large data
> array (especially for surfaces). It is better to use bitmap format (for example PNG
> or JPEG). However, program has no internal limitations for size of output file. Pa-
> rameter *fname* specifies the file name, *descr* adds description to file (default is file
> name). If file name is terminated by 'z' (for example, 'fname.svgz') then file will be
> compressed in gzip format.

void **WriteTEX** (const char *fname, const char   [Method on `mglGraph`]
        *descr="")
void **mgl_write_tex** (HMGL *gr*, const char *fname, const char   [C function]
        *descr)

> Exports current frame to LaTeX (package Tikz/PGF) file using vector representation.
> Note, the output file may be too large for graphic of large data array (especially for
> surfaces). It is better to use bitmap format (for example PNG or JPEG). However,
> program has no internal limitations for size of output file. Parameter *fname* specifies
> the file name, *descr* adds description to file (default is file name). Note, there is no
> text scaling now (for example, in subplots), what may produce miss-aligned labels.

void **WritePRC** (const char *fname, const char   [Method on `mglGraph`]
        *descr="", bool *make_pdf*=true)
void **mgl_write_prc** (HMGL *gr*, const char *fname, const char   [C function]
        *descr, int *make_pdf*)

> Exports current frame to PRC file using vector representation (see http://en.
> wikipedia.org/wiki/PRC_%28file_format%29). Note, the output file may be too
> large for graphic of large data array (especially for surfaces). It is better to use bitmap
> format (for example PNG or JPEG). However, program has no internal limitations
> for size of output file. Parameter *fname* specifies the file name, *descr* adds description
> to file (default is file name). If parameter *make_pdf*=true and PDF was enabled at
> MathGL configure then corresponding PDF file with 3D image will be created.

void **WriteOBJ** (const char *fname, const char   [Method on `mglGraph`]
        *descr="")
void **mgl_write_obj** (HMGL *gr*, const char *fname, const char   [C function]
        *descr)

> Exports current frame to OBJ/MTL file using vector representation (see OBJ format
> for details). Note, the output file may be too large for graphic of large data array (es-
> pecially for surfaces). It is better to use bitmap format (for example PNG or JPEG).
> However, program has no internal limitations for size of output file. Parameter *fname*
> specifies the file name, *descr* adds description to file (default is file name).

void WriteXYZ (const char *_fname_, const char   [Method on `mglGraph`]
        *_descr_="")
void mgl_write_xyz (HMGL _gr_, const char *_fname_, const char   [C function]
        *_descr_)
    Exports current frame to XYZ/XYZL/XYZF files using vector representation (see
    XYZ format for details). Note, the output file may be too large for graphic of large
    data array (especially for surfaces). It is better to use bitmap format (for example
    PNG or JPEG). However, program has no internal limitations for size of output file.
    Parameter _fname_ specifies the file name, _descr_ adds description to file (default is file
    name).

void WriteSTL (const char *_fname_, const char   [Method on `mglGraph`]
        *_descr_="")
void mgl_write_stl (HMGL _gr_, const char *_fname_, const char   [C function]
        *_descr_)
    Exports current frame to STL file using vector representation (see STL format for
    details). Note, the output file may be too large for graphic of large data array (espe-
    cially for surfaces). It is better to use bitmap format (for example PNG or JPEG).
    However, program has no internal limitations for size of output file. Parameter _fname_
    specifies the file name, _descr_ adds description to file (default is file name.

void WriteOFF (const char *_fname_, const char   [Method on `mglGraph`]
        *_descr_="", bool _colored_=false)
void mgl_write_off (HMGL _gr_, const char *_fname_, const char   [C function]
        *_descr_, bool _colored_)
    Exports current frame to OFF file using vector representation (see OFF format for
    details). Note, the output file may be too large for graphic of large data array (espe-
    cially for surfaces). It is better to use bitmap format (for example PNG or JPEG).
    However, program has no internal limitations for size of output file. Parameter _fname_
    specifies the file name, _descr_ adds description to file (default is file name).

void ShowImage (const char *_viewer_, bool   [Method on `mglGraph`]
        nowait=false)
void mgl_show_image (const char *_viewer_, int _nowait_)   [C function]
    Displays the current picture using external program _viewer_ for viewing. The function
    save the picture to temporary file and call _viewer_ to display it. If _nowait_=true then
    the function return immediately (it will not wait while window will be closed).

void WriteJSON (const char *_fname_, const char   [Method on `mglGraph`]
        *_descr_="")
void mgl_write_json (HMGL _gr_, const char *_fname_, const char   [C function]
        *_descr_)
    Exports current frame to textual file using Section B.3 [JSON format], page 278. Later
    this file can be used for faster loading and viewing by JavaScript script. Parameter
    fname specifies the file name, _descr_ adds description to file.

void ExportMGLD (const char *fname, const char   [Method on mglGraph]
      *descr="")
void mgl_export_mgld (HMGL gr, const char *fname, const char   [C function]
      *descr)
> Exports points and primitives in file using Section B.2 [MGLD format], page 277.
> Later this file can be used for faster loading and viewing by mglview utility. Parameter
> fname specifies the file name, descr adds description to file (default is file name).

void ImportMGLD (const char *fname, bool add=false)   [Method on mglGraph]
void mgl_import_mgld (HMGL gr, const char *fname, int add)   [C function]
> Imports points and primitives in file using Section B.2 [MGLD format], page 277.
> Later this file can be used for faster loading and viewing by mglview utility. Parameter
> fname specifies the file name, add sets to append or replace primitives to existed ones.

4.5.2 Frames/Animation

These functions provide ability to create several pictures simultaneously. For most of cases
it is useless but for widget classes (see Chapter 5 [Widget classes], page 205) they can
provide a way to show animation. Also you can write several frames into animated GIF
file.

void NewFrame ()   [Method on mglGraph]
void mgl_new_frame (HMGL gr)   [C function]
> Creates new frame. Function returns current frame id. This is not thread safe function
> in OpenGL mode! Use direct list creation in multi-threading drawing. The function
> EndFrame() **must** be call after the finishing of the frame drawing for each call of this
> function.

void EndFrame ()   [Method on mglGraph]
void mgl_end_frame (HMGL gr)   [C function]
> Finishes the frame drawing.

int GetNumFrame ()   [Method on mglGraph]
int mgl_get_num_frame (HMGL gr)   [C function]
> Gets the number of created frames.

void SetFrame (int i)   [Method on mglGraph]
void mgl_set_frame (HMGL gr, int i)   [C function]
> Finishes the frame drawing and sets drawing data to frame i, which should be in range
> [0, GetNumFrame()-1]. This function is similar to EndFrame() but don't add frame
> to the GIF image.

void GetFrame (int i)   [Method on mglGraph]
void mgl_get_frame (HMGL gr, int i)   [C function]
> Replaces drawing data by one from frame i. Function work if MGL_VECT_FRAME is set
> on (by default).

void ShowFrame (int i)   [Method on mglGraph]
void mgl_show_frame (HMGL gr, int i)   [C function]
> Appends drawing data from frame i to current one. Function work if MGL_VECT_FRAME
> is set on (by default).

void DelFrame (int *i*)	[Method on mglGraph]
void mgl_del_frame (HMGL *gr*, int *i*)	[C function]

Deletes drawing data for frame *i* and shift all later frame indexes. Function work if `MGL_VECT_FRAME` is set on (by default). Do nothing in OpenGL mode.

void ResetFrames ()	[Method on mglGraph]
void mgl_reset_frames (HMGL *gr*)	[C function]

Reset frames counter (start it from zero).

void StartGIF (const char **fname*, int *ms*=100)	[Method on mglGraph]
void mgl_start_gif (HMGL *gr*, const char **fname*, int *ms*)	[C function]

Start writing frames into animated GIF file *fname*. Parameter *ms* set the delay between frames in milliseconds. You **should not** change the picture size during writing the cinema. Use `CloseGIF()` to finalize writing. Note, that this function is disabled in OpenGL mode.

void CloseGIF ()	[Method on mglGraph]
void mgl_close_gif (HMGL *gr*)	[C function]

Finish writing animated GIF and close connected pointers.

4.5.3 Bitmap in memory

These functions return the created picture (bitmap), its width and height. You may display it by yourself in any graphical library (see also, Chapter 5 [Widget classes], page 205) or save in file (see also, Section 4.5.1 [Export to file], page 151).

const unsigned char * GetRGB ()	[Method on mglGraph]
void GetRGB (char **buf*, int *size*)	[Method on mglGraph]
void GetBGRN (char **buf*, int *size*)	[Method on mglGraph]
const unsigned char * mgl_get_rgb (HMGL *gr*)	[C function]

Gets RGB bitmap of the current state of the image. Format of each element of bits is: {red, green, blue}. Number of elements is Width*Height. Position of element {i,j} is [3*i + 3*Width*j] (or is [4*i + 4*Width*j] for `GetBGRN()`). You have to provide the proper *size* of the buffer, *buf*, i.e. the code for Python should look like

```
from mathgl import *
gr = mglGraph();
bits='\t';
bits=bits.expandtabs(4*gr.GetWidth()*gr.GetHeight());
gr.GetBGRN(bits, len(bits));
```

const unsigned char * GetRGBA ()	[Method on mglGraph]
void GetRGBA (char **buf*, int *size*)	[Method on mglGraph]
const unsigned char * mgl_get_rgba (HMGL *gr*)	[C function]

Gets RGBA bitmap of the current state of the image. Format of each element of bits is: {red, green, blue, alpha}. Number of elements is Width*Height. Position of element {i,j} is [4*i + 4*Width*j].

int GetWidth ()	[Method on mglGraph]
int GetHeight ()	[Method on mglGraph]

`int mgl_get_width (HMGL `*gr*`)`   [C function]
`int mgl_get_height (HMGL `*gr*`)`   [C function]
>   Gets width and height of the image.

`mglPoint CalcXYZ (int `*xs*`, int `*ys*`)`   [Method on `mglGraph`]
`void mgl_calc_xyz (HMGL `*gr*`, int `*xs*`, int `*ys*`, mreal *`*x*`, mreal *`*y*`,`   [C function]
>   `mreal *`*z*`)`
>   Calculate 3D coordinate {x,y,z} for screen point {xs,ys}. At this moment it ignore
>   perspective and transformation formulas (curvilinear coordinates). The calculation
>   are done for the last used InPlot (see Section 4.4 [Subplots and rotation], page 147).

`mglPoint CalcScr (mglPoint `*p*`)`   [Method on `mglGraph`]
`void mgl_calc_scr (HMGL `*gr*`, mreal `*x*`, mreal `*y*`, mreal `*z*`, int *`*xs*`,`   [C function]
>   `int *`*ys*`)`
>   Calculate screen point {xs,ys} for 3D coordinate {x,y,z}. The calculation are done
>   for the last used InPlot (see Section 4.4 [Subplots and rotation], page 147).

`void SetObjId (int `*id*`)`   [Method on `mglGraph`]
`void mgl_set_obj_id (HMGL `*gr*`, int `*id*`)`   [C function]
>   Set the numeric id for object or subplot/inplot.

`int GetObjId (int `*xs*`, int `*ys*`)`   [Method on `mglGraph`]
`int mgl_get_obj_id (HMGL `*gr*`, int `*xs*`, int `*ys*`)`   [C function]
>   Get the numeric id for most upper object at pixel {xs, ys} of the picture.

`int GetSplId (int `*xs*`, int `*ys*`)`   [Method on `mglGraph`]
`int mgl_get_spl_id (HMGL `*gr*`, int `*xs*`, int `*ys*`)`   [C function]
>   Get the numeric id for most subplot/inplot at pixel {xs, ys} of the picture.

`void Highlight (int `*id*`)`   [Method on `mglGraph`]
`void mgl_highlight (HMGL `*gr*`, int `*id*`)`   [C function]
>   Highlight the object with given *id*.

`long IsActive (int `*xs*`, int `*ys*`, int `*d*`=1)`   [Method on `mglGraph`]
`long mgl_is_active (HMGL `*gr*`, int `*xs*`, int `*ys*`, int `*d*`)`   [C function]
>   Checks if point {xs, ys} is close to one of active point (i.e. mglBase::Act) with
>   accuracy *d* and return its index or `-1` if not found. Active points are special points
>   which characterize primitives (like edges and so on). This function for advanced users
>   only.

4.5.4 Parallelization

Many of things MathGL do in parallel by default (if MathGL was built with pthread).
However, there is function which set the number of threads to be used.

`int mgl_set_num_thr (int `*n*`)`   [C function]
>   Set the number of threads to be used by MathGL. If *n*<1 then the number of threads
>   is set as maximal number of processors (cores). If *n*=1 then single thread will be used
>   (this is default if pthread was disabled).

Another option is combining bitmap image (taking into account Z-ordering) from different instances of `mglGraph`. This method is most appropriate for computer clusters when the data size is so large that it exceed the memory of single computer node.

int Combine (const mglGraph *g)   [Method on `mglGraph`]
int mgl_combine_gr (HMGL gr, HMGL g)   [C function]
>   Combine drawing from instance g with gr (or with this) taking into account Z-ordering of pixels. The width and height of both instances must be the same.

int MPI_Send (int id)   [Method on `mglGraph`]
int mgl_mpi_send (HMGL gr, int id)   [C function]
>   Send graphical information from node id using MPI. The width and height in both nodes must be the same.

int MPI_Recv (int id)   [Method on `mglGraph`]
int mgl_mpi_send (HMGL gr, int id)   [C function]
>   Receive graphical information from node id using MPI. The width and height in both nodes must be the same.

4.6 Primitives

These functions draw some simple objects like line, point, sphere, drop, cone and so on. See Section 2.9.7 [Using primitives], page 107, for sample code and picture.

clf   [MGL command]
void Clf ()   [Method on `mglGraph`]
void Clf (mreal r, mreal g, mreal b)   [Method on `mglGraph`]
void mgl_clf (HMGL gr)   [C function]
void mgl_clf_rgb (HMGL gr, mreal r, mreal g, mreal b)   [C function]
>   Clear the picture and fill it by color specified color.

ball x y ['col'='r.']   [MGL command]
ball x y z ['col'='r.']   [MGL command]
void Ball (mglPoint p, char col='r')   [Method on `mglGraph`]
void Mark (mglPoint p, const char *mark)   [Method on `mglGraph`]
void mgl_mark (HMGL gr, mreal x, mreal y, mreal z, const char   [C function]
>   *mark)
>   Draws a mark (point '.' by default) at position $p=\{x, y, z\}$ with color col.

errbox x y ex ey ['stl'=”]   [MGL command]
errbox x y z ex ey ez ['stl'=”]   [MGL command]
void Error (mglPoint p, mglPoint e, char *stl="")   [Method on `mglGraph`]
void mgl_error_box (HMGL gr, mreal x, mreal y, mreal z, mreal ex,   [C function]
>   mreal ey, mreal ez, char *stl)
>   Draws a 3d error box at position $p=\{x, y, z\}$ with sizes $e=\{ex, ey, ez\}$ and style stl. Use NAN for component of e to reduce number of drawn elements.

line x1 y1 x2 y2 ['stl'=”]   [MGL command]
line x1 y1 z1 x2 y2 z2 ['stl'=”]   [MGL command]

void Line (mglPoint *p1*, mglPoint *p2*, char **stl*="B",   [Method on `mglGraph`]
      int *num*=2)

void mgl_line (HMGL *gr*, mreal *x1*, mreal *y1*, mreal *z1*, mreal *x2*,   [C function]
      mreal *y2*, mreal *z2*, char **stl*, int *num*)

    Draws a geodesic line (straight line in Cartesian coordinates) from point *p1* to *p2*
    using line style *stl*. Parameter *num* define the "quality" of the line. If *num*=2 then the
    stright line will be drawn in all coordinate system (independently on transformation
    formulas (see Section 4.3.2 [Curved coordinates], page 143). Contrary, for large values
    (for example, =100) the geodesic line will be drawn in corresponding coordinate
    system (straight line in Cartesian coordinates, circle in polar coordinates and so on).
    Line will be drawn even if it lies out of bounding box.

curve x1 y1 dx1 dy1 x2 y2 dx2 dy2 ['*stl*='']   [MGL command]
curve x1 y1 z1 dx1 dy1 dz1 x2 y2 z2 dx2 dy2 dz2 ['*stl*='']   [MGL command]
void Curve (mglPoint *p1*, mglPoint *d1*, mglPoint *p2*,   [Method on `mglGraph`]
      mglPoint *d2*, const char **stl*="B", int *num*=100)

void mgl_curve (HMGL *gr*, mreal *x1*, mreal *y1*, mreal *z1*, mreal *dx1*,   [C function]
      mreal *dy1*, mreal *dz1*, mreal *x2*, mreal *y2*, mreal *z2*, mreal *dx2*, mreal
      dy2, mreal *dz2*, const char **stl*, int *num*)

    Draws Bezier-like curve from point *p1* to *p2* using line style *stl*. At this tangent is
    codirected with *d1*, *d2* and proportional to its amplitude. Parameter *num* define the
    "quality" of the curve. If *num*=2 then the straight line will be drawn in all coor-
    dinate system (independently on transformation formulas, see Section 4.3.2 [Curved
    coordinates], page 143). Contrary, for large values (for example, =100) the spline like
    Bezier curve will be drawn in corresponding coordinate system. Curve will be drawn
    even if it lies out of bounding box.

face x1 y1 x2 y2 x3 y3 x4 y4 ['*stl*='']   [MGL command]
face x1 y1 z1 x2 y2 z2 x3 y3 z3 x4 y4 z4 ['*stl*='']   [MGL command]
void Face (mglPoint *p1*, mglPoint *p2*, mglPoint *p3*,   [Method on `mglGraph`]
      mglPoint *p4*, const char **stl*="w")

void mgl_face (HMGL *gr*, mreal *x1*, mreal *y1*, mreal *z1*, mreal *x2*,   [C function]
      mreal *y2*, mreal *z2*, mreal *x3*, mreal *y3*, mreal *z3*, mreal *x4*, mreal *y4*,
      mreal *z4*, const char **stl*)

    Draws the solid quadrangle (face) with vertexes *p1*, *p2*, *p3*, *p4* and with color(s) *stl*.
    At this colors can be the same for all vertexes or different if all 4 colors are specified
    for each vertex. Face will be drawn even if it lies out of bounding box.

rect x1 y1 x2 y2 ['*stl*='']   [MGL command]
rect x1 y1 z1 x2 y2 z2 ['*stl*='']   [MGL command]

    Draws the solid rectangle (face) with vertexes {*x1*, *y1*, *z1*} and {*x2*, *y2*, *z2*} with
    color *stl*. At this colors can be the same for all vertexes or separately if all 4 colors
    are specified for each vertex. Face will be drawn even if it lies out of bounding box.

facex x0 y0 z0 wy wz ['*stl*='' d1=0 d2=0]   [MGL command]
facey x0 y0 z0 wx wz ['*stl*='' d1=0 d2=0]   [MGL command]
facez x0 y0 z0 wx wy ['*stl*='' d1=0 d2=0]   [MGL command]
void FaceX (mreal *x0*, mreal *y0*, mreal *z0*, mreal *wy*,   [Method on `mglGraph`]
      mreal *wz*, const char **stl*="w", mreal *d1*=0, mreal *d2*=0)

void FaceY (mreal *x0*, mreal *y0*, mreal *z0*, mreal *wx*,   [Method on `mglGraph`]
        mreal *wz*, const char *`*stl`*="w", mreal *d1*=0, mreal *d2*=0)
void FaceZ (mreal *x0*, mreal *y0*, mreal *z0*, mreal *wx*,   [Method on `mglGraph`]
        mreal *wy*, const char *`*stl`*="w", mreal *d1*=0, mreal *d2*=0)
void mgl_facex (HMGL *gr*, mreal *x0*, mreal *y0*, mreal *z0*, mreal *wy*,   [C function]
        mreal *wz*, const char *`*stl`*, mreal *d1*, mreal *d2*)
void mgl_facey (HMGL *gr*, mreal *x0*, mreal *y0*, mreal *z0*, mreal *wx*,   [C function]
        mreal *wz*, const char *`*stl`*, mreal *d1*, mreal *d2*)
void mgl_facez (HMGL *gr*, mreal *x0*, mreal *y0*, mreal *z0*, mreal *wx*,   [C function]
        mreal *wy*, const char *`*stl`*, mreal *d1*, mreal *d2*)
> Draws the solid rectangle (face) perpendicular to [x,y,z]-axis correspondingly at po-
> sition {*x0*, *y0*, *z0*} with color *stl* and with widths *wx*, *wy*, *wz* along corresponding
> directions. At this colors can be the same for all vertexes or separately if all 4 colors
> are specified for each vertex. Parameters *d1*!=0, *d2*!=0 set additional shift of the last
> vertex (i.e. to draw quadrangle). Face will be drawn even if it lies out of bounding
> box.

sphere *x0* *y0* *r* ['col'='r']   [MGL command]
sphere *x0* *y0* *z0* *r* ['col'='r']   [MGL command]
void Sphere (mglPoint *p*, mreal *r*, const char *`*stl`*="r")   [Method on `mglGraph`]
void mgl_sphere (HMGL *gr*, mreal *x0*, mreal *y0*, mreal *z0*, mreal *r*,   [C function]
        const char *`*stl`*)
> Draw the sphere with radius *r* and center at point *p*={*x0*, *y0*, *z0*} and color *stl*.

drop *x0* *y0* *dx* *dy* *r* ['col'='r' sh=1 asp=1]   [MGL command]
drop *x0* *y0* *z0* *dx* *dy* *dz* *r* ['col'='r' sh=1 asp=1]   [MGL command]
void Drop (mglPoint *p*, mglPoint *d*, mreal *r*, const char   [Method on `mglGraph`]
        `*col`="r", mreal *shift*=1, mreal *ap*=1)
void mgl_drop (HMGL *gr*, mreal *x0*, mreal *y0*, mreal *z0*, mreal *dx*,   [C function]
        mreal *dy*, mreal *dz*, mreal *r*, const char *`*col`*, mreal *shift*, mreal *ap*)
> Draw the drop with radius *r* at point *p* elongated in direction *d* and with color *col*.
> Parameter *shift* set the degree of drop oblongness: '0' is sphere, '1' is maximally
> oblongness drop. Parameter *ap* set relative width of the drop (this is analogue of
> "ellipticity" for the sphere).

cone *x1* *y1* *z1* *x2* *y2* *z2* *r1* [r2=-1 'stl'=']   [MGL command]
void Cone (mglPoint *p1*, mglPoint *p2*, mreal *r1*, mreal   [Method on `mglGraph`]
        r2=-1, const char *`*stl`*="B")
void mgl_cone (HMGL *gr*, mreal *x1*, mreal *y1*, mreal *z1*, mreal *x2*,   [C function]
        mreal *y2*, mreal *z2*, mreal *r1*, mreal *r2*, const char *`*stl`*)
> Draw tube (or truncated cone if *edge*=`false`) between points *p1*, *p2* with radius at
> the edges *r1*, *r2*. If *r2*<0 then it is supposed that *r2*=*r1*. The cone color is defined by
> string *stl*. If style contain '@' then edges will be drawn.

circle *x0* *y0* *r* ['col'='r']   [MGL command]
circle *x0* *y0* *z0* *r* ['col'='r']   [MGL command]
void Circle (mglPoint *p*, mreal *r*, const char *`*stl`*="r")   [Method on `mglGraph`]
> Draw the circle with radius *r* and center at point *p*={*x0*, *y0*, *z0*}. Parameter *col* may
> contain

- colors for filling and boundary (second one if style '@' is used, black color is used by default);
- '#' for wire figure (boundary only);
- '@' for filling and boundary.

ellipse x1 y1 x2 y2 r ['col'='r']   [MGL command]
ellipse x1 y1 z1 x2 y2 z2 r ['col'='r']   [MGL command]
void Ellipse (mglPoint *p1*, mglPoint *p2*, mreal *r*, const   [Method on mglGraph]
        char **col*="r")
void mgl_ellipse (HMGL *gr*, mreal *x1*, mreal *y1*, mreal *z1*, mreal   [C function]
        x2, mreal *y2*, mreal *z2*, mreal *r*, const char **col*)
    Draw the ellipse with radius *r* and focal points *p1*, *p2*. Parameter *col* may contain

- colors for filling and boundary (second one if style '@' is used, black color is used by default);
- '#' for wire figure (boundary only);
- '@' for filling and boundary.

rhomb x1 y1 x2 y2 r ['col'='r']   [MGL command]
rhomb x1 y1 z1 x2 y2 z2 r ['col'='r']   [MGL command]
void Rhomb (mglPoint *p1*, mglPoint *p2*, mreal *r*, const   [Method on mglGraph]
        char **col*="r")
void mgl_rhomb (HMGL *gr*, mreal *x1*, mreal *y1*, mreal *z1*, mreal *x2*,   [C function]
        mreal *y2*, mreal *z2*, mreal *r*, const char **col*)
    Draw the rhombus with width *r* and edge points *p1*, *p2*. Parameter *col* may contain

- colors for filling and boundary (second one if style '@' is used, black color is used by default);
- '#' for wire figure (boundary only);
- '@' for filling and boundary.

4.7 Text printing

These functions draw the text. There are functions for drawing text in arbitrary place, in arbitrary direction and along arbitrary curve. MathGL can use arbitrary font-faces and parse many TeX commands (for more details see Section 3.5 [Font styles], page 130). All these functions have 2 variant: for printing 8-bit text (char *) and for printing Unicode text (wchar_t *). In first case the conversion into the current locale is used. So sometimes you need to specify it by setlocale() function. The *size* argument control the size of text: if positive it give the value, if negative it give the value relative to SetFontSize(). The font type (STIX, arial, courier, times and so on) can be selected by function LoadFont(). See Section 4.2.6 [Font settings], page 139.

    The font parameters are described by string. This string may set the text color 'wkrgbcymhRGBCYMHW' (see Section 3.2 [Color styles], page 127). Also, after delimiter symbol ':', it can contain characters of font type ('rbiwou') and/or align ('LRC') specification. The font types are: 'r' – roman (or regular) font, 'i' – italic style, 'b' – bold style, 'w' – wired style, 'o' – over-lined text, 'u' – underlined text. By default roman font is used. The align types are: 'L' – align left (default), 'C' – align center, 'R' – align right. For

example, string 'b:iC' correspond to italic font style for centered text which printed by blue color.

If string contains symbols 'aA' then text is printed at absolute position $\{x, y\}$ (supposed to be in range [0,1]) of picture (for 'A') or subplot/inplot (for 'a'). If string contains symbol '@' then box around text is drawn.

See Section 2.2.7 [Text features], page 28, for sample code and picture.

<pre>
text x y 'text' ['fnt'='" size=-1]   [MGL command]
text x y z 'text' ['fnt'='" size=-1]   [MGL command]
void Puts (mglPoint p, const char *text, const char   [Method on mglGraph]
        *fnt=":C", mreal size=-1)
void Putsw (mglPoint p, const wchar_t *text, const   [Method on mglGraph]
        char *fnt=":C", mreal size=-1)
void Puts (mreal x, mreal y, const char *text, const   [Method on mglGraph]
        char *fnt=":AC", mreal size=-1)
void Putsw (mreal x, mreal y, const wchar_t *text,   [Method on mglGraph]
        const char *fnt=":AC", mreal size=-1)
void mgl_puts (HMGL gr, mreal x, mreal y, mreal z, const char   [C function]
        *text, const char *fnt, mreal size)
void mgl_putsw (HMGL gr, mreal x, mreal y, mreal z, const   [C function]
        wchar_t *text, const char *fnt, mreal size)
</pre>
The function plots the string *text* at position *p* with fonts specifying by the criteria *fnt*. The size of font is set by *size* parameter (default is -1).

<pre>
text x y dx dy 'text' ['fnt'=':L' size=-1]   [MGL command]
text x y z dx dy dz 'text' ['fnt'=':L' size=-1]   [MGL command]
void Puts (mglPoint p, mglPoint d, const char *text,   [Method on mglGraph]
        const char *fnt=":L", mreal size=-1)
void Putsw (mglPoint p, mglPoint d, const wchar_t   [Method on mglGraph]
        *text, const char *fnt=":L", mreal size=-1)
void mgl_puts_dir (HMGL gr, mreal x, mreal y, mreal z, mreal dx,   [C function]
        mreal dy, mreal dz, const char *text, const char *fnt, mreal size)
void mgl_putsw_dir (HMGL gr, mreal x, mreal y, mreal z, mreal dx,   [C function]
        mreal dy, mreal dz, const wchar_t *text, const char *fnt, mreal size)
</pre>
The function plots the string *text* at position *p* along direction *d* with specified *size*. Parameter *fnt* set text style and text position: above ('T') or under ('t') the line.

<pre>
fgets x y 'fname' [n=0 'fnt'='" size=-1.4]   [MGL command]
fgets x y z 'fname' [n=0 'fnt'='" size=-1.4]   [MGL command]
</pre>
Draws unrotated *n*-th line of file *fname* at position $\{x,y,z\}$ with specified *size*. By default parameters from [font], page 139 command are used.

<pre>
text ydat 'text' ['fnt'=']   [MGL command]
text xdat ydat 'text' ['fnt'=']   [MGL command]
text xdat ydat zdat 'text' ['fnt'=']   [MGL command]
void Text (const mglDataA &y, const char *text, const   [Method on mglGraph]
        char *fnt="", const char *opt="")
</pre>

void Text (const mglDataA &*y*, const wchar_t **text,   [Method on `mglGraph`]
      const char **fnt="", const char **opt="")
void Text (const mglDataA &*x*, const mglDataA &*y*,   [Method on `mglGraph`]
      const char **text, const char **fnt="", const char **opt="")
void Text (const mglDataA &*x*, const mglDataA &*y*,   [Method on `mglGraph`]
      const wchar_t **text, const char **fnt="", const char **opt="")
void Text (const mglDataA &*x*, const mglDataA &*y*,   [Method on `mglGraph`]
      const mglDataA &*z*, const char **text, const char **fnt="", const char
      **opt="")
void Text (const mglDataA &*x*, const mglDataA &*y*,   [Method on `mglGraph`]
      const mglDataA &*z*, const wchar_t **text, const char **fnt="", const
      char **opt="")
void mgl_text_y (HMGL *gr*, HCDT *y*, const char **text, const char   [C function]
      **fnt, const char **opt)
void mgl_textw_y (HMGL *gr*, HCDT *y*, const wchar_t **text, const   [C function]
      char **fnt, const char **opt)
void mgl_text_xy (HCDT *x*, HCDT *y*, const char **text, const char   [C function]
      **fnt, const char **opt)
void mgl_textw_xy (HCDT *x*, HCDT *y*, const wchar_t **text, const   [C function]
      char **fnt, const char **opt)
void mgl_text_xyz (HCDT *x*, HCDT *y*, HCDT *z*, const char **text,   [C function]
      const char **fnt, const char **opt)
void mgl_textw_xyz (HCDT *x*, HCDT *y*, HCDT *z*, const wchar_t **text,   [C function]
      const char **fnt, const char **opt)
    The function draws *text* along the curve between points $\{x[i], y[i], z[i]\}$ by font style
    fnt. The string *fnt* may contain symbols 't' for printing the text under the curve (de-
    fault), or 'T' for printing the text above the curve. The sizes of 1st dimension must
    be equal for all arrays `x.nx=y.nx=z.nx`. If array *x* is not specified then its an auto-
    matic array is used with values equidistantly distributed in interval [*Min*.x, *Max*.x]
    (see Section 4.3.1 [Ranges (bounding box)], page 142). If array *z* is not specified then
    $z[i] = Min.z$ is used. String *opt* contain command options (see Section 3.7 [Command
    options], page 132).

4.8 Axis and Colorbar

These functions draw the "things for measuring", like axis with ticks, colorbar with ticks,
grid along axis, bounding box and labels for axis. For more information see Section 4.3
[Axis settings], page 141.

axis [*'dir'='xyz' 'stl'=*]   [MGL command]
void Axis (const char **dir="xyz", const char **stl="",   [Method on `mglGraph`]
      const char **opt="")
void mgl_axis (HMGL *gr*, const char **dir, const char **stl, const   [C function]
      char **opt)
    Draws axes with ticks (see Section 4.3 [Axis settings], page 141). Parameter *dir* may
    contain:

        • 'xyz' for drawing axis in corresponding direction;

- '`XYZ`' for drawing axis in corresponding direction but with inverted positions of labels;
- '`_`' for disabling tick labels;
- '`U`' for disabling rotation of tick labels;
- '`AKDTVISO`' for drawing arrow at the end of axis;
- '`a`' for forced adjusting of axis ticks.

Styles of ticks and axis can be overrided by using *stl* string. See Section 2.2.2 [Axis and ticks], page 19, for sample code and picture.

colorbar [*'sch'*=”]   [MGL command]
void Colorbar (const char *sch="")   [Method on `mglGraph`]
void mgl_colorbar (HMGL *gr*, const char *sch)   [C function]
    Draws colorbar. Parameter *sch* may contain:

- color scheme (see Section 3.4 [Color scheme], page 128);
- '`<>^_`' for positioning at left, at right, at top or at bottom correspondingly;
- '`I`' for positioning near bounding (by default, is positioned at edges of subplot);
- '`A`' for using absolute coordinates.

See Section 2.2.4 [Colorbars], page 25, for sample code and picture.

colorbar *vdat* [*'sch'*=”]   [MGL command]
void Colorbar (const mglDataA &*v*, const char   [Method on `mglGraph`]
      sch="")
void mgl_colorbar_val (HMGL *gr*, HCDT *v*, const char *sch)   [C function]
    The same as previous but with sharp colors *sch* (current palette if `sch=""`) for values
    v. See Section 2.6.13 [ContD sample], page 75, for sample code and picture.

colorbar *'sch'* x y [`w=1 h=1`]   [MGL command]
void Colorbar (const char *sch*, mreal *x*, mreal *y*,   [Method on `mglGraph`]
      mreal *w*=1, mreal *h*=1)
void mgl_colorbar_ext (HMGL *gr*, const char *sch*, mreal *x*, mreal   [C function]
      y, mreal *w*, mreal *h*)
    The same as first one but at arbitrary position of subplot {*x*, *y*} (supposed to be in
    range [0,1]). Parameters *w*, *h* set the relative width and height of the colorbar.

colorbar *vdat 'sch'* x y [`w=1 h=1`]   [MGL command]
void Colorbar (const mglDataA &*v*, const char *sch*,   [Method on `mglGraph`]
      mreal *x*, mreal *y*, mreal *w*=1, mreal *h*=1)
void mgl_colorbar_val_ext (HMGL *gr*, HCDT *v*, const char *sch*,   [C function]
      mreal *x*, mreal *y*, mreal *w*, mreal *h*)
    The same as previous but with sharp colors *sch* (current palette if `sch=""`) for values
    v. See Section 2.6.13 [ContD sample], page 75, for sample code and picture.

grid [*'dir'*=*'xyz'* *'pen'*=*'B'*]   [MGL command]
void Grid (const char *dir*="xyz", const char   [Method on `mglGraph`]
      pen="B", const char *opt*="")

void **mgl_axis_grid** (HMGL *gr*, const char **dir*, const char **pen*,   [C function]
        const char **opt*)
>   Draws grid lines perpendicular to direction determined by string parameter *dir*. The
>   step of grid lines is the same as tick step for [axis], page 163. The style of lines is
>   determined by *pen* parameter (default value is dark blue solid line 'B-').

box ['*stl*'='*k*' **ticks=on**]   [MGL command]
void **Box** (const char **col*="", bool *ticks*=**true**)   [Method on mglGraph]
void **mgl_box** (HMGL *gr*, int *ticks*)   [C function]
void **mgl_box_str** (HMGL *gr*, const char **col*, int *ticks*)   [C function]
>   Draws bounding box outside the plotting volume with color *col*. If *col* contain '@'
>   then filled faces are drawn. At this first color is used for faces (default is light yellow),
>   last one for edges. See Section 2.2.5 [Bounding box], page 26, for sample code and
>   picture.

xlabel '*text*' [**pos=1**]   [MGL command]
ylabel '*text*' [**pos=1**]   [MGL command]
zlabel '*text*' [**pos=1**]   [MGL command]
tlabel '*text*' [**pos=1**]   [MGL command]
void **Label** (char *dir*, const char **text*, mreal *pos*=1,   [Method on mglGraph]
        const char **opt*="")
void **Label** (char *dir*, const wchar_t **text*, mreal *pos*=1,   [Method on mglGraph]
        const char **opt*="")
void **mgl_label** (HMGL *gr*, char *dir*, const char **text*, mreal *pos*,   [C function]
        const char **opt*)
void **mgl_labelw** (HMGL *gr*, char *dir*, const wchar_t **text*, mreal   [C function]
        pos, const char **opt*)
>   Prints the label *text* for axis *dir*='x','y','z','t' (here 't' is "ternary" axis $t = 1-x-y$).
>   The position of label is determined by *pos* parameter. If *pos*=0 then label is printed
>   at the center of axis. If *pos*>0 then label is printed at the maximum of axis. If *pos*<0
>   then label is printed at the minimum of axis. Value option set additional shifting of
>   the label. See Section 4.7 [Text printing], page 161.

4.9 Legend

These functions draw legend to the graph (useful for Section 4.10 [1D plotting], page 167).
Legend entry is a pair of strings: one for style of the line, another one with description text
(with included TeX parsing). The arrays of strings may be used directly or by accumulating
first to the internal arrays (by function [addlegend], page 166) and further plotting it. The
position of the legend can be selected automatic or manually (even out of bounding box).
Parameters *fnt* and *size* specify the font style and size (see Section 4.2.6 [Font settings],
page 139). Parameter *llen* set the relative width of the line sample and the text indent. If
line style string for entry is empty then the corresponding text is printed without indent.
Parameter *fnt* may contain:

- font style for legend text;
- 'A' for positioning in absolute coordinates;
- '#' for drawing box around legend;

- colors for background (first one) and border (second one) of legend. Note, that last color is always used as color for legend text.

See Section 2.2.8 [Legend sample], page 31, for sample code and picture.

---

legend [pos=3 *'fnt'='#'*]   [MGL command]
void Legend (int *pos*=0x3, const char **fnt*="#", const   [Method on `mglGraph`]
    char **opt*="")
void mgl_legend (HMGL *gr*, int *pos*, const char **fnt*, const char   [C function]
    *opt)

    Draws legend of accumulated legend entries by font *fnt* with *size*. Parameter *pos* sets the position of the legend: '0' is bottom left corner, '1' is bottom right corner, '2' is top left corner, '3' is top right corner (is default). Parameter *fnt* can contain colors for face (1st one), for border (2nd one) and for text (last one). If less than 3 colors are specified then the color for border is black (for 2 and less colors), and the color for face is white (for 1 or none colors). If string *fnt* contain '#' then border around the legend is drawn. If string *fnt* contain '-' then legend entries will arranged horizontally.

---

legend x y [*'fnt'='#'*]   [MGL command]
void Legend (mreal *x*, mreal *y*, const char **fnt*="#",   [Method on `mglGraph`]
    const char **opt*="")
void mgl_legend_pos (HMGL *gr*, mreal *x*, mreal *y*, const char **fnt*,   [C function]
    const char **opt*)

    Draws legend of accumulated legend entries by font *fnt* with *size*. Position of legend is determined by parameter *x*, *y* which supposed to be normalized to interval [0,1].

---

addlegend *'text' 'stl'*   [MGL command]
void AddLegend (const char **text*, const char **style*)   [Method on `mglGraph`]
void AddLegend (const wchar_t **text*, const char   [Method on `mglGraph`]
    *style)
void mgl_add_legend (HMGL *gr*, const char **text*, const char   [C function]
    *style)
void mgl_add_legendw (HMGL *gr*, const wchar_t **text*, const char   [C function]
    *style)

    Adds string *text* to internal legend accumulator. The style of described line and mark is specified in string *style* (see Section 3.3 [Line styles], page 127).

---

clearlegend   [MGL command]
void ClearLegend ()   [Method on `mglGraph`]
void mgl_clear_legend (HMGL *gr*)   [C function]

    Clears saved legend strings.

---

legendmarks val   [MGL command]
void SetLegendMarks (int *num*)   [Method on `mglGraph`]
void mgl_set_legend_marks (HMGL *gr*, int *num*)   [C function]

    Set the number of marks in the legend. By default 1 mark is used.

4.10 1D plotting

These functions perform plotting of 1D data. 1D means that data depended from only 1 parameter like parametric curve {x[i],y[i],z[i]}, i=1...n. By default (if absent) values of x[i] are equidistantly distributed in axis range, and z[i]=*Min*.z. The plots are drawn for each row if one of the data is the matrix. By any case the sizes of 1st dimension **must be equal** for all arrays x.nx=y.nx=z.nx.

String *pen* specifies the color and style of line and marks (see Section 3.3 [Line styles], page 127). By default (pen="") solid line with color from palette is used (see Section 4.2.7 [Palette and colors], page 140). Symbol '!' set to use new color from palette for each point (not for each curve, as default). String *opt* contain command options (see Section 3.7 [Command options], page 132). See Section 2.5 [1D samples], page 42, for sample code and picture.

plot *ydat* ['stl'=”]   [MGL command]
plot *xdat ydat* ['stl'=”]   [MGL command]
plot *xdat ydat zdat* ['stl'=”]   [MGL command]
void Plot (const mglDataA &*y*, const char **pen*="",   [Method on mglGraph]
      const char **opt*="")
void Plot (const mglDataA &*x*, const mglDataA &*y*,   [Method on mglGraph]
      const char **pen*="", const char **opt*="")
void Plot (const mglDataA &*x*, const mglDataA &*y*,   [Method on mglGraph]
      const mglDataA &*z*, const char **pen*="", const char **opt*="")
void mgl_plot (HMGL *gr*, HCDT *y*, const char **pen*, const char   [C function]
      *opt)
void mgl_plot_xy (HMGL *gr*, HCDT *x*, HCDT *y*, const char **pen*,   [C function]
      const char **opt*)
void mgl_plot_xyz (HMGL *gr*, HCDT *x*, HCDT *y*, HCDT *z*, const char   [C function]
      *pen, const char **opt*)
    These functions draw continuous lines between points {x[i], y[i], z[i]}. See also [area], page 169, [step], page 167, [stem], page 170, [tube], page 176, [mark], page 173, [error], page 173, [belt], page 178, [tens], page 168, [tape], page 168. See Section 2.5.1 [Plot sample], page 43, for sample code and picture.

radar *adat* ['stl'=”]   [MGL command]
void Radar (const mglDataA &*a*, const char **pen*="",   [Method on mglGraph]
      const char **opt*="")
void mgl_radar (HMGL *gr*, HCDT *a*, const char **pen*, const char   [C function]
      *opt)
    This functions draws radar chart which is continuous lines between points located on an radial lines (like plot in Polar coordinates). Parameter *value* in options *opt* set the additional shift of data (i.e. the data *a*+*value* is used instead of *a*). If value<0 then r=max(0, -min(value). If *pen* containt '#' symbol then "grid" (radial lines and circle for *r*) is drawn. See also [plot], page 167. See Section 2.5.2 [Radar sample], page 44, for sample code and picture.

step *ydat* ['stl'=”]   [MGL command]
step *xdat ydat* ['stl'=”]   [MGL command]

step *xdat ydat zdat* ['stl'='']   [MGL command]
void Step (const mglDataA &*y*, const char *pen*="",   [Method on mglGraph]
      const char *opt*="")
void Step (const mglDataA &*x*, const mglDataA &*y*,   [Method on mglGraph]
      const char *pen*="", const char *opt*="")
void Step (const mglDataA &*x*, const mglDataA &*y*,   [Method on mglGraph]
      const mglDataA &*z*, const char *pen*="", const char *opt*="")
void mgl_step (HMGL *gr*, HCDT *y*, const char *pen*, const char   [C function]
      opt)
void mgl_step_xy (HMGL *gr*, HCDT *x*, HCDT *y*, const char *pen*,   [C function]
      const char *opt*)
void mgl_step_xyz (HMGL *gr*, HCDT *x*, HCDT *y*, HCDT *z*, const char   [C function]
      pen, const char *opt*)

These functions draw continuous stairs for points to axis plane. See also [plot], page 167, [stem], page 170, [tile], page 178, [boxs], page 178. See Section 2.5.3 [Step sample], page 45, for sample code and picture.

tens *ydat cdat* ['stl'='']   [MGL command]
tens *xdat ydat cdat* ['stl'='']   [MGL command]
tens *xdat ydat zdat cdat* ['stl'='']   [MGL command]
void Tens (const mglDataA &*y*, const mglDataA &*c*,   [Method on mglGraph]
      const char *pen*="", const char *opt*="")
void Tens (const mglDataA &*x*, const mglDataA &*y*,   [Method on mglGraph]
      const mglDataA &*c*, const char *pen*="", const char *opt*="")
void Tens (const mglDataA &*x*, const mglDataA &*y*,   [Method on mglGraph]
      const mglDataA &*z*, const mglDataA &*c*, const char *pen*="", const
      char *opt*="")
void mgl_tens (HMGL *gr*, HCDT *y*, HCDT *c*, const char *pen*, const   [C function]
      char *opt*)
void mgl_tens_xy (HMGL *gr*, HCDT *x*, HCDT *y*, HCDT *c*, const char   [C function]
      pen, const char *opt*)
void mgl_tens_xyz (HMGL *gr*, HCDT *x*, HCDT *y*, HCDT *z*, HCDT *c*, const   [C function]
      char *pen*, const char *opt*)

These functions draw continuous lines between points {$x[i]$, $y[i]$, $z[i]$} with color defined by the special array $c[i]$ (look like tension plot). String *pen* specifies the color scheme (see Section 3.4 [Color scheme], page 128) and style and/or width of line (see Section 3.3 [Line styles], page 127). See also [plot], page 167, [mesh], page 177, [fall], page 177. See Section 2.5.4 [Tens sample], page 46, for sample code and picture.

tape *ydat* ['stl'='']   [MGL command]
tape *xdat ydat* ['stl'='']   [MGL command]
tape *xdat ydat zdat* ['stl'='']   [MGL command]
void Tape (const mglDataA &*y*, const char *pen*="",   [Method on mglGraph]
      const char *opt*="")
void Tape (const mglDataA &*x*, const mglDataA &*y*,   [Method on mglGraph]
      const char *pen*="", const char *opt*="")
void Tape (const mglDataA &*x*, const mglDataA &*y*,   [Method on mglGraph]
      const mglDataA &*z*, const char *pen*="", const char *opt*="")

void mgl_tape (HMGL *gr*, HCDT *y*, const char **pen, const char   [C function]
          **opt)
void mgl_tape_xy (HMGL *gr*, HCDT *x*, HCDT *y*, const char **pen,   [C function]
          const char **opt)
void mgl_tape_xyz (HMGL *gr*, HCDT *x*, HCDT *y*, HCDT *z*, const char   [C function]
          **pen, const char **opt)

> These functions draw tapes of normals for curve between points $\{x[i], y[i], z[i]\}$. Initial
> tape(s) was selected in x-y plane (for 'x' in *pen*) and/or y-z plane (for 'x' in *pen*).
> The width of tape is proportional to [barwidth], page 137. See also [plot], page 167,
> [flow], page 192, [barwidth], page 137. See Section 2.5.20 [Tape sample], page 61, for
> sample code and picture.

area *ydat* ['stl'=”]   [MGL command]
area *xdat ydat* ['stl'=”]   [MGL command]
area *xdat ydat zdat* ['stl'=”]   [MGL command]
void Area (const mglDataA &*y*, const char **pen="",   [Method on mglGraph]
          const char **opt="")
void Area (const mglDataA &*x*, const mglDataA &*y*,   [Method on mglGraph]
          const char **pen="", const char **opt="")
void Area (const mglDataA &*x*, const mglDataA &*y*,   [Method on mglGraph]
          const mglDataA &*z*, const char **pen="", const char **opt="")
void mgl_area (HMGL *gr*, HCDT *y*, const char **pen, const char   [C function]
          **opt)
void mgl_area_xy (HMGL *gr*, HCDT *x*, HCDT *y*, const char **pen,   [C function]
          const char **opt)
void mgl_area_xyz (HMGL *gr*, HCDT *x*, HCDT *y*, HCDT *z*, const char   [C function]
          **pen, const char **opt)

> These functions draw continuous lines between points and fills it to axis plane. Also
> you can use gradient filling if number of specified colors is equal to 2*number of curves.
> See also [plot], page 167, [bars], page 170, [stem], page 170, [region], page 169. See
> Section 2.5.5 [Area sample], page 47, for sample code and picture.

region *ydat1 ydat2* ['stl'=”]   [MGL command]
region *xdat ydat1 ydat2* ['stl'=”]   [MGL command]
void Region (const mglDataA &*y1*, const mglDataA &*y2*,   [Method on mglGraph]
          const char **pen="", const char **opt="")
void Region (const mglDataA &*x*, const mglDataA &*y1*,   [Method on mglGraph]
          const mglDataA &*y2*, const char **pen="", const char **opt="")
void mgl_region (HMGL *gr*, HCDT *y1*, HCDT *y2*, const char **pen,   [C function]
          const char **opt)
void mgl_region_xy (HMGL *gr*, HCDT *x*, HCDT *y1*, HCDT *y2*, const   [C function]
          char **pen, const char **opt)

> These functions fill area between 2 curves. Dimensions of arrays *y1* and *y2* must
> be equal. Also you can use gradient filling if number of specified colors is equal to
> 2*number of curves. If *pen* contain symbol 'i' then only area with y1<y<y2 will be
> filled else the area with y2<y<y1 will be filled too. See also [area], page 169, [bars],
> page 170, [stem], page 170. See Section 2.5.6 [Region sample], page 48, for sample
> code and picture.

stem *ydat* ['stl'=']   [MGL command]
stem *xdat ydat* ['stl'=']   [MGL command]
stem *xdat ydat zdat* ['stl'=']   [MGL command]
void Stem (const mglDataA &*y*, const char **pen*="",   [Method on mglGraph]
     const char **opt*="")
void Stem (const mglDataA &*x*, const mglDataA &*y*,   [Method on mglGraph]
     const char **pen*="", const char **opt*="")
void Stem (const mglDataA &*x*, const mglDataA &*y*,   [Method on mglGraph]
     const mglDataA &*z*, const char **pen*="", const char **opt*="")
void mgl_stem (HMGL *gr*, HCDT *y*, const char **pen*, const char   [C function]
     *opt)
void mgl_stem_xy (HMGL *gr*, HCDT *x*, HCDT *y*, const char **pen*,   [C function]
     const char **opt*)
void mgl_stem_xyz (HMGL *gr*, HCDT *x*, HCDT *y*, HCDT *z*, const char   [C function]
     *pen, const char **opt*)

    These functions draw vertical lines from points to axis plane. See also [area], page 169,
    [bars], page 170, [plot], page 167, [mark], page 173. See Section 2.5.7 [Stem sample],
    page 49, for sample code and picture.

bars *ydat* ['stl'=']   [MGL command]
bars *xdat ydat* ['stl'=']   [MGL command]
bars *xdat ydat zdat* ['stl'=']   [MGL command]
void Bars (const mglDataA &*y*, const char **pen*="",   [Method on mglGraph]
     const char **opt*="")
void Bars (const mglDataA &*x*, const mglDataA &*y*,   [Method on mglGraph]
     const char **pen*="", const char **opt*="")
void Bars (const mglDataA &*x*, const mglDataA &*y*,   [Method on mglGraph]
     const mglDataA &*z*, const char **pen*="", const char **opt*="")
void mgl_bars (HMGL *gr*, HCDT *y*, const char **pen*, const char   [C function]
     *opt)
void mgl_bars_xy (HMGL *gr*, HCDT *x*, HCDT *y*, const char **pen*,   [C function]
     const char **opt*)
void mgl_bars_xyz (HMGL *gr*, HCDT *x*, HCDT *y*, HCDT *z*, const char   [C function]
     *pen, const char **opt*)

    These functions draw vertical bars from points to axis plane. If string *pen* contain
    symbol 'a' then lines are drawn one above another (like summation). If string contain
    symbol 'f' then waterfall chart is drawn for determining the cumulative effect of
    sequentially introduced positive or negative values. You can give different colors for
    positive and negative values if number of specified colors is equal to 2*number of
    curves. See also [barh], page 170, [cones], page 171, [area], page 169, [stem], page 170,
    [chart], page 171, [barwidth], page 137. See Section 2.5.8 [Bars sample], page 50, for
    sample code and picture.

barh *vdat* ['stl'=']   [MGL command]
barh *ydat vdat* ['stl'=']   [MGL command]
void Barh (const mglDataA &*v*, const char **pen*="",   [Method on mglGraph]
     const char **opt*="")

void **Barh** (const `mglDataA` &*y*, const `mglDataA` &*v*,   [Method on `mglGraph`]
        const char **pen*="", const char **opt*="")
void **mgl_barh** (HMGL *gr*, HCDT *v*, const char **pen*, const char   [C function]
        *opt)
void **mgl_barh_xy** (HMGL *gr*, HCDT *y*, HCDT *v*, const char **pen*,   [C function]
        const char **opt*)
>   These functions draw horizontal bars from points to axis plane. If string contain
>   symbol 'a' then lines are drawn one above another (like summation). If string contain
>   symbol 'f' then waterfall chart is drawn for determining the cumulative effect of
>   sequentially introduced positive or negative values. You can give different colors
>   for positive and negative values if number of specified colors is equal to 2*number
>   of curves. See also [bars], page 170, [barwidth], page 137. See Section 2.5.9 [Barh
>   sample], page 51, for sample code and picture.

cones *ydat* ['*stl*'="]   [MGL command]
cones *xdat ydat* ['*stl*'="]   [MGL command]
cones *xdat ydat zdat* ['*stl*'="]   [MGL command]
void **Cones** (const `mglDataA` &*y*, const char **pen*="",   [Method on `mglGraph`]
        const char **opt*="")
void **Cones** (const `mglDataA` &*x*, const `mglDataA` &*y*,   [Method on `mglGraph`]
        const char **pen*="", const char **opt*="")
void **Cones** (const `mglDataA` &*x*, const `mglDataA` &*y*,   [Method on `mglGraph`]
        const `mglDataA` &*z*, const char **pen*="", const char **opt*="")
void **mgl_cones** (HMGL *gr*, HCDT *y*, const char **pen*, const char   [C function]
        *opt)
void **mgl_cones_xy** (HMGL *gr*, HCDT *x*, HCDT *y*, const char **pen*,   [C function]
        const char **opt*)
void **mgl_cones_xyz** (HMGL *gr*, HCDT *x*, HCDT *y*, HCDT *z*, const char   [C function]
        *pen, const char **opt*)
>   These functions draw cones from points to axis plane. If string contain symbol 'a' then
>   cones are drawn one above another (like summation). You can give different colors
>   for positive and negative values if number of specified colors is equal to 2*number
>   of curves. See also [bars], page 170, [barwidth], page 137. See Section 2.5.10 [Cones
>   sample], page 52, for sample code and picture.

chart *adat* ['*col*'="]   [MGL command]
void **Chart** (const `mglDataA` &*a*, const char **col*="",   [Method on `mglGraph`]
        const char **opt*="")
void **mgl_chart** (HMGL *gr*, HCDT *a*, const char **col*, const char   [C function]
        *opt)
>   The function draws colored stripes (boxes) for data in array *a*. The number of stripes
>   is equal to the number of rows in *a* (equal to *a.ny*). The color of each next stripe is
>   cyclically changed from colors specified in string *col* or in palette Pal (see Section 4.2.7
>   [Palette and colors], page 140). Spaces in colors denote transparent "color" (i.e.
>   corresponding stripe(s) are not drawn). The stripe width is proportional to value of
>   element in *a*. Chart is plotted only for data with non-negative elements. If string *col*
>   have symbol '#' then black border lines are drawn. The most nice form the chart have

in 3d (after rotation of coordinates) or in cylindrical coordinates (becomes so called Pie chart). See Section 2.5.11 [Chart sample], page 53, for sample code and picture.

boxplot *adat* ['stl'="]	[MGL command]
boxplot *xdat adat* ['stl'="]	[MGL command]
void BoxPlot (const mglDataA &*a*, const char **pen="",	[Method on mglGraph]
const char **opt="")	
void BoxPlot (const mglDataA &*x*, const mglDataA &*a*,	[Method on mglGraph]
const char **pen="", const char **opt="")	
void mgl_boxplot (HMGL *gr*, HCDT *a*, const char **pen, const char	[C function]
**opt)	
void mgl_boxplot_xy (HMGL *gr*, HCDT *x*, HCDT *a*, const char **pen,	[C function]
const char **opt)	

These functions draw boxplot (also known as a box-and-whisker diagram) at points $x[i]$. This is five-number summaries of data $a[i,j]$ (minimum, lower quartile (Q1), median (Q2), upper quartile (Q3) and maximum) along second (j-th) direction. See also [plot], page 167, [error], page 173, [bars], page 170, [barwidth], page 137. See Section 2.5.12 [BoxPlot sample], page 54, for sample code and picture.

candle *vdat1* ['stl'="]	[MGL command]
candle *vdat1 vdat2* ['stl'="]	[MGL command]
candle *vdat1 ydat1 ydat2* ['stl'="]	[MGL command]
candle *vdat1 vdat2 ydat1 ydat2* ['stl'="]	[MGL command]
candle *xdat vdat1 vdat2 ydat1 ydat2* ['stl'="]	[MGL command]
void Candle (const mglDataA &*v1*, const char **pen="",	[Method on mglGraph]
const char **opt="")	
void Candle (const mglDataA &*v1*, const mglDataA &*v2*,	[Method on mglGraph]
const char **pen="", const char **opt="")	
void Candle (const mglDataA &*v1*, const mglDataA &*y1*,	[Method on mglGraph]
const mglDataA &*y2*, const char **pen="", const char **opt="")	
void Candle (const mglDataA &*v1*, const mglDataA &*v2*,	[Method on mglGraph]
const mglDataA &*y1*, const mglDataA &*y2*, const char **pen="", const	
char **opt="")	
void Candle (const mglDataA &*x*, const mglDataA &*v1*,	[Method on mglGraph]
const mglDataA &*v2*, const mglDataA &*y1*, const mglDataA &*y2*, const	
char **pen="", const char **opt="")	
void mgl_candle (HMGL *gr*, HCDT *v1*, HCDT *y1*, HCDT *y2*, const char	[C function]
**pen, const char **opt)	
void mgl_candle_yv (HMGL *gr*, HCDT *v1*, HCDT *v2*, HCDT *y1*, HCDT *y2*,	[C function]
const char **pen, const char **opt)	
void mgl_candle_xyv (HMGL *gr*, HCDT *x*, HCDT *v1*, HCDT *v2*, HCDT *y1*,	[C function]
HCDT *y2*, const char **pen, const char **opt)	

These functions draw candlestick chart at points $x[i]$. This is a combination of a line-chart and a bar-chart, in that each bar represents the range of price movement over a given time interval. Wire (or white) candle correspond to price growth $v1[i]<v2[i]$, opposite case – solid (or dark) candle. "Shadows" show the minimal $y1$ and maximal $y2$ prices. If $v2$ is absent then it is determined as $v2[i]=v1[i+1]$. See also [plot],

error *ydat yerr* ['*stl*='"]   [MGL command]
error *xdat ydat yerr* ['*stl*='"]   [MGL command]
error *xdat ydat xerr yerr* ['*stl*='"]   [MGL command]
void Error (const mglDataA &*y*, const mglDataA &*ey*,   [Method on mglGraph]
        const char **pen*="", const char **opt*="")
void Error (const mglDataA &*x*, const mglDataA &*y*,   [Method on mglGraph]
        const mglDataA &*ey*, const char **pen*="", const char **opt*="")
void Error (const mglDataA &*x*, const mglDataA &*y*,   [Method on mglGraph]
        const mglDataA &*ex*, const mglDataA &*ey*, const char **pen*="", const
        char **opt*="")
void mgl_error (HMGL *gr*, HCDT *y*, HCDT *ey*, const char **pen*, const   [C function]
        char **opt*)
void mgl_error_xy (HMGL *gr*, HCDT *x*, HCDT *y*, HCDT *ey*, const char   [C function]
        *pen, const char **opt*)
void mgl_error_exy (HMGL *gr*, HCDT *x*, HCDT *y*, HCDT *ex*, HCDT *ey*,   [C function]
        const char **pen*, const char **opt*)

These functions draw error boxes $\{ex[i], ey[i]\}$ at points $\{x[i], y[i]\}$. This can be useful, for example, in experimental points, or to show numeric error or some estimations and so on. If string *pen* contain symbol '@' than large semitransparent mark is used instead of error box. See also [plot], page 167, [mark], page 173. See Section 2.5.14 [Error sample], page 55, for sample code and picture.

mark *ydat rdat* ['*stl*='"]   [MGL command]
mark *xdat ydat rdat* ['*stl*='"]   [MGL command]
mark *xdat ydat zdat rdat* ['*stl*='"]   [MGL command]
void Mark (const mglDataA &*y*, const mglDataA &*r*,   [Method on mglGraph]
        const char **pen*="", const char **opt*="")
void Mark (const mglDataA &*x*, const mglDataA &*y*,   [Method on mglGraph]
        const mglDataA &*r*, const char **pen*="", const char **opt*="")
void Mark (const mglDataA &*x*, const mglDataA &*y*,   [Method on mglGraph]
        const mglDataA &*z*, const mglDataA &*r*, const char **pen*="", const
        char **opt*="")
void mgl_mark_y (HMGL *gr*, HCDT *y*, HCDT *r*, const char **pen*, const   [C function]
        char **opt*)
void mgl_mark_xy (HMGL *gr*, HCDT *x*, HCDT *y*, HCDT *r*, const char   [C function]
        *pen, const char **opt*)
void mgl_mark_xyz (HMGL *gr*, HCDT *x*, HCDT *y*, HCDT *z*, HCDT *r*, const   [C function]
        char **pen*, const char **opt*)

These functions draw marks with size $r[i]$*[marksize], page 137 at points $\{x[i], y[i], z[i]\}$. If you need to draw markers of the same size then you can use [plot], page 167 function with empty line style ' '. For markers with size in axis range use [error], page 173 with style '@'. See also [plot], page 167, [textmark], page 174, [error], page 173, [stem], page 170. See Section 2.5.15 [Mark sample], page 56, for sample code and picture.

textmark *ydat* *'txt'* [*'stl'='*]   [MGL command]
textmark *ydat rdat* *'txt'* [*'stl'='*]   [MGL command]
textmark *xdat ydat rdat* *'txt'* [*'stl'='*]   [MGL command]
textmark *xdat ydat zdat rdat* *'txt'* [*'stl'='*]   [MGL command]
void **TextMark** (const mglDataA &*y*, const char **txt,   [Method on `mglGraph`]
       const char **fnt="", const char **opt="")
void **TextMark** (const mglDataA &*y*, const wchar_t **txt,   [Method on `mglGraph`]
       const char **fnt="", const char **opt="")
void **TextMark** (const mglDataA &*y*, const mglDataA &*r*,   [Method on `mglGraph`]
       const char **txt, const char **fnt="", const char **opt="")
void **TextMark** (const mglDataA &*y*, const mglDataA &*r*,   [Method on `mglGraph`]
       const wchar_t **txt, const char **fnt="", const char **opt="")
void **TextMark** (const mglDataA &*x*, const mglDataA &*y*,   [Method on `mglGraph`]
       const mglDataA &*r*, const char **txt, const char **fnt="", const char
       **opt="")
void **TextMark** (const mglDataA &*x*, const mglDataA &*y*,   [Method on `mglGraph`]
       const mglDataA &*r*, const wchar_t **txt, const char **fnt="", const
       char **opt="")
void **TextMark** (const mglDataA &*x*, const mglDataA &*y*,   [Method on `mglGraph`]
       const mglDataA &*z*, const mglDataA &*r*, const char **txt, const char
       **fnt="", const char **opt="")
void **TextMark** (const mglDataA &*x*, const mglDataA &*y*,   [Method on `mglGraph`]
       const mglDataA &*z*, const mglDataA &*r*, const wchar_t **txt, const char
       **fnt="", const char **opt="")
void **mgl_textmark** (HMGL *gr*, HCDT *y*, const char **txt, const char   [C function]
       **fnt, const char **opt)
void **mgl_textmarkw** (HMGL *gr*, HCDT *y*, const wchar_t **txt, const   [C function]
       char **fnt, const char **opt)
void **mgl_textmark_yr** (HMGL *gr*, HCDT *y*, HCDT *r*, const char **txt,   [C function]
       const char **fnt, const char **opt)
void **mgl_textmarkw_yr** (HMGL *gr*, HCDT *y*, HCDT *r*, const wchar_t   [C function]
       **txt, const char **fnt, const char **opt)
void **mgl_textmark_xyr** (HMGL *gr*, HCDT *x*, HCDT *y*, HCDT *r*, const   [C function]
       char **txt, const char **fnt, const char **opt)
void **mgl_textmarkw_xyr** (HMGL *gr*, HCDT *x*, HCDT *y*, HCDT *r*, const   [C function]
       wchar_t **txt, const char **fnt, const char **opt)
void **mgl_textmark_xyzr** (HMGL *gr*, HCDT *x*, HCDT *y*, HCDT *z*, HCDT *r*,   [C function]
       const char **txt, const char **fnt, const char **opt)
void **mgl_textmarkw_xyzr** (HMGL *gr*, HCDT *x*, HCDT *y*, HCDT *z*, HCDT *r*,   [C function]
       const wchar_t **txt, const char **fnt, const char **opt)

These functions draw string *txt* as marks with size proportional to *r*[i]*marksize at points {*x*[i], *y*[i], *z*[i]}. By default (if omitted) *r*[i]=1. See also [plot], page 167, [mark], page 173, [stem], page 170. See Section 2.5.16 [TextMark sample], page 57, for sample code and picture.

label *ydat* *'txt'* [*'stl'='*]   [MGL command]
label *xdat ydat* *'txt'* [*'stl'='*]   [MGL command]

`label` *xdat ydat zdat 'txt'* [*'stl'='*]   [MGL command]
`void Label (const mglDataA &`*y*`, const char *`*txt*`, const`   [Method on `mglGraph`]
         `char *`*fnt*`="", const char *`*opt*`="")`
`void Label (const mglDataA &`*y*`, const wchar_t *`*txt*`,`   [Method on `mglGraph`]
         `const char *`*fnt*`="", const char *`*opt*`="")`
`void Label (const mglDataA &`*x*`, const mglDataA &`*y*`,`   [Method on `mglGraph`]
         `const char *`*txt*`, const char *`*fnt*`="", const char *`*opt*`="")`
`void Label (const mglDataA &`*x*`, const mglDataA &`*y*`,`   [Method on `mglGraph`]
         `const wchar_t *`*txt*`, const char *`*fnt*`="", const char *`*opt*`="")`
`void Label (const mglDataA &`*x*`, const mglDataA &`*y*`,`   [Method on `mglGraph`]
         `const mglDataA &`*z*`, const char *`*txt*`, const char *`*fnt*`="", const char`
         `*`*opt*`="")`
`void Label (const mglDataA &`*x*`, const mglDataA &`*y*`,`   [Method on `mglGraph`]
         `const mglDataA &`*z*`, const wchar_t *`*txt*`, const char *`*fnt*`="", const`
         `char *`*opt*`="")`
`void mgl_label (HMGL `*gr*`, HCDT `*y*`, const char *`*txt*`, const char`   [C function]
         `*`*fnt*`, const char *`*opt*`)`
`void mgl_labelw (HMGL `*gr*`, HCDT `*y*`, const wchar_t *`*txt*`, const`   [C function]
         `char *`*fnt*`, const char *`*opt*`)`
`void mgl_label_xy (HMGL `*gr*`, HCDT `*x*`, HCDT `*y*`, const char *`*txt*`,`   [C function]
         `const char *`*fnt*`, const char *`*opt*`)`
`void mgl_labelw_xy (HMGL `*gr*`, HCDT `*x*`, HCDT `*y*`, const wchar_t *`*txt*`,`   [C function]
         `const char *`*fnt*`, const char *`*opt*`)`
`void mgl_label_xyz (HMGL `*gr*`, HCDT `*x*`, HCDT `*y*`, HCDT `*z*`, const char`   [C function]
         `*`*txt*`, const char *`*fnt*`, const char *`*opt*`)`
`void mgl_labelw_xyz (HMGL `*gr*`, HCDT `*x*`, HCDT `*y*`, HCDT `*z*`, const`   [C function]
         `wchar_t *`*txt*`, const char *`*fnt*`, const char *`*opt*`)`
     These functions draw string *txt* at points {*x*[i], *y*[i], *z*[i]}. If string *txt* contain '`%x`',
     '`%y`', '`%z`' or '`%n`' then it will be replaced by the value of x-,y-,z-coordinate of the point
     or its index. See also [plot], page 167, [mark], page 173, [textmark], page 174, [table],
     page 175. See Section 2.5.17 [Label sample], page 58, for sample code and picture.

`table` *vdat 'txt'* [*'stl'='#'*]   [MGL command]
`table` *x y vdat 'txt'* [*'stl'='#'*]   [MGL command]
`void Table (const mglDataA &`*val*`, const char *`*txt*`,`   [Method on `mglGraph`]
         `const char *`*fnt*`="", const char *`*opt*`="")`
`void Table (const mglDataA &`*val*`, const wchar_t *`*txt*`,`   [Method on `mglGraph`]
         `const char *`*fnt*`="", const char *`*opt*`="")`
`void Table (mreal `*x*`, mreal `*y*`, const mglDataA &`*val*`,`   [Method on `mglGraph`]
         `const char *`*txt*`, const char *`*fnt*`="", const char *`*opt*`="")`
`void Table (mreal `*x*`, mreal `*y*`, const mglDataA &`*val*`,`   [Method on `mglGraph`]
         `const wchar_t *`*txt*`, const char *`*fnt*`="", const char *`*opt*`="")`
`void mgl_table (HMGL `*gr*`, mreal `*x*`, mreal `*y*`, HCDT `*val*`, const char`   [C function]
         `*`*txt*`, const char *`*fnt*`, const char *`*opt*`)`

void mgl_tablew (HMGL *gr*, mreal *x*, mreal *y*, HCDT *val*, const   [C function]
    wchar_t **txt*, const char **fnt*, const char **opt*)
    These functions draw table with values of *val* and captions from string *txt* (separated
    by newline symbol '\n') at points {*x*, *y*} (default at {0,0}) related to current subplot.
    If string *fnt* contain '#' then cell border will be drawn. If string *fnt* contain '|' then
    table width is limited by subplot width (equivalent option 'value 1'). If string *fnt*
    contain '=' then widths of all cells are the same. Option value set the width of the
    table (default is 1). See also [plot], page 167, [label], page 174. See Section 2.5.18
    [Table sample], page 59, for sample code and picture.

tube *ydat rdat* ['*stl*'='']   [MGL command]
tube *ydat* rval ['*stl*'='']   [MGL command]
tube *xdat ydat rdat* ['*stl*'='']   [MGL command]
tube *xdat ydat* rval ['*stl*'='']   [MGL command]
tube *xdat ydat zdat rdat* ['*stl*'='']   [MGL command]
tube *xdat ydat zdat* rval ['*stl*'='']   [MGL command]
void Tube (const mglDataA &*y*, const mglDataA &*r*,   [Method on mglGraph]
    const char **pen*="", const char **opt*="")
void Tube (const mglDataA &*y*, mreal *r*, const char   [Method on mglGraph]
    *pen="", const char **opt*="")
void Tube (const mglDataA &*x*, const mglDataA &*y*,   [Method on mglGraph]
    const mglDataA &*r*, const char **pen*="", const char **opt*="")
void Tube (const mglDataA &*x*, const mglDataA &*y*,   [Method on mglGraph]
    mreal *r*, const char **pen*="", const char **opt*="")
void Tube (const mglDataA &*x*, const mglDataA &*y*,   [Method on mglGraph]
    const mglDataA &*z*, const mglDataA &*r*, const char **pen*="", const
    char **opt*="")
void Tube (const mglDataA &*x*, const mglDataA &*y*,   [Method on mglGraph]
    const mglDataA &*z*, mreal *r*, const char **pen*="", const char **opt*="")
void mgl_tube_r (HMGL *gr*, HCDT *y*, HCDT *r*, const char **pen*, const   [C function]
    char **opt*)
void mgl_tube (HMGL *gr*, HCDT *y*, mreal *r*, const char **pen*, const   [C function]
    char **opt*)
void mgl_tube_xyr (HMGL *gr*, HCDT *x*, HCDT *y*, HCDT *r*, const char   [C function]
    *pen, const char **opt*)
void mgl_tube_xy (HMGL *gr*, HCDT *x*, HCDT *y*, mreal *r*, const char   [C function]
    *pen, const char **opt*)
void mgl_tube_xyzr (HMGL *gr*, HCDT *x*, HCDT *y*, HCDT *z*, HCDT *r*,   [C function]
    const char **pen*, const char **opt*)
void mgl_tube_xyz (HMGL *gr*, HCDT *x*, HCDT *y*, HCDT *z*, mreal *r*,   [C function]
    const char **pen*, const char **opt*)
    These functions draw the tube with variable radius *r*[i] along the curve between points
    {*x*[i], *y*[i], *z*[i]}. See also [plot], page 167. See Section 2.5.19 [Tube sample], page 60,
    for sample code and picture.

torus *rdat zdat* ['*stl*'='']   [MGL command]
void Torus (const mglDataA &*r*, const mglDataA &*z*,   [Method on mglGraph]
    const char **pen*="", const char **opt*="")

void `mgl_torus` (HMGL *gr*, HCDT *r*, HCDT *z*, const char **pen*, const   [C function]
         char **opt*)

> These functions draw surface which is result of curve {*r*, *z*} rotation around axis. If string *pen* contain symbols 'x' or 'z' then rotation axis will be set to specified direction (default is 'y'). If string *pen* have symbol '#' then wire plot is produced. If string *pen* have symbol '.' then plot by dots is produced. See also [plot], page 167, [axial], page 182. See Section 2.5.21 [Torus sample], page 62, for sample code and picture.

4.11 2D plotting

These functions perform plotting of 2D data. 2D means that data depend from 2 independent parameters like matrix $f(x_i, y_j), i = 1...n, j = 1...m$. By default (if absent) values of x, y are equidistantly distributed in axis range. The plots are drawn for each z slice of the data. The minor dimensions of arrays x, y, z should be equal `x.nx=z.nx && y.nx=z.ny` or `x.nx=y.nx=z.nx && x.ny=y.ny=z.ny`. Arrays x and y can be vectors (not matrices as z). String *sch* sets the color scheme (see Section 3.4 [Color scheme], page 128) for plot. String *opt* contain command options (see Section 3.7 [Command options], page 132). See Section 2.6 [2D samples], page 63, for sample code and picture.

`surf` *zdat* ['*sch*'='']   [MGL command]
`surf` *xdat ydat zdat* ['*sch*'='']   [MGL command]
void `Surf` (const mglDataA &*z*, const char **sch*="",   [Method on `mglGraph`]
         const char **opt*="")
void `Surf` (const mglDataA &*x*, const mglDataA &*y*,   [Method on `mglGraph`]
         const mglDataA &*z*, const char **sch*="", const char **opt*="")
void `mgl_surf` (HMGL *gr*, HCDT *z*, const char **sch*, const char **opt*)   [C function]
void `mgl_surf_xy` (HMGL *gr*, HCDT *x*, HCDT *y*, HCDT *z*, const char   [C function]
         *sch, const char **opt*)

> The function draws surface specified parametrically {x[i,j], y[i,j], z[i,j]}. If string *sch* have symbol '#' then grid lines are drawn. If string *sch* have symbol '.' then plot by dots is produced. See also [mesh], page 177, [dens], page 179, [belt], page 178, [tile], page 178, [boxs], page 178, [surfc], page 187, [surfa], page 188. See Section 2.6.1 [Surf sample], page 64, for sample code and picture.

`mesh` *zdat* ['*sch*'='']   [MGL command]
`mesh` *xdat ydat zdat* ['*sch*'='']   [MGL command]
void `Mesh` (const mglDataA &*z*, const char **sch*="",   [Method on `mglGraph`]
         const char **opt*="")
void `Mesh` (const mglDataA &*x*, const mglDataA &*y*,   [Method on `mglGraph`]
         const mglDataA &*z*, const char **sch*="", const char **opt*="")
void `mgl_mesh` (HMGL *gr*, HCDT *z*, const char **sch*, const char **opt*)   [C function]
void `mgl_mesh_xy` (HMGL *gr*, HCDT *x*, HCDT *y*, HCDT *z*, const char   [C function]
         *sch, const char **opt*)

> The function draws mesh lines for surface specified parametrically {x[i,j], y[i,j], z[i,j]}. See also [surf], page 177, [fall], page 177, [meshnum], page 138, [cont], page 179, [tens], page 168. See Section 2.6.4 [Mesh sample], page 67, for sample code and picture.

`fall` *zdat* ['*sch*'='']   [MGL command]
`fall` *xdat ydat zdat* ['*sch*'='']   [MGL command]

void Fall (const mglDataA &*z*, const char *sch="",   [Method on `mglGraph`]
        const char *opt="")
void Fall (const mglDataA &*x*, const mglDataA &*y*,   [Method on `mglGraph`]
        const mglDataA &*z*, const char *sch="", const char *opt="")
void mgl_fall (HMGL *gr*, HCDT *z*, const char *sch, const char *opt)   [C function]
void mgl_fall_xy (HMGL *gr*, HCDT *x*, HCDT *y*, HCDT *z*, const char   [C function]
        *sch, const char *opt)

The function draws fall lines for surface specified parametrically $\{x[i,j],\ y[i,j],\ z[i,j]\}$. This plot can be used for plotting several curves shifted in depth one from another. If *sch* contain 'x' then lines are drawn along x-direction else (by default) lines are drawn along y-direction. See also [belt], page 178, [mesh], page 177, [tens], page 168, [meshnum], page 138. See Section 2.6.5 [Fall sample], page 68, for sample code and picture.

belt *zdat* ['*sch*'='']   [MGL command]
belt *xdat ydat zdat* ['*sch*'='']   [MGL command]
void Belt (const mglDataA &*z*, const char *sch="",   [Method on `mglGraph`]
        const char *opt="")
void Belt (const mglDataA &*x*, const mglDataA &*y*,   [Method on `mglGraph`]
        const mglDataA &*z*, const char *sch="", const char *opt="")
void mgl_belt (HMGL *gr*, HCDT *z*, const char *sch, const char *opt)   [C function]
void mgl_belt_xy (HMGL *gr*, HCDT *x*, HCDT *y*, HCDT *z*, const char   [C function]
        *sch, const char *opt)

The function draws belts for surface specified parametrically $\{x[i,j],\ y[i,j],\ z[i,j]\}$. This plot can be used as 3d generalization of [plot], page 167). If *sch* contain 'x' then belts are drawn along x-direction else (by default) belts are drawn along y-direction. See also [fall], page 177, [surf], page 177, [plot], page 167, [meshnum], page 138. See Section 2.6.6 [Belt sample], page 69, for sample code and picture.

boxs *zdat* ['*sch*'='']   [MGL command]
boxs *xdat ydat zdat* ['*sch*'='']   [MGL command]
void Boxs (const mglDataA &*z*, const char *sch="",   [Method on `mglGraph`]
        const char *opt="")
void Boxs (const mglDataA &*x*, const mglDataA &*y*,   [Method on `mglGraph`]
        const mglDataA &*z*, const char *sch="", const char *opt="")
void mgl_boxs (HMGL *gr*, HCDT *z*, const char *sch, const char *opt)   [C function]
void mgl_boxs_xy (HMGL *gr*, HCDT *x*, HCDT *y*, HCDT *z*, const char   [C function]
        *sch, const char *opt)

The function draws vertical boxes for surface specified parametrically $\{x[i,j],\ y[i,j],\ z[i,j]\}$. Symbol '@' in *sch* set to draw filled boxes. See also [surf], page 177, [dens], page 179, [tile], page 178, [step], page 167. See Section 2.6.7 [Boxs sample], page 70, for sample code and picture.

tile *zdat* ['*sch*'='']   [MGL command]
tile *xdat ydat zdat* ['*sch*'='']   [MGL command]
void Tile (const mglDataA &*z*, const char *sch="",   [Method on `mglGraph`]
        const char *opt="")

void Tile (const mglDataA &*x*, const mglDataA &*y*,   [Method on mglGraph]
     const mglDataA &*z*, const char **sch="", const char **opt="")
void mgl_tile (HMGL *gr*, HCDT *z*, const char **sch, const char **opt)   [C function]
void mgl_tile_xy (HMGL *gr*, HCDT *x*, HCDT *y*, HCDT *z*, const char   [C function]
    *sch, const char **opt)

    The function draws horizontal tiles for surface specified parametrically $\{x[i,j],\ y[i,j],$ $z[i,j]\}$. Such plot can be used as 3d generalization of [step], page 167. See also [surf], page 177, [boxs], page 178, [step], page 167, [tiles], page 189. See Section 2.6.8 [Tile sample], page 71, for sample code and picture.

dens *zdat* ['*sch*'="]   [MGL command]
dens *xdat ydat zdat* ['*sch*'="]   [MGL command]
void Dens (const mglDataA &*z*, const char **sch="",   [Method on mglGraph]
     const char **opt="", mreal *zVal*=NAN)
void Dens (const mglDataA &*x*, const mglDataA &*y*,   [Method on mglGraph]
     const mglDataA &*z*, const char **sch="", const char **opt="", mreal
     zVal=NAN)
void mgl_dens (HMGL *gr*, HCDT *z*, const char **sch, const char **opt)   [C function]
void mgl_dens_xy (HMGL *gr*, HCDT *x*, HCDT *y*, HCDT *z*, const char   [C function]
    *sch, const char **opt)

    The function draws density plot for surface specified parametrically $\{x[i,j],\ y[i,j],\ z[i,j]\}$ at $z = Min.z$. If string *sch* have symbol '#' then grid lines are drawn. If string *sch* have symbol '.' then plot by dots is produced. See also [surf], page 177, [cont], page 179, [contf], page 180, [boxs], page 178, [tile], page 178, dens[xyz]. See Section 2.6.10 [Dens sample], page 72, for sample code and picture.

cont *vdat zdat* ['*sch*'="]   [MGL command]
cont *vdat xdat ydat zdat* ['*sch*'="]   [MGL command]
void Cont (const mglDataA &*v*, const mglDataA &*z*,   [Method on mglGraph]
     const char **sch="", const char **opt="")
void Cont (const mglDataA &*v*, const mglDataA &*x*,   [Method on mglGraph]
     const mglDataA &*y*, const mglDataA &*z*, const char **sch="", const
     char **opt="")
void mgl_cont__val (HMGL *gr*, HCDT *v*, HCDT *z*, const char **sch,   [C function]
     const char **opt)
void mgl_cont_xy_val (HMGL *gr*, HCDT *v*, HCDT *x*, HCDT *y*, HCDT *z*,   [C function]
     const char **sch, const char **opt)

    The function draws contour lines for surface specified parametrically $\{x[i,j],\ y[i,j],$ $z[i,j]\}$ at $z=v[k]$ or at $z = Min.z$ if *sch* contain symbol '_'. Contours are plotted for $z[i,j]=v[k]$ where $v[k]$ are values of data array *v*. If string *sch* have symbol 't' or 'T' then contour labels $v[k]$ will be drawn below (or above) the contours. See also [dens], page 179, [contf], page 180, [contd], page 180, [axial], page 182, cont[xyz]. See Section 2.6.11 [Cont sample], page 73, for sample code and picture.

cont *zdat* ['*sch*'="]   [MGL command]
cont *xdat ydat zdat* ['*sch*'="]   [MGL command]
void Cont (const mglDataA &*z*, const char **sch="",   [Method on mglGraph]
     const char **opt="")

void Cont (const mglDataA &*x*, const mglDataA &*y*,   [Method on mglGraph]
      const mglDataA &*z*, const char **sch*="", const char **opt*="")

void mgl_cont (HMGL *gr*, HCDT *z*, const char **sch*, const char **opt*)   [C function]

void mgl_cont_xy (HMGL *gr*, HCDT *x*, HCDT *y*, HCDT *z*, const char   [C function]
      *sch, const char **opt*)

> The same as previous with vector *v* of *num*-th elements equidistantly distributed in color range. Here *num* is equal to parameter *value* in options *opt* (default is 7).

contf *vdat zdat* ['sch'=”]   [MGL command]

contf *vdat xdat ydat zdat* ['sch'=”]   [MGL command]

void ContF (const mglDataA &*v*, const mglDataA &*z*,   [Method on mglGraph]
      const char **sch*="", const char **opt*="")

void ContF (const mglDataA &*v*, const mglDataA &*x*,   [Method on mglGraph]
      const mglDataA &*y*, const mglDataA &*z*, const char **sch*="", const
      char **opt*="")

void mgl_contf_val (HMGL *gr*, HCDT *v*, HCDT *z*, const char **sch*,   [C function]
      const char **opt*)

void mgl_contf_xy_val (HMGL *gr*, HCDT *v*, HCDT *x*, HCDT *y*, HCDT *z*, [C function]
      const char **sch*, const char **opt*)

> The function draws solid (or filled) contour lines for surface specified parametrically $\{x[i,j], y[i,j], z[i,j]\}$ at $z=v[k]$ or at $z = Min.z$ if *sch* contain symbol '_'. Contours are plotted for $z[i,j]=v[k]$ where $v[k]$ are values of data array *v* (must be v.nx>2). See also [dens], page 179, [cont], page 179, [contd], page 180, contf[xyz]. See Section 2.6.12 [ContF sample], page 74, for sample code and picture.

contf *zdat* ['sch'=”]   [MGL command]

contf *xdat ydat zdat* ['sch'=”]   [MGL command]

void ContF (const mglDataA &*z*, const char **sch*="",   [Method on mglGraph]
      const char **opt*="")

void ContF (const mglDataA &*x*, const mglDataA &*y*,   [Method on mglGraph]
      const mglDataA &*z*, const char **sch*="", const char **opt*="")

void mgl_contf (HMGL *gr*, HCDT *z*, const char **sch*, const char   [C function]
      *opt)

void mgl_contf_xy (HMGL *gr*, HCDT *x*, HCDT *y*, HCDT *z*, const char   [C function]
      *sch, const char **opt*)

> The same as previous with vector *v* of *num*-th elements equidistantly distributed in color range. Here *num* is equal to parameter *value* in options *opt* (default is 7).

contd *vdat zdat* ['sch'=”]   [MGL command]

contd *vdat xdat ydat zdat* ['sch'=”]   [MGL command]

void ContD (const mglDataA &*v*, const mglDataA &*z*,   [Method on mglGraph]
      const char **sch*="", const char **opt*="")

void ContD (const mglDataA &*v*, const mglDataA &*x*,   [Method on mglGraph]
      const mglDataA &*y*, const mglDataA &*z*, const char **sch*="", const
      char **opt*="")

void mgl_contd_val (HMGL *gr*, HCDT *v*, HCDT *z*, const char **sch*,   [C function]
      const char **opt*)

void `mgl_contd_xy_val` (HMGL *gr*, HCDT *v*, HCDT *x*, HCDT *y*, HCDT *z*,   [C function]
        const char **sch*, const char **opt*)

The function draws solid (or filled) contour lines for surface specified parametrically
$\{x[i,j], y[i,j], z[i,j]\}$ at $z=v[k]$ (or at $z = Min.z$ if *sch* contain symbol '_') with manual
colors. Contours are plotted for $z[i,j]=v[k]$ where $v[k]$ are values of data array *v* (must
be `v.nx>2`). String *sch* sets the contour colors: the color of k-th contour is determined
by character `sch[k%strlen(sch)]`. See also [dens], page 179, [cont], page 179, [contf],
page 180. See Section 2.6.13 [ContD sample], page 75, for sample code and picture.

contd *zdat* $\left['sch'=\right.$”]   [MGL command]
contd *xdat ydat zdat* $\left['sch'=\right.$”]   [MGL command]
void `ContD` (const mglDataA &*z*, const char **sch*="",   [Method on `mglGraph`]
        const char **opt*="")
void `ContD` (const mglDataA &*x*, const mglDataA &*y*,   [Method on `mglGraph`]
        const mglDataA &*z*, const char **sch*="", const char **opt*="")
void `mgl_contd` (HMGL *gr*, HCDT *z*, const char **sch*, const char   [C function]
        *opt)
void `mgl_contd_xy` (HMGL *gr*, HCDT *x*, HCDT *y*, HCDT *z*, const char   [C function]
        *sch, const char **opt*)

The same as previous with vector *v* of *num*-th elements equidistantly distributed in
color range. Here *num* is equal to parameter *value* in options *opt* (default is 7).

contv *vdat zdat* $\left['sch'=\right.$”]   [MGL command]
contv *vdat xdat ydat zdat* $\left['sch'=\right.$”]   [MGL command]
void `ContV` (const mglDataA &*v*, const mglDataA &*z*,   [Method on `mglGraph`]
        const char **sch*="", const char **opt*="")
void `ContV` (const mglDataA &*v*, const mglDataA &*x*,   [Method on `mglGraph`]
        const mglDataA &*y*, const mglDataA &*z*, const char **sch*="", const
        char **opt*="")
void `mgl_contv_val` (HMGL *gr*, HCDT *v*, HCDT *z*, const char **sch*,   [C function]
        const char **opt*)
void `mgl_contv_xy_val` (HMGL *gr*, HCDT *v*, HCDT *x*, HCDT *y*, HCDT *z*,   [C function]
        const char **sch*, const char **opt*)

The function draws vertical cylinder (tube) at contour lines for surface specified para-
metrically $\{x[i,j], y[i,j], z[i,j]\}$ at $z=v[k]$ or at $z = Min.z$ if *sch* contain symbol '_'.
Contours are plotted for $z[i,j]=v[k]$ where $v[k]$ are values of data array *v*. See also
[cont], page 179, [contf], page 180. See Section 2.6.14 [ContV sample], page 76, for
sample code and picture.

contv *zdat* $\left['sch'=\right.$”]   [MGL command]
contv *xdat ydat zdat* $\left['sch'=\right.$”]   [MGL command]
void `ContV` (const mglDataA &*z*, const char **sch*="",   [Method on `mglGraph`]
        const char **opt*="")
void `ContV` (const mglDataA &*x*, const mglDataA &*y*,   [Method on `mglGraph`]
        const mglDataA &*z*, const char **sch*="", const char **opt*="")
void `mgl_contv` (HMGL *gr*, HCDT *z*, const char **sch*, const char   [C function]
        *opt)

void mgl_contv_xy (HMGL *gr*, HCDT *x*, HCDT *y*, HCDT *z*, const char   [C function]
        **sch, const char **opt)
    The same as previous with vector *v* of *num*-th elements equidistantly distributed in
    color range. Here *num* is equal to parameter *value* in options *opt* (default is 7).

axial *vdat zdat* [*'sch'=*"]   [MGL command]
axial *vdat xdat ydat zdat* [*'sch'=*"]   [MGL command]
void Axial (const mglDataA &*v*, const mglDataA &*z*,   [Method on mglGraph]
        const char **sch="", const char **opt="")
void Axial (const mglDataA &*v*, const mglDataA &*x*,   [Method on mglGraph]
        const mglDataA &*y*, const mglDataA &*z*, const char **sch="", const
        char **opt="")
void mgl_axial_val (HMGL *gr*, HCDT *v*, HCDT *z*, const char **sch,   [C function]
        const char **opt)
void mgl_axial_xy_val (HMGL *gr*, HCDT *v*, HCDT *x*, HCDT *y*, HCDT *z*,   [C function]
        const char **sch, const char **opt)
    The function draws surface which is result of contour plot rotation for surface specified
    parametrically $\{x[i,j], y[i,j], z[i,j]\}$. Contours are plotted for $z[i,j]=v[k]$ where $v[k]$ are
    values of data array *v*. If string *sch* have symbol '#' then wire plot is produced. If
    string *sch* have symbol '.' then plot by dots is produced. If string contain symbols 'x'
    or 'z' then rotation axis will be set to specified direction (default is 'y'). See also [cont],
    page 179, [contf], page 180, [torus], page 176, [surf3], page 183. See Section 2.6.15
    [Axial sample], page 77, for sample code and picture.

axial *zdat* [*'sch'=*"]   [MGL command]
axial *xdat ydat zdat* [*'sch'=*"]   [MGL command]
void Axial (const mglDataA &*z*, const char **sch="",   [Method on mglGraph]
        const char **opt="", int *num*=3)
void Axial (const mglDataA &*x*, const mglDataA &*y*,   [Method on mglGraph]
        const mglDataA &*z*, const char **sch="", const char **opt="", int
        num=3)
void mgl_axial (HMGL *gr*, HCDT *z*, const char **sch, const char   [C function]
        **opt)
void mgl_axial_xy (HMGL *gr*, HCDT *x*, HCDT *y*, HCDT *z*, const char   [C function]
        **sch, const char **opt)
    The same as previous with vector *v* of *num*-th elements equidistantly distributed in
    color range. Here *num* is equal to parameter *value* in options *opt* (default is 3).

grid2 *zdat* [*'sch'=*"]   [MGL command]
grid2 *xdat ydat zdat* [*'sch'=*"]   [MGL command]
void Grid (const mglDataA &*z*, const char **sch="",   [Method on mglGraph]
        const char **opt="")
void Grid (const mglDataA &*x*, const mglDataA &*y*,   [Method on mglGraph]
        const mglDataA &*z*, const char **sch="", const char **opt="")
void mgl_grid (HMGL *gr*, HCDT *z*, const char **sch, const char **opt)   [C function]

void **mgl_grid_xy** (HMGL *gr*, HCDT *x*, HCDT *y*, HCDT *z*, const char   [C function]
        **sch, const char *opt)
> The function draws grid lines for density plot of surface specified parametrically {*x*[i,j],
> *y*[i,j], *z*[i,j]} at *z* = *Min.z*. See also [dens], page 179, [cont], page 179, [contf], page 180,
> [meshnum], page 138.

4.12 3D plotting

These functions perform plotting of 3D data. 3D means that data depend from 3 independent parameters like matrix $f(x_i, y_j, z_k), i = 1...n, j = 1...m, k = 1...l$. By default (if absent) values of *x*, *y*, *z* are equidistantly distributed in axis range. The minor dimensions of arrays *x*, *y*, *z*, *a* should be equal `x.nx=a.nx && y.nx=a.ny && z.nz=a.nz` or `x.nx=y.nx=z.nx=a.nx && x.ny=y.ny=z.ny=a.ny && x.nz=y.nz=z.nz=a.nz`. Arrays *x*, *y* and *z* can be vectors (not matrices as *a*). String *sch* sets the color scheme (see Section 3.4 [Color scheme], page 128) for plot. String *opt* contain command options (see Section 3.7 [Command options], page 132). See Section 2.7 [3D samples], page 79, for sample code and picture.

surf3 *adat* val ['*sch*'=''']   [MGL command]
surf3 *xdat ydat zdat adat* val ['*sch*'=''']   [MGL command]
void **Surf3** (mreal *val*, const mglDataA &*a*, const char   [Method on mglGraph]
        **sch='"", const char *opt="")
void **Surf3** (mreal *val*, const mglDataA &*x*, const   [Method on mglGraph]
        mglDataA &*y*, const mglDataA &*z*, const mglDataA &*a*, const char
        **sch="", const char *opt="")
void **mgl_surf3_val** (HMGL *gr*, mreal *val*, HCDT *a*, const char *sch,   [C function]
        const char *opt)
void **mgl_surf3_xyz_val** (HMGL *gr*, mreal *val*, HCDT *x*, HCDT *y*, HCDT   [C function]
        z, HCDT *a*, const char *sch, const char *opt)
> The function draws isosurface plot for 3d array specified parametrically *a*[i,j,k](*x*[i,j,k],
> *y*[i,j,k], *z*[i,j,k]) at *a*(x,y,z)=*val*. If string contain '#' then wire plot is produced.
> If string *sch* have symbol '.' then plot by dots is produced. Note, that there is
> possibility of incorrect plotting due to uncertainty of cross-section defining if there are
> two or more isosurface intersections inside one cell. See also [cloud], page 184, [dens3],
> page 184, [surf3c], page 187, [surf3a], page 188, [axial], page 182. See Section 2.7.1
> [Surf3 sample], page 79, for sample code and picture.

surf3 *adat* ['*sch*'=''']   [MGL command]
surf3 *xdat ydat zdat adat* ['*sch*'=''']   [MGL command]
void **Surf3** (const mglDataA &*a*, const char *sch="",   [Method on mglGraph]
        const char *opt="")
void **Surf3** (const mglDataA &*x*, const mglDataA &*y*,   [Method on mglGraph]
        const mglDataA &*z*, const mglDataA &*a*, const char *sch="", const
        char *opt="")
void **mgl_surf3** (HMGL *gr*, HCDT *a*, const char *sch, const char   [C function]
        **opt)

void `mgl_surf3_xyz` (HMGL *gr*, HCDT *x*, HCDT *y*, HCDT *z*, HCDT *a*,   [C function]
      const char **sch*, const char **opt*)

> Draws *num*-th uniformly distributed in color range isosurfaces for 3d data. Here *num* is equal to parameter *value* in options *opt* (default is 3).

`cloud` *adat* ['*sch*='']   [MGL command]
`cloud` *xdat ydat zdat adat* ['*sch*='']   [MGL command]
void `Cloud` (const mglDataA &*a*, const char **sch*="",   [Method on `mglGraph`]
      const char **opt*="")
void `Cloud` (const mglDataA &*x*, const mglDataA &*y*,   [Method on `mglGraph`]
      const mglDataA &*z*, const mglDataA &*a*, const char **sch*="", const
      char **opt*="")
void `mgl_cloud` (HMGL *gr*, HCDT *a*, const char **sch*, const char   [C function]
      *opt)
void `mgl_cloud_xyz` (HMGL *gr*, HCDT *x*, HCDT *y*, HCDT *z*, HCDT *a*,   [C function]
      const char **sch*, const char **opt*)

> The function draws cloud plot for 3d data specified parametrically a[i,j,k](x[i,j,k], y[i,j,k], z[i,j,k]). This plot is a set of cubes with color and transparency proportional to value of a. The resulting plot is like cloud – low value is transparent but higher ones are not. The number of plotting cells depend on [meshnum], page 138. If string *sch* contain symbol '.' then lower quality plot will produced with much low memory usage. If string *sch* contain symbol 'i' then transparency will be inversed, i.e. higher become transparent and lower become not transparent. See also [surf3], page 183, [meshnum], page 138. See Section 2.7.4 [Cloud sample], page 82, for sample code and picture.

`dens3` *adat* ['*sch*='' `sval=-1`]   [MGL command]
`dens3` *xdat ydat zdat adat* ['*sch*='' `sval=-1`]   [MGL command]
void `Dens3` (const mglDataA &*a*, const char **sch*="",   [Method on `mglGraph`]
      mreal *sVal*=-1, const char **opt*="")
void `Dens3` (const mglDataA &*x*, const mglDataA &*y*,   [Method on `mglGraph`]
      const mglDataA &*z*, const mglDataA &*a*, const char **sch*="", mreal
      sVal=-1, const char **opt*="")
void `mgl_dens3` (HMGL *gr*, HCDT *a*, const char **sch*, mreal *sVal*,   [C function]
      const char **opt*)
void `mgl_dens3_xyz` (HMGL *gr*, HCDT *x*, HCDT *y*, HCDT *z*, HCDT *a*,   [C function]
      const char **sch*, mreal *sVal*, const char **opt*)

> The function draws density plot for 3d data specified parametrically a[i,j,k](x[i,j,k], y[i,j,k], z[i,j,k]). Density is plotted at slice *sVal* in direction {'x', 'y', 'z'} if *sch* contain corresponding symbol (by default, 'y' direction is used). If string *stl* have symbol '#' then grid lines are drawn. See also [cont3], page 184, [contf3], page 185, [dens], page 179, [grid3], page 186. See Section 2.7.5 [Dens3 sample], page 83, for sample code and picture.

`cont3` *vdat adat* ['*sch*='' `sval=-1`]   [MGL command]
`cont3` *vdat xdat ydat zdat adat* ['*sch*='' `sval=-1`]   [MGL command]
void `Cont3` (const mglDataA &*v*, const mglDataA &*a*,   [Method on `mglGraph`]
      const char **sch*="", mreal *sVal*=-1, const char **opt*="")

void Cont3 (const mglDataA &*v*, const mglDataA &*x*,   [Method on mglGraph]
    const mglDataA &*y*, const mglDataA &*z*, const mglDataA &*a*, const char
    **sch="", mreal *sVal*=-1, const char **opt="")
void mgl_cont3_val (HMGL *gr*, HCDT *v*, HCDT *a*, const char **sch,   [C function]
    mreal *sVal*, const char **opt)
void mgl_cont3_xyz_val (HMGL *gr*, HCDT *v*, HCDT *x*, HCDT *y*, HCDT *z*,   [C function]
    HCDT *a*, const char **sch, mreal *sVal*, const char **opt)
    The function draws contour plot for 3d data specified parametrically a[i,j,k](x[i,j,k],
    y[i,j,k], z[i,j,k]). Contours are plotted for values specified in array *v* at slice *sVal* in
    direction {'x', 'y', 'z'} if *sch* contain corresponding symbol (by default, 'y' direction
    is used). If string *sch* have symbol '#' then grid lines are drawn. If string *sch* have
    symbol 't' or 'T' then contour labels will be drawn below (or above) the contours.
    See also [dens3], page 184, [contf3], page 185, [cont], page 179, [grid3], page 186. See
    Section 2.7.6 [Cont3 sample], page 84, for sample code and picture.

cont3 *adat* ['*sch*'=" sval=-1]   [MGL command]
cont3 *xdat ydat zdat adat* ['*sch*'=" sval=-1]   [MGL command]
void Cont3 (const mglDataA &*a*, const char **sch="",   [Method on mglGraph]
    mreal *sVal*=-1, const char **opt="", const char **opt="")
void Cont3 (const mglDataA &*x*, const mglDataA &*y*,   [Method on mglGraph]
    const mglDataA &*z*, const mglDataA &*a*, const char **sch="", mreal
    sVal=-1, const char **opt="")
void mgl_cont3 (HMGL *gr*, HCDT *a*, const char **sch, mreal *sVal*,   [C function]
    const char **opt)
void mgl_cont3_xyz (HMGL *gr*, HCDT *x*, HCDT *y*, HCDT *z*, HCDT *a*,   [C function]
    const char **sch, mreal *sVal*, const char **opt)
    The same as previous with vector *v* of *num*-th elements equidistantly distributed in
    color range. Here *num* is equal to parameter *value* in options *opt* (default is 7).

contf3 *vdat adat* ['*sch*'=" sval=-1]   [MGL command]
contf3 *vdat xdat ydat zdat adat* ['*sch*'=" sval=-1]   [MGL command]
void Contf3 (const mglDataA &*v*, const mglDataA &*a*,   [Method on mglGraph]
    const char **sch="", mreal *sVal*=-1, const char **opt="")
void Contf3 (const mglDataA &*v*, const mglDataA &*x*,   [Method on mglGraph]
    const mglDataA &*y*, const mglDataA &*z*, const mglDataA &*a*, const char
    **sch="", mreal *sVal*=-1, const char **opt="")
void mgl_contf3_val (HMGL *gr*, HCDT *v*, HCDT *a*, const char **sch,   [C function]
    mreal *sVal*, const char **opt)
void mgl_contf3_xyz_val (HMGL *gr*, HCDT *v*, HCDT *x*, HCDT *y*, HCDT *z*,   [C function]
    HCDT *a*, const char **sch, mreal *sVal*, const char **opt)
    The function draws solid (or filled) contour plot for 3d data specified parametrically
    a[i,j,k](x[i,j,k], y[i,j,k], z[i,j,k]). Contours are plotted for values specified in array *v* at
    slice *sVal* in direction {'x', 'y', 'z'} if *sch* contain corresponding symbol (by default,
    'y' direction is used). If string *sch* have symbol '#' then grid lines are drawn. See
    also [dens3], page 184, [cont3], page 184, [contf], page 180, [grid3], page 186. See
    Section 2.7.7 [ContF3 sample], page 85, for sample code and picture.

```
contf3 adat ['sch'=" sval=-1]                                    [MGL command]
contf3 xdat ydat zdat adat ['sch'=" sval=-1]                     [MGL command]
void Contf3 (const mglDataA &a, const char *sch="",       [Method on mglGraph]
        mreal sVal=-1, const char *opt="", const char *opt="")
void Contf3 (const mglDataA &x, const mglDataA &y,        [Method on mglGraph]
        const mglDataA &z, const mglDataA &a, const char *sch="", mreal
        sVal=-1, const char *opt="")
void mgl_contf3 (HMGL gr, HCDT a, const char *sch, mreal sVal,      [C function]
        const char *opt)
void mgl_contf3_xyz (HMGL gr, HCDT x, HCDT y, HCDT z, HCDT a,       [C function]
        const char *sch, mreal sVal, const char *opt)
```
The same as previous with vector *v* of *num*-th elements equidistantly distributed in
color range. Here *num* is equal to parameter *value* in options *opt* (default is 7).

```
grid3 adat ['sch'=" sval=-1]                                     [MGL command]
grid3 xdat ydat zdat adat ['sch'=" sval=-1]                      [MGL command]
void Grid3 (const mglDataA &a, const char *sch="",        [Method on mglGraph]
        mreal sVal=-1, const char *opt="")
void Grid3 (const mglDataA &x, const mglDataA &y,         [Method on mglGraph]
        const mglDataA &z, const mglDataA &a, const char *sch="", mreal
        sVal=-1, const char *opt="")
void mgl_grid3 (HMGL gr, HCDT a, const char *sch, mreal sVal,       [C function]
        const char *opt)
void mgl_grid3_xyz (HMGL gr, HCDT x, HCDT y, HCDT z, HCDT a,        [C function]
        const char *sch, mreal sVal, const char *opt)
```
The function draws grid for 3d data specified parametrically $a[i,j,k](x[i,j,k], y[i,j,k], z[i,j,k])$. Grid is plotted at slice *sVal* in direction {'x', 'y', 'z'} if *sch* contain corresponding symbol (by default, 'y' direction is used). See also [cont3], page 184, [contf3], page 185, [dens3], page 184, [grid2], page 182, [meshnum], page 138.

```
beam tr g1 g2 adat rval ['sch'=" flag=0 num=3]                   [MGL command]
void Beam (const mglDataA &tr, const mglDataA &g1,        [Method on mglGraph]
        const mglDataA &g2, const mglDataA &a, mreal r, const char *stl="",
        int flag=0, int num=3)
void Beam (mreal val, const mglDataA &tr, const            [Method on mglGraph]
        mglDataA &g1, const mglDataA &g2, const mglDataA &a, mreal r, const
        char *stl="", int flag=0)
void mgl_beam (HMGL gr, HCDT tr, HCDT g1, HCDT g2, HCDT a, mreal r,  [C function]
        const char *stl, int flag, int num)
void mgl_beam_val (HMGL gr, mreal val, HCDT tr, HCDT g1, HCDT g2,   [C function]
        HCDT a, mreal r, const char *stl, int flag)
```
Draws the isosurface for 3d array *a* at constant values of *a=val*. This is special kind of plot for *a* specified in accompanied coordinates along curve *tr* with orts *g1*, *g2* and with transverse scale *r*. Variable *flag* is bitwise: '0x1' - draw in accompanied (not laboratory) coordinates; '0x2' - draw projection to $\rho - z$ plane; '0x4' - draw normalized in each slice field. The x-size of data arrays *tr*, *g1*, *g2* must be nx>2. The y-size of data arrays *tr*, *g1*, *g2* and z-size of the data array *a* must be equal. See also [surf3], page 183.

4.13 Dual plotting

These plotting functions draw *two matrix* simultaneously. There are 5 generally different types of data representations: surface or isosurface colored by other data (SurfC, Surf3C), surface or isosurface transpared by other data (SurfA, Surf3A), tiles with variable size (TileS), mapping diagram (Map), STFA diagram (STFA). By default (if absent) values of x, y, z are equidistantly distributed in axis range. The minor dimensions of arrays x, y, z, c should be equal. Arrays x, y (and z for `Surf3C, Surf3A`) can be vectors (not matrices as c). String *sch* sets the color scheme (see Section 3.4 [Color scheme], page 128) for plot. String *opt* contain command options (see Section 3.7 [Command options], page 132).

`surfc` *zdat cdat* [*'sch'=''*]   [MGL command]
`surfc` *xdat ydat zdat cdat* [*'sch'=''*]   [MGL command]
`void SurfC (const mglDataA &`*z*`, const mglDataA &`*c*`,`   [Method on `mglGraph`]
        `const char *`*sch*`="", const char *`*opt*`="")`
`void SurfC (const mglDataA &`*x*`, const mglDataA &`*y*`,`   [Method on `mglGraph`]
        `const mglDataA &`*z*`, const mglDataA &`*c*`, const char *`*sch*`="", const`
        `char *`*opt*`="")`
`void mgl_surfc (HMGL `*gr*`, HCDT `*z*`, HCDT `*c*`, const char *`*sch*`, const`   [C function]
        `char *`*opt*`)`
`void mgl_surfc_xy (HMGL `*gr*`, HCDT `*x*`, HCDT `*y*`, HCDT `*z*`, HCDT `*c*`, const`   [C function]
        `char *`*sch*`, const char *`*opt*`)`
   The function draws surface specified parametrically {x[i,j], y[i,j], z[i,j]} and color it by matrix c[i,j]. If string *sch* have symbol '`#`' then grid lines are drawn. If string *sch* have symbol '`.`' then plot by dots is produced. All dimensions of arrays z and c must be equal. Surface is plotted for each z slice of the data. See also [surf], page 177, [surfa], page 188, [surf3c], page 187. See Section 2.6.2 [SurfC sample], page 65, for sample code and picture.

`surf3c` *adat cdat* `val` [*'sch'=''*]   [MGL command]
`surf3c` *xdat ydat zdat adat cdat* `val` [*'sch'=''*]   [MGL command]
`void Surf3C (mreal `*val*`, const mglDataA &`*a*`, const`   [Method on `mglGraph`]
        `mglDataA &`*c*`, const char *`*sch*`="", const char *`*opt*`="")`
`void Surf3C (mreal `*val*`, const mglDataA &`*x*`, const`   [Method on `mglGraph`]
        `mglDataA &`*y*`, const mglDataA &`*z*`, const mglDataA &`*a*`, const mglDataA`
        `&`*c*`, const char *`*sch*`="", const char *`*opt*`="")`
`void mgl_surf3c_val (HMGL `*gr*`, mreal `*val*`, HCDT `*a*`, HCDT `*c*`, const`   [C function]
        `char *`*sch*`, const char *`*opt*`)`
`void mgl_surf3c_xyz_val (HMGL `*gr*`, mreal `*val*`, HCDT `*x*`, HCDT `*y*`,`   [C function]
        `HCDT `*z*`, HCDT `*a*`, HCDT `*c*`, const char *`*sch*`, const char *`*opt*`)`
   The function draws isosurface plot for 3d array specified parametrically a[i,j,k](x[i,j,k], y[i,j,k], z[i,j,k]) at a(x,y,z)=*val*. It is mostly the same as [surf3], page 183 function but the color of isosurface depends on values of array c. If string *sch* contain '`#`' then wire plot is produced. If string *sch* have symbol '`.`' then plot by dots is produced. See also [surf3], page 183, [surfc], page 187, [surf3a], page 188. See Section 2.7.2 [Surf3C sample], page 80, for sample code and picture.

`surf3c` *adat cdat* [*'sch'=''*]   [MGL command]
`surf3c` *xdat ydat zdat adat cdat* [*'sch'=''*]   [MGL command]

```
void Surf3C (const mglDataA &a, const mglDataA &c,        [Method on mglGraph]
        const char *sch="", const char *opt="")
void Surf3C (const mglDataA &x, const mglDataA &y,        [Method on mglGraph]
        const mglDataA &z, const mglDataA &a, const mglDataA &c, const char
        *sch="", const char *opt="")
void mgl_surf3c (HMGL gr, HCDT a, HCDT c, const char *sch, const    [C function]
        char *opt)
void mgl_surf3c_xyz (HMGL gr, HCDT x, HCDT y, HCDT z, HCDT a,       [C function]
        HCDT c, const char *sch, const char *opt)
```
Draws *num*-th uniformly distributed in color range isosurfaces for 3d data. Here *num*
is equal to parameter *value* in options *opt* (default is 3).

```
surfa zdat cdat ['sch'=”]                                          [MGL command]
surfa xdat ydat zdat cdat ['sch'=”]                               [MGL command]
void SurfA (const mglDataA &z, const mglDataA &c,        [Method on mglGraph]
        const char *sch="", const char *opt="")
void SurfA (const mglDataA &x, const mglDataA &y,        [Method on mglGraph]
        const mglDataA &z, const mglDataA &c, const char *sch="", const
        char *opt="")
void mgl_surfa (HMGL gr, HCDT z, HCDT c, const char *sch, const    [C function]
        char *opt)
void mgl_surfa_xy (HMGL gr, HCDT x, HCDT y, HCDT z, HCDT c, const  [C function]
        char *sch, const char *opt)
```
The function draws surface specified parametrically $\{x[i,j], y[i,j], z[i,j]\}$ and transpar-
ent it by matrix $c[i,j]$. If string *sch* have symbol '#' then grid lines are drawn. If string
sch have symbol '.' then plot by dots is produced. All dimensions of arrays *z* and *c*
must be equal. Surface is plotted for each z slice of the data. See also [surf], page 177,
[surfc], page 187, [surf3a], page 188. See Section 2.6.3 [SurfA sample], page 66, for
sample code and picture.

```
surf3a adat cdat val ['sch'=”]                                    [MGL command]
surf3a xdat ydat zdat adat cdat val ['sch'=”]                    [MGL command]
void Surf3A (mreal val, const mglDataA &a, const         [Method on mglGraph]
        mglDataA &c, const char *sch="", const char *opt="")
void Surf3A (mreal val, const mglDataA &x, const         [Method on mglGraph]
        mglDataA &y, const mglDataA &z, const mglDataA &a, const mglDataA
        &c, const char *sch="", const char *opt="")
void mgl_surf3a_val (HMGL gr, mreal val, HCDT a, HCDT c, const     [C function]
        char *sch, const char *opt)
void mgl_surf3a_xyz_val (HMGL gr, mreal val, HCDT x, HCDT y,       [C function]
        HCDT z, HCDT a, HCDT c, const char *sch, const char *opt)
```
The function draws isosurface plot for 3d array specified parametrically $a[i,j,k](x[i,j,k],$
$y[i,j,k], z[i,j,k])$ at $a(x,y,z)=val$. It is mostly the same as [surf3], page 183 function
but the color of isosurface depends on values of array *c*. If string *sch* contain '#' then
wire plot is produced. If string *sch* have symbol '.' then plot by dots is produced. See
also [surf3], page 183, [surfc], page 187, [surf3a], page 188. See Section 2.7.3 [Surf3A
sample], page 81, for sample code and picture.

surf3a *adat cdat* ['*sch*'='']   [MGL command]

surf3a *xdat ydat zdat adat cdat* ['*sch*'='']   [MGL command]

void Surf3A (const mglDataA &*a*, **const mglDataA** &*c*,   [Method on **mglGraph**]
    const char **sch*="", **const char** **opt*="")

void Surf3A (const mglDataA &*x*, **const mglDataA** &*y*,   [Method on **mglGraph**]
    const mglDataA &*z*, **const mglDataA** &*a*, **const mglDataA** &*c*, **const char**
    *sch="", **const char** **opt*="")

void mgl_surf3a (HMGL *gr*, **HCDT** *a*, **HCDT** *c*, **const char** **sch*, **const**   [C function]
    char **opt*)

void mgl_surf3a_xyz (HMGL *gr*, **HCDT** *x*, **HCDT** *y*, **HCDT** *z*, **HCDT** *a*,   [C function]
    HCDT *c*, **const char** **sch*, **const char** **opt*)

Draws *num*-th uniformly distributed in color range isosurfaces for 3d data. At this array *c* can be vector with values of transparency and *num*=*c*.nx. In opposite case *num* is equal to parameter *value* in options *opt* (default is 3).

tiles *zdat rdat* ['*sch*'='']   [MGL command]

tiles *xdat ydat zdat rdat* ['*sch*'='']   [MGL command]

void TileS (const mglDataA &*z*, **const mglDataA** &*c*,   [Method on **mglGraph**]
    const char **sch*="", **const char** **opt*="")

void TileS (const mglDataA &*x*, **const mglDataA** &*y*,   [Method on **mglGraph**]
    const mglDataA &*z*, **const mglDataA** &*r*, **const char** **sch*="", **const**
    char **opt*="")

void mgl_tiles (HMGL *gr*, **HCDT** *z*, **HCDT** *c*, **const char** **sch*, **const**   [C function]
    char **opt*)

void mgl_tiles_xy (HMGL *gr*, **HCDT** *x*, **HCDT** *y*, **HCDT** *z*, **HCDT** *r*, **const**   [C function]
    char **sch*, **const char** **opt*)

The function draws horizontal tiles for surface specified parametrically {*x*[i,j], *y*[i,j], *z*[i,j]}. It is mostly the same as [tile], page 178 but the size of tiles is determined by *r* array. This is some kind of "transparency" useful for exporting to EPS files. Tiles is plotted for each z slice of the data. See also [surfa], page 188, [tile], page 178. See Section 2.6.9 [TileS sample], page 72, for sample code and picture.

map *udat vdat* ['*sch*'='']   [MGL command]

map *xdat ydat udat vdat* ['*sch*'='']   [MGL command]

void Map (const mglDataA &*ax*, **const mglDataA** &*ay*,   [Method on **mglGraph**]
    const char **sch*="", **const char** **opt*="")

void Map (const mglDataA &*x*, **const mglDataA** &*y*, **const**   [Method on **mglGraph**]
    mglDataA &*ax*, **const mglDataA** &*ay*, **const char** **sch*="", **const char**
    *opt="")

void mgl_map (HMGL *gr*, **HCDT** *ax*, **HCDT** *ay*, **const char** **sch*, **const**   [C function]
    char **opt*)

void mgl_map_xy (HMGL *gr*, **HCDT** *x*, **HCDT** *y*, **HCDT** *ax*, **HCDT** *ay*, **const**   [C function]
    char **sch*, **const char** **opt*)

The function draws mapping plot for matrices {*ax*, *ay* } which parametrically depend on coordinates *x*, *y*. The initial position of the cell (point) is marked by color. Height is proportional to Jacobian(ax,ay). This plot is like Arnold diagram ??? If string *sch* contain symbol '.' then the color ball at matrix knots are drawn otherwise face

is drawn. See Section 2.9.9 [Mapping visualization], page 111, for sample code and picture.

`stfa` *re im* `dn` [*'sch'=*'']	[MGL command]
`stfa` *xdat ydat re im* `dn` [*'sch'=*'']	[MGL command]
`void STFA (const mglDataA &`*re*`, const mglDataA &`*im*`,`	[Method on `mglGraph`]

> `int `*dn*`, const char *`*sch*`="", const char *`*opt*`="")`

`void STFA (const mglDataA &`*x*`, const mglDataA &`*y*`,`	[Method on `mglGraph`]

> `const mglDataA &`*re*`, const mglDataA &`*im*`, int `*dn*`, const char *`*sch*`="",`
> `const char *`*opt*`="")`

`void mgl_stfa (HMGL `*gr*`, HCDT `*re*`, HCDT `*im*`, int `*dn*`, const char *`*sch*`,`	[C function]

> `const char *`*opt*`)`

`void mgl_stfa_xy (HMGL `*gr*`, HCDT `*x*`, HCDT `*y*`, HCDT `*re*`, HCDT `*im*`, int`	[C function]

> *dn*`, const char *`*sch*`, const char *`*opt*`)`

> Draws spectrogram of complex array *re*+i*`im` for Fourier size of *dn* points at plane z=Min.z. For example in 1D case, result is density plot of data $res[i,j] = |\sum_d^d nexp(I*j*d)*(re[i*dn+d] + I*im[i*dn+d])|/dn$ with size {int(nx/dn), dn, ny}. At this array *re*, *im* parametrically depend on coordinates *x*, *y*. The size of *re* and *im* must be the same. The minor dimensions of arrays *x*, *y*, *re* should be equal. Arrays *x*, *y* can be vectors (not matrix as *re*). See Section 2.9.8 [STFA sample], page 110, for sample code and picture.

4.14 Vector fields

These functions perform plotting of 2D and 3D vector fields. There are 5 generally different types of vector fields representations: simple vector field (Vect), vectors along the curve (Traj), vector field by dew-drops (Dew), flow threads (Flow, FlowP), flow pipes (Pipe). By default (if absent) values of *x*, *y*, *z* are equidistantly distributed in axis range. The minor dimensions of arrays *x*, *y*, *z*, *ax* should be equal. The size of *ax*, *ay* and *az* must be equal. Arrays *x*, *y*, *z* can be vectors (not matrices as *ax*). String *sch* sets the color scheme (see Section 3.4 [Color scheme], page 128) for plot. String *opt* contain command options (see Section 3.7 [Command options], page 132).

`traj` *xdat ydat udat vdat* [*'sch'=*'']	[MGL command]
`traj` *xdat ydat zdat udat vdat wdat* [*'sch'=*'']	[MGL command]
`void Traj (const mglDataA &`*x*`, const mglDataA &`*y*`,`	[Method on `mglGraph`]

> `const mglDataA &`*ax*`, const mglDataA &`*ay*`, const char *`*sch*`="", const`
> `char *`*opt*`="")`

`void Traj (const mglDataA &`*x*`, const mglDataA &`*y*`,`	[Method on `mglGraph`]

> `const mglDataA &`*z*`, const mglDataA &`*ax*`, const mglDataA &`*ay*`, const`
> `mglDataA &`*az*`, const char *`*sch*`="", const char *`*opt*`="")`

`void mgl_traj_xyz (HMGL `*gr*`, HCDT`*x*`, HCDT`*y*`, HCDT`*z*`, HCDT`*ax*`, HCDT`*ay*`,`	[C function]

> `HCDT`*az*`, const char *`*sch*`, const char *`*opt*`)`

`void mgl_traj_xy (HMGL `*gr*`, HCDT`*x*`, HCDT`*y*`, HCDT`*ax*`, HCDT`*ay*`, const`	[C function]

> `char *`*sch*`, const char *`*opt*`)`

> The function draws vectors {*ax*, *ay*, *az*} along a curve {*x*, *y*, *z*}. The length of arrows are proportional to $\sqrt{ax^2 + ay^2 + az^2}$. String *pen* specifies the color (see Section 3.3 [Line styles], page 127). By default (`pen=""`) color from palette is used

(see Section 4.2.7 [Palette and colors], page 140). Option *value* set the vector length factor (if non-zero) or vector length to be proportional the distance between curve points (if *value*=0). The minor sizes of all arrays must be equal and large 2. The plots are drawn for each row if one of the data is the matrix. See also [vect], page 191. See Section 2.8.3 [Traj sample], page 95, for sample code and picture.

vect *udat vdat* ['sch'='']	[MGL command]
vect *xdat ydat udat vdat* ['sch'='']	[MGL command]
void **Vect** (const mglDataA &*ax*, const mglDataA &*ay*,	[Method on mglGraph]
const char **sch*="", const char **opt*="")	
void **Vect** (const mglDataA &*x*, const mglDataA &*y*,	[Method on mglGraph]
const mglDataA &*ax*, const mglDataA &*ay*, const char **sch*="", const	
char **opt*="")	
void **mgl_vect_2d** (HMGL *gr*, HCDT *ax*, HCDT *ay*, const char **sch*,	[C function]
const char **opt*)	
void **mgl_vect_xy** (HMGL *gr*, HCDT *x*, HCDT *y*, HCDT *ax*, HCDT *ay*,	[C function]
const char **sch*, const char **opt*)	

The function draws plane vector field plot for the field $\{ax, ay\}$ depending parametrically on coordinates x, y at level $z=Min.z$. The length and color of arrows are proportional to $\sqrt{\{ax^2+ay^2\}}$. The number of arrows depend on [meshnum], page 138. The appearance of the hachures (arrows) can be changed by symbols:

- 'f' for drawing arrows with fixed lengths,

- '>', '<' for drawing arrows to or from the cell point (default is centering),

- '.' for drawing hachures with dots instead of arrows,

- '=' for enabling color gradient along arrows.

See also [flow], page 192, [dew], page 192. See Section 2.8.1 [Vect sample], page 93, for sample code and picture.

vect *udat vdat wdat* ['sch'='']	[MGL command]
vect *xdat ydat zdat udat vdat wdat* ['sch'='']	[MGL command]
void **Vect** (const mglDataA &*ax*, const mglDataA &*ay*,	[Method on mglGraph]
const mglDataA &*az*, const char **sch*="", const char **opt*="")	
void **Vect** (const mglDataA &*x*, const mglDataA &*y*,	[Method on mglGraph]
const mglDataA &*z*, const mglDataA &*ax*, const mglDataA &*ay*, const	
mglDataA &*az*, const char **sch*="", const char **opt*="")	
void **mgl_vect_3d** (HMGL *gr*, HCDT *ax*, HCDT *ay*, HCDT *az*, const char	[C function]
*sch, const char **opt*)	
void **mgl_vect_xyz** (HMGL *gr*, HCDT *x*, HCDT *y*, HCDT *z*, HCDT *ax*, HCDT	[C function]
ay, HCDT *az*, const char **sch*, const char **opt*)	

This is 3D version of the first functions. Here arrays *ax*, *ay*, *az* must be 3-ranged tensors with equal sizes and the length and color of arrows is proportional to $\sqrt{\{ax^2+ay^2+az^2\}}$.

vect3 *udat vdat wdat* ['sch'='' *sval*]	[MGL command]
vect3 *xdat ydat zdat udat vdat wdat* ['sch'='' *sval*]	[MGL command]

void **Vect3** (const mglDataA &*ax*, const mglDataA &*ay*,   [Method on mglGraph]
    const mglDataA &*az*, const char **sch*="", mreal *sVal*=-1, const char
    *opt="")

void **Vect3** (const mglDataA &*x*, const mglDataA &*y*,   [Method on mglGraph]
    const mglDataA &*z*, const mglDataA &*ax*, const mglDataA &*ay*, const
    mglDataA &*az*, const char **sch*="", mreal *sVal*=-1, const char **opt*="")

void **mgl_vect3** (HMGL *gr*, HCDT *ax*, HCDT *ay*, HCDT *az*, const char   [C function]
    *sch, mreal *sVal*, const char **opt*)

void **mgl_vect3_xyz** (HMGL *gr*, HCDT *x*, HCDT *y*, HCDT *z*, HCDT *ax*,   [C function]
    HCDT *ay*, HCDT *az*, const char **sch*, mreal *sVal*, const char **opt*)

    The function draws 3D vector field plot for the field {ax, ay, az} depending para-
metrically on coordinates x, y, z. Vector field is drawn at slice *sVal* in direction {'x',
'y', 'z'} if *sch* contain corresponding symbol (by default, 'y' direction is used). The
length and color of arrows are proportional to $\sqrt{ax^2 + ay^2 + az^2}$. The number of
arrows depend on . The appearance of the hachures (arrows)
can be changed by symbols:

- 'f' for drawing arrows with fixed lengths,
- '>', '<' for drawing arrows to or from the cell point (default is centering),
- '.' for drawing hachures with dots instead of arrows,
- '=' for enabling color gradient along arrows.

     for sample code and picture.

dew *udat vdat* ['*sch*'="]   [MGL command]
dew *xdat ydat udat vdat* ['*sch*'="]   [MGL command]
void **Dew** (const mglDataA &*ax*, const mglDataA &*ay*,   [Method on mglGraph]
    const char **sch*="", const char **opt*="")
void **Dew** (const mglDataA &*x*, const mglDataA &*y*, const   [Method on mglGraph]
    mglDataA &*ax*, const mglDataA &*ay*, const char **sch*="", const char
    *opt="")
void **mgl_dew** (HMGL *gr*, HCDT *ax*, HCDT *ay*, const char **sch*, const   [C function]
    char **opt*)
void **mgl_dew_xy** (HMGL *gr*, HCDT *x*, HCDT *y*, HCDT *ax*, HCDT *ay*, const   [C function]
    char **sch*, const char **opt*)

    The function draws dew-drops for plane vector field {ax, ay} depending parametri-
cally on coordinates x, y at level z=Min.z. Note that this is very expensive plot in
memory usage and creation time! The color of drops is proportional to $\sqrt{ax^2 + ay^2}$.
The number of drops depend on . See also . See
for sample code and picture.

flow *udat vdat* ['*sch*'="]   [MGL command]
flow *xdat ydat udat vdat* ['*sch*'="]   [MGL command]
void **Flow** (const mglDataA &*ax*, const mglDataA &*ay*,   [Method on mglGraph]
    const char **sch*="", const char **opt*="")
void **Flow** (const mglDataA &*x*, const mglDataA &*y*,   [Method on mglGraph]
    const mglDataA &*ax*, const mglDataA &*ay*, const char **sch*="", const
    char **opt*="")

`void mgl_flow_2d (HMGL` *gr,* `HCDT` *ax,* `HCDT` *ay,* `const char *`*sch,*   [C function]
        `const char *`*opt*)
`void mgl_flow_xy (HMGL` *gr,* `HCDT` *x,* `HCDT` *y,* `HCDT` *ax,* `HCDT` *ay,*   [C function]
        `const char *`*sch,* `const char *`*opt*)
    The function draws flow threads for the plane vector field {*ax, ay*} parametrically
    depending on coordinates *x, y* at level *z* = *Min*.z. Number of threads is proportional
    to *value* option (default is 5). String *sch* may contain:

- color scheme – up-half (warm) corresponds to normal flow (like attractor),
  bottom-half (cold) corresponds to inverse flow (like source);

- '`#`' for starting threads from edges only;

- '`v`' for drawing arrows on the threads;

- '`x`', '`z`' for drawing tapes of normals in x-y and y-z planes correspondingly.

    See also [pipe], page 194, [vect], page 191, [tape], page 168, [barwidth], page 137. See
    Section 2.8.4 [Flow sample], page 96, for sample code and picture.

`flow` *udat vdat wdat* [*'sch'=*"]   [MGL command]
`flow` *xdat ydat zdat udat vdat wdat* [*'sch'=*"]   [MGL command]
`void Flow (const mglDataA &`*ax,* `const mglDataA &`*ay,*   [Method on `mglGraph`]
        `const mglDataA &`*az,* `const char *`*sch*`=""`, `const char *`*opt*`=""`)
`void Flow (const mglDataA &`*x,* `const mglDataA &`*y,*   [Method on `mglGraph`]
        `const mglDataA &`*z,* `const mglDataA &`*ax,* `const mglDataA &`*ay,* `const`
        `mglDataA &`*az,* `const char *`*sch*`=""`, `const char *`*opt*`=""`)
`void mgl_flow_3d (HMGL` *gr,* `HCDT` *ax,* `HCDT` *ay,* `HCDT` *az,* `const char`   [C function]
        `*`*sch,* `const char *`*opt*)
`void mgl_flow_xyz (HMGL` *gr,* `HCDT` *x,* `HCDT` *y,* `HCDT` *z,* `HCDT` *ax,* `HCDT`   [C function]
        ay, `HCDT` *az,* `const char *`*sch,* `const char *`*opt*)
    This is 3D version of the first functions. Here arrays *ax, ay, az* must be 3-ranged
    tensors with equal sizes and the color of line is proportional to $\sqrt{\{ax^2 + ay^2 + az^2\}}$.

`flow` x0 y0 *udat vdat* [*'sch'=*"]   [MGL command]
`flow` x0 y0 *xdat ydat udat vdat* [*'sch'=*"]   [MGL command]
`void FlowP (mglPoint` *p0,* `const mglDataA &`*ax,* `const`   [Method on `mglGraph`]
        `mglDataA &`*ay,* `const char *`*sch*`=""`, `const char *`*opt*`=""`)
`void FlowP (mglPoint` *p0,* `const mglDataA &`*x,* `const`   [Method on `mglGraph`]
        `mglDataA &`*y,* `const mglDataA &`*ax,* `const mglDataA &`*ay,* `const char`
        `*`*sch*`=""`, `const char *`*opt*`=""`)
`void mgl_flowp_2d (HMGL` *gr,* `mreal` *x0,* `mreal` *y0,* `mreal` *z0,* `HCDT`   [C function]
        ax, `HCDT` *ay,* `const char *`*sch,* `const char *`*opt*)
`void mgl_flowp_xy (HMGL` *gr,* `mreal` *x0,* `mreal` *y0,* `mreal` *z0,* `HCDT` *x,*   [C function]
        `HCDT` *y,* `HCDT` *ax,* `HCDT` *ay,* `const char *`*sch,* `const char *`*opt*)
    The same as first one ([flow], page 192) but draws single flow thread starting from
    point *p0*={*x0,y0,z0*}.

`flow` x0 y0 z0 *udat vdat wdat* [*'sch'=*"]   [MGL command]
`flow` x0 y0 z0 *xdat ydat zdat udat vdat wdat* [*'sch'=*"]   [MGL command]

void FlowP (mglPoint *p0*, const mglDataA &*ax*, const   [Method on `mglGraph`]
    mglDataA &*ay*, const mglDataA &*az*, const char *`*sch*=""`, const char
    `*`*opt*`=""`)

void FlowP (mglPoint *p0*, const mglDataA &*x*, const   [Method on `mglGraph`]
    mglDataA &*y*, const mglDataA &*z*, const mglDataA &*ax*, const mglDataA
    &*ay*, const mglDataA &*az*, const char *`*sch*=""`, const char *`*opt*=""`)

void mgl_flowp_3d (HMGL *gr*, mreal *x0*, mreal *y0*, mreal *z0*, HCDT   [C function]
    ax, HCDT *ay*, HCDT *az*, const char *`*sch*`, const char *`*opt*`)

void mgl_flowp_xyz (HMGL *gr*, mreal *x0*, mreal *y0*, mreal *z0*, HCDT   [C function]
    x, HCDT *y*, HCDT *z*, HCDT *ax*, HCDT *ay*, HCDT *az*, const char *`*sch*`, const char
    `*`*opt*`)
    This is 3D version of the previous functions.

grad *pdat* [`'sch'=`"]   [MGL command]
grad *xdat ydat pdat* [`'sch'=`"]   [MGL command]
grad *xdat ydat zdat pdat* [`'sch'=`"]   [MGL command]
void Grad (const mglDataA &*phi*, const char *`*sch*=""`,   [Method on `mglGraph`]
    const char *`*opt*=""`)

void Grad (const mglDataA &*x*, const mglDataA &*y*,   [Method on `mglGraph`]
    const mglDataA &*phi*, const char *`*sch*=""`, const char *`*opt*=""`)

void Grad (const mglDataA &*x*, const mglDataA &*y*,   [Method on `mglGraph`]
    const mglDataA &*z*, const mglDataA &*phi*, const char *`*sch*=""`, const
    char *`*opt*=""`)

void mgl_grad (HMGL *gr*, HCDT *phi*, const char *`*sch*`, const char   [C function]
    `*`*opt*`)

void mgl_grad_xy (HMGL *gr*, HCDT *x*, HCDT *y*, HCDT *phi*, const char   [C function]
    `*`*sch*`, const char *`*opt*`)

void mgl_grad_xyz (HMGL *gr*, HCDT *x*, HCDT *y*, HCDT *z*, HCDT *phi*,   [C function]
    const char *`*sch*`, const char *`*opt*`)
    The function draws gradient lines for scalar field *phi*[i,j] (or *phi*[i,j,k] in 3d case)
    specified parametrically {*x*[i,j,k], *y*[i,j,k], *z*[i,j,k]}. Number of lines is proportional to
    value option (default is 5). See also

pipe *udat vdat* [`'sch'=`" `r0=0.05`]   [MGL command]
pipe *xdat ydat udat vdat* [`'sch'=`" `r0=0.05`]   [MGL command]
void Pipe (const mglDataA &*ax*, const mglDataA &*ay*,   [Method on `mglGraph`]
    const char *`*sch*=""`, mreal *r0*=0.05, const char *`*opt*=""`)

void Pipe (const mglDataA &*x*, const mglDataA &*y*,   [Method on `mglGraph`]
    const mglDataA &*ax*, const mglDataA &*ay*, const char *`*sch*=""`, mreal
    r0=0.05, const char *`*opt*=""`)

void mgl_pipe_2d (HMGL *gr*, HCDT *ax*, HCDT *ay*, const char *`*sch*`,   [C function]
    mreal *r0*, const char *`*opt*`)

void mgl_pipe_xy (HMGL *gr*, HCDT *x*, HCDT *y*, HCDT *ax*, HCDT *ay*,   [C function]
    const char *`*sch*`, mreal *r0*, const char *`*opt*`)
    The function draws flow pipes for the plane vector field {*ax*, *ay*} parametrically
    depending on coordinates *x*, *y* at level *z* = *Min.z*. Number of pipes is proportional
    to *value* option (default is 5). If '#' symbol is specified then pipes start only from
    edges of axis range. The color of lines is proportional to $\sqrt{ax^2 + ay^2}$. Warm color

corresponds to normal flow (like attractor). Cold one corresponds to inverse flow (like source). Parameter *r0* set the base pipe radius. If *r0<0* or symbol 'i' is specified then pipe radius is inverse proportional to amplitude. The vector field is plotted for each z slice of *ax*, *ay*. See also [flow], page 192, [vect], page 191. See Section 2.8.5 [Pipe sample], page 97, for sample code and picture.

pipe *udat vdat wdat* ['*sch*'=" `r0=0.05`]   [MGL command]
pipe *xdat ydat zdat udat vdat wdat* ['*sch*'=" `r0=0.05`]   [MGL command]
void Pipe (const mglDataA &*ax*, const mglDataA &*ay*,   [Method on mglGraph]
  const mglDataA &*az*, const char **sch*="", mreal *r0*=0.05, const char
  *opt="")
void Pipe (const mglDataA &*x*, const mglDataA &*y*,   [Method on mglGraph]
  const mglDataA &*z*, const mglDataA &*ax*, const mglDataA &*ay*, const
  mglDataA &*az*, const char **sch*="", mreal *r0*=0.05, const char
  *opt="")
void mgl_pipe_3d (HMGL *gr*, HCDT *ax*, HCDT *ay*, HCDT *az*, const char   [C function]
  *sch, mreal *r0*, const char **opt*)
void mgl_pipe_xyz (HMGL *gr*, HCDT *x*, HCDT *y*, HCDT *z*, HCDT *ax*, HCDT   [C function]
  ay, HCDT *az*, const char **sch*, mreal *r0*, const char **opt*)
  This is 3D version of the first functions. Here arrays *ax*, *ay*, *az* must be 3-ranged tensors with equal sizes and the color of line is proportional to $\sqrt{\{ax^2 + ay^2 + az^2\}}$.

4.15 Other plotting

These functions perform miscellaneous plotting. There is unstructured data points plots (Dots), surface reconstruction (Crust), surfaces on the triangular or quadrangular mesh (TriPlot, TriCont, QuadPlot), textual formula plotting (Plots by formula), data plots at edges (Dens[XYZ], Cont[XYZ], ContF[XYZ]). Each type of plotting has similar interface. There are 2 kind of versions which handle the arrays of data and coordinates or only single data array. Parameters of color scheme are specified by the string argument. See Section 3.4 [Color scheme], page 128.

densx *dat* ['*sch*'=" `sval=nan`]   [MGL command]
densy *dat* ['*sch*'=" `sval=nan`]   [MGL command]
densz *dat* ['*sch*'=" `sval=nan`]   [MGL command]
void DensX (const mglDataA &*a*, const char **stl*="",   [Method on mglGraph]
  mreal *sVal*=NAN, const char **opt*="")
void DensY (const mglDataA &*a*, const char **stl*="",   [Method on mglGraph]
  mreal *sVal*=NAN, const char **opt*="")
void DensZ (const mglDataA &*a*, const char **stl*="",   [Method on mglGraph]
  mreal *sVal*=NAN, const char **opt*="")
void mgl_dens_x (HMGL *gr*, HCDT *a*, const char **stl*, mreal *sVal*,   [C function]
  const char **opt*)
void mgl_dens_y (HMGL *gr*, HCDT *a*, const char **stl*, mreal *sVal*,   [C function]
  const char **opt*)

void **mgl_dens_z** (HMGL *gr*, HCDT *a*, const char **stl*, mreal *sVal*,   [C function]
      const char **opt*)

    These plotting functions draw density plot in x, y, or z plain. If *a* is a tensor (3-dimensional data) then interpolation to a given *sVal* is performed. These functions are useful for creating projections of the 3D data array to the bounding box. See also [ContXYZ], page 196, [ContFXYZ], page 196, [dens], page 179, Section 4.17 [Data manipulation], page 203. See Section 2.7.8 [Dens projection sample], page 86, for sample code and picture.

contx *dat* [*'sch'=*" sval=nan]   [MGL command]
conty *dat* [*'sch'=*" sval=nan]   [MGL command]
contz *dat* [*'sch'=*" sval=nan]   [MGL command]
void **ContX** (const mglDataA &*a*, const char **stl*="",   [Method on **mglGraph**]
      mreal *sVal*=NAN, const char **opt*="")
void **ContY** (const mglDataA &*a*, const char **stl*="",   [Method on **mglGraph**]
      mreal *sVal*=NAN, const char **opt*="")
void **ContZ** (const mglDataA &*a*, const char **stl*="",   [Method on **mglGraph**]
      mreal *sVal*=NAN, const char **opt*="")
void **mgl_cont_x** (HMGL *gr*, HCDT *a*, const char **stl*, mreal *sVal*,   [C function]
      const char **opt*)
void **mgl_cont_y** (HMGL *gr*, HCDT *a*, const char **stl*, mreal *sVal*,   [C function]
      const char **opt*)
void **mgl_cont_z** (HMGL *gr*, HCDT *a*, const char **stl*, mreal *sVal*,   [C function]
      const char **opt*)

    These plotting functions draw contour lines in x, y, or z plain. If *a* is a tensor (3-dimensional data) then interpolation to a given *sVal* is performed. These functions are useful for creating projections of the 3D data array to the bounding box. See also [ContFXYZ], page 196, [DensXYZ], page 195, [cont], page 179, Section 4.17 [Data manipulation], page 203. See Section 2.7.9 [Cont projection sample], page 87, for sample code and picture.

void **ContX** (const mglDataA &*v*, const mglDataA &*a*,   [Method on **mglGraph**]
      const char **stl*="", mreal *sVal*=NAN, const char **opt*="")
void **ContY** (const mglDataA &*v*, const mglDataA &*a*,   [Method on **mglGraph**]
      const char **stl*="", mreal *sVal*=NAN, const char **opt*="")
void **ContZ** (const mglDataA &*v*, const mglDataA &*a*,   [Method on **mglGraph**]
      const char **stl*="", mreal *sVal*=NAN, const char **opt*="")
void **mgl_cont_x_val** (HMGL *gr*, HCDT *v*, HCDT *a*, const char **stl*,   [C function]
      mreal *sVal*, const char **opt*)
void **mgl_cont_y_val** (HMGL *gr*, HCDT *v*, HCDT *a*, const char **stl*,   [C function]
      mreal *sVal*, const char **opt*)
void **mgl_cont_z_val** (HMGL *gr*, HCDT *v*, HCDT *a*, const char **stl*,   [C function]
      mreal *sVal*, const char **opt*)

    The same as previous with manual contour levels.

contfx *dat* [*'sch'=*" sval=nan]   [MGL command]
contfy *dat* [*'sch'=*" sval=nan]   [MGL command]
contfz *dat* [*'sch'=*" sval=nan]   [MGL command]

void ContFX (const mglDataA &*a*, const char **stl="",   [Method on mglGraph]
      mreal *sVal*=NAN, const char **opt="")
void ContFY (const mglDataA &*a*, const char **stl="",   [Method on mglGraph]
      mreal *sVal*=NAN, const char **opt="")
void ContFZ (const mglDataA &*a*, const char **stl="",   [Method on mglGraph]
      mreal *sVal*=NAN, const char **opt="")
void mgl_contf_x (HMGL *gr*, HCDT *a*, const char **stl, mreal *sVal*,   [C function]
      const char **opt)
void mgl_contf_y (HMGL *gr*, HCDT *a*, const char **stl, mreal *sVal*,   [C function]
      const char **opt)
void mgl_contf_z (HMGL *gr*, HCDT *a*, const char **stl, mreal *sVal*,   [C function]
      const char **opt)

    These plotting functions draw solid contours in x, y, or z plain. If a is a tensor (3-dimensional data) then interpolation to a given *sVal* is performed. These functions are useful for creating projections of the 3D data array to the bounding box. See also [ContFXYZ], page 196, [DensXYZ], page 195, [cont], page 179, Section 4.17 [Data manipulation], page 203. See Section 2.7.10 [ContF projection sample], page 88, for sample code and picture.

void ContFX (const mglDataA &*v*, const mglDataA &*a*,   [Method on mglGraph]
      const char **stl="", mreal *sVal*=NAN, const char **opt="")
void ContFY (const mglDataA &*v*, const mglDataA &*a*,   [Method on mglGraph]
      const char **stl="", mreal *sVal*=NAN, const char **opt="")
void ContFZ (const mglDataA &*v*, const mglDataA &*a*,   [Method on mglGraph]
      const char **stl="", mreal *sVal*=NAN, const char **opt="")
void mgl_contf_x_val (HMGL *gr*, HCDT *v*, HCDT *a*, const char **stl,   [C function]
      mreal *sVal*, const char **opt)
void mgl_contf_y_val (HMGL *gr*, HCDT *v*, HCDT *a*, const char **stl,   [C function]
      mreal *sVal*, const char **opt)
void mgl_contf_z_val (HMGL *gr*, HCDT *v*, HCDT *a*, const char **stl,   [C function]
      mreal *sVal*, const char **opt)

    The same as previous with manual contour levels.

fplot '*y(x)*' ['*pen*'='']   [MGL command]
void FPlot (const char **eqY, const char **pen="",   [Method on mglGraph]
      const char **opt="")
void mgl_fplot (HMGL *gr*, const char **eqY, const char **pen,   [C function]
      const char **opt)

    Draws command function '$y(x)$' at plane $z=Min.z$ where 'x' variable is changed in xrange. You do not need to create the data arrays to plot it. See also [plot], page 167.

fplot '$x(t)$' '$y(t)$' '$z(t)$' ['*pen*'='']   [MGL command]
void FPlot (const char **eqX, const char **eqY, const   [Method on mglGraph]
      char **eqZ, const char **pen, const char **opt="")

void mgl_fplot_xyz (HMGL *gr*, const char **eqX*, const char **eqY*,   [C function]
        const char **eqZ*, const char **pen*, const char **opt*)
    Draws command parametrical curve {'x(t)', 'y(t)', 'z(t)'} where 't' variable is
    changed in range [0, 1]. You do not need to create the data arrays to plot it. See also
    [plot], page 167.

fsurf 'z(*x*,*y*)' ['sch'=']   [MGL command]
void FSurf (const char **eqZ*, const char **sch*="",   [Method on mglGraph]
        const char **opt*="");
void mgl_fsurf (HMGL *gr*, const char **eqZ*, const char **sch*,   [C function]
        const char **opt*);
    Draws command surface for function 'z(x,y)' where 'x', 'y' variable are changed in
    xrange, yrange. You do not need to create the data arrays to plot it. See also [surf],
    page 177.

fsurf 'x(*u*,*v*)' 'y(*u*,*v*)' 'z(*u*,*v*)' ['sch'=']   [MGL command]
void FSurf (const char **eqX*, const char **eqY*, const   [Method on mglGraph]
        char **eqZ*, const char **sch*="", const char **opt*="")
void mgl_fsurf_xyz (HMGL *gr*, const char **eqX*, const char **eqY*,   [C function]
        const char **eqZ*, const char **sch*, const char **opt*)
    Draws command parametrical surface {'x(u,v)', 'y(u,v)', 'z(u,v)'} where 'u', 'v'
    variable are changed in range [0, 1]. You do not need to create the data arrays to
    plot it. See also [surf], page 177.

triplot *idat xdat ydat* ['sch'=']   [MGL command]
triplot *idat xdat ydat zdat* ['sch'=']   [MGL command]
triplot *idat xdat ydat zdat cdat* ['sch'=']   [MGL command]
void TriPlot (const mglDataA &*id*, const mglDataA &*x*,   [Method on mglGraph]
        const mglDataA &*y*, const char **sch*="", const char **opt*="")
void TriPlot (const mglDataA &*id*, const mglDataA &*x*,   [Method on mglGraph]
        const mglDataA &*y*, const mglDataA &*z*, const mglDataA &*c*, const char
        *sch="", const char **opt*="")
void TriPlot (const mglDataA &*id*, const mglDataA &*x*,   [Method on mglGraph]
        const mglDataA &*y*, const mglDataA &*z*, const char **sch*="", const
        char **opt*="")
void mgl_triplot_xy (HMGL *gr*, HCDT *id*, HCDT *x*, HCDT *y*, const   [C function]
        char **sch*, const char **opt*)
void mgl_triplot_xyz (HMGL *gr*, HCDT *id*, HCDT *x*, HCDT *y*, HCDT *z*,   [C function]
        const char **sch*, const char **opt*)
void mgl_triplot_xyzc (HMGL *gr*, HCDT *id*, HCDT *x*, HCDT *y*, HCDT *z*,   [C function]
        HCDT *c*, const char **sch*, const char **opt*)
    The function draws the surface of triangles. Triangle vertexes are set by indexes *id* of
    data points {*x*[i], *y*[i], *z*[i]}. String *sch* sets the color scheme. If string contain '#' then
    wire plot is produced. First dimensions of *id* must be 3 or greater. Arrays *x*, *y*, *z* must
    have equal sizes. Parameter *c* set the colors of triangles (if *id*.ny=*c*.nx) or colors of ver-
    texes (if *x*.nx=*c*.nx). See also [dots], page 200, [crust], page 200, [quadplot], page 199,
    [triangulation], page 239. See Section 2.7.11 [TriPlot and QuadPlot], page 89, for
    sample code and picture.

tricont *vdat idat xdat ydat zdat cdat* ['sch'=']   [MGL command]
tricont *vdat idat xdat ydat zdat* ['sch'=']   [MGL command]
tricont *idat xdat ydat zdat* ['sch'=']   [MGL command]
void TriCont (const mglDataA &*id*, const mglDataA &*x*,   [Method on mglGraph]
        const mglDataA &*y*, const mglDataA &*z*, const mglDataA &*c*, const char
        *sch="", const char **opt*="")
void TriCont (const mglDataA &*id*, const mglDataA &*x*,   [Method on mglGraph]
        const mglDataA &*y*, const mglDataA &*z*, const char **sch*="", const
        char **opt*="")
void TriContV (const mglDataA &*v*, const mglDataA &*id*,   [Method on mglGraph]
        const mglDataA &*x*, const mglDataA &*y*, const mglDataA &*z*, const
        mglDataA &*c*, const char **sch*="", const char **opt*="")
void TriContV (const mglDataA &*v*, const mglDataA &*id*,   [Method on mglGraph]
        const mglDataA &*x*, const mglDataA &*y*, const mglDataA &*z*, const char
        *sch="", const char **opt*="")
void mgl_tricont_xyzc (HMGL *gr*, HCDT *id*, HCDT *x*, HCDT *y*, HCDT *z*,   [C function]
        HCDT *c*, const char **sch*, const char **opt*)
void mgl_tricont_xyz (HMGL *gr*, HCDT *id*, HCDT *x*, HCDT *y*, HCDT *z*,   [C function]
        const char **sch*, const char **opt*)
void mgl_tricont_xyzcv (HMGL *gr*, HCDT *v*, HCDT *id*, HCDT *x*, HCDT *y*,   [C function]
        HCDT *z*, HCDT *c*, const char **sch*, const char **opt*)
void mgl_tricont_xyzv (HMGL *gr*, HCDT *v*, HCDT *id*, HCDT *x*, HCDT *y*,   [C function]
        HCDT *z*, const char **sch*, const char **opt*)
    The function draws contour lines for surface of triangles at $z=v[k]$ (or at $z = Min.z$
    if *sch* contain symbol '_'). Triangle vertexes are set by indexes *id* of data points
    {$x[i]$, $y[i]$, $z[i]$}. Contours are plotted for $z[i,j]=v[k]$ where $v[k]$ are values of data
    array *v*. String *sch* sets the color scheme. Array *c* (if specified) is used for contour
    coloring. First dimensions of *id* must be 3 or greater. Arrays *x*, *y*, *z* must have equal
    sizes. Parameter *c* set the colors of triangles (if *id*.ny=*c*.nx) or colors of vertexes (if
    x.nx=*c*.nx). See also [triplot], page 198, [cont], page 179, [triangulation], page 239.

quadplot *idat xdat ydat* ['sch'=']   [MGL command]
quadplot *idat xdat ydat zdat* ['sch'=']   [MGL command]
quadplot *idat xdat ydat zdat cdat* ['sch'=']   [MGL command]
void QuadPlot (const mglDataA &*id*, const mglDataA &*x*,   [Method on mglGraph]
        const mglDataA &*y*, const char **sch*="", const char **opt*="")
void QuadPlot (const mglDataA &*id*, const mglDataA &*x*,   [Method on mglGraph]
        const mglDataA &*y*, const mglDataA &*z*, const mglDataA &*c*, const char
        *sch="", const char **opt*="")
void QuadPlot (const mglDataA &*id*, const mglDataA &*x*,   [Method on mglGraph]
        const mglDataA &*y*, const mglDataA &*z*, const char **sch*="", const
        char **opt*="")
void mgl_quadplot_xy (HMGL *gr*, HCDT *id*, HCDT *x*, HCDT *y*, const   [C function]
        char **sch*, const char **opt*)
void mgl_quadplot_xyz (HMGL *gr*, HCDT *id*, HCDT *x*, HCDT *y*, HCDT *z*,   [C function]
        const char **sch*, const char **opt*)

void `mgl_quadplot_xyzc` (HMGL *gr*, HCDT *id*, HCDT *x*, HCDT *y*, HCDT *z*,   [C function]
        HCDT *c*, `const char` **sch*, `const char` **opt*)
> The function draws the surface of quadrangles. Quadrangles vertexes are set by indexes *id* of data points {*x*[i], *y*[i], *z*[i]}. String *sch* sets the color scheme. If string contain '`#`' then wire plot is produced. First dimensions of *id* must be 4 or greater. Arrays *x*, *y*, *z* must have equal sizes. Parameter *c* set the colors of quadrangles (if *id*.ny=*c*.nx) or colors of vertexes (if *x*.nx=*c*.nx). See also [triplot], page 198. See Section 2.7.11 [TriPlot and QuadPlot], page 89, for sample code and picture.

`dots` *xdat ydat zdat* ['*sch*'=']   [MGL command]
`dots` *xdat ydat zdat adat* ['*sch*'=']   [MGL command]
void `Dots` (`const mglDataA` *&x*, `const mglDataA` *&y*,   [Method on `mglGraph`]
        `const mglDataA` *&z*, `const char` **sch*="", `const char` **opt*="")
void `Dots` (`const mglDataA` *&x*, `const mglDataA` *&y*,   [Method on `mglGraph`]
        `const mglDataA` *&z*, `const mglDataA` *&a*, `const char` **sch*="", `const`
        `char` **opt*="")
void `mgl_dots` (HMGL *gr*, HCDT *x*, HCDT *y*, HCDT *z*, `const char` **sch*,   [C function]
        `const char` **opt*)
void `mgl_dots_a` (HMGL *gr*, HCDT *x*, HCDT *y*, HCDT *z*, HCDT *a*, `const`   [C function]
        `char` **sch*, `const char` **opt*)
> The function draws the arbitrary placed points {*x*[i], *y*[i], *z*[i]}. String *sch* sets the color scheme. If array *a* is specified then it define colors of dots. Arrays *x*, *y*, *z*, *a* must have equal sizes. See also [crust], page 200, [mark], page 173, [plot], page 167. See Section 2.7.12 [Dots sample], page 90, for sample code and picture.

`crust` *xdat ydat zdat* ['*sch*'=']   [MGL command]
void `Crust` (`const mglDataA` *&x*, `const mglDataA` *&y*,   [Method on `mglGraph`]
        `const mglDataA` *&z*, `const char` **sch*="", `const char` **opt*="")
void `mgl_crust` (HMGL *gr*, HCDT *x*, HCDT *y*, HCDT *z*, `const char` **sch*,   [C function]
        `const char` **opt*)
> The function reconstruct and draws the surface for arbitrary placed points {*x*[i], *y*[i], *z*[i]}. String *sch* sets the color scheme. If string contain '`#`' then wire plot is produced. Arrays *x*, *y*, *z* must have equal sizes. See also [dots], page 200, [triplot], page 198.

4.16 Nonlinear fitting

These functions fit data to formula. Fitting goal is to find formula parameters for the best fit the data points, i.e. to minimize the sum $\sum_i (f(x_i, y_i, z_i) - a_i)^2/s_i^2$. At this, approximation function '`f`' can depend only on one argument '`x`' (1D case), on two arguments '`x,y`' (2D case) and on three arguments '`x,y,z`' (3D case). The function '`f`' also may depend on parameters. Normally the list of fitted parameters is specified by *var* string (like, '`abcd`'). Usually user should supply initial values for fitted parameters by *ini* variable. But if he/she don't supply it then the zeros are used. Parameter *print*=`true` switch on printing the found coefficients to *Message* (see Section 4.2.8 [Error handling], page 140).

Functions Fit() and FitS() do not draw the obtained data themselves. They fill the data *fit* by formula '`f`' with found coefficients and return it. At this, the '`x,y,z`' coordinates are equidistantly distributed in the axis range. Number of points in *fit* is selected as maximal value of *fit* size and the value of *mglFitPnts*. Note, that this functions use GSL library

and do something only if MathGL was compiled with GSL support. See Section 2.9.11 [Nonlinear fitting sample], page 113, for sample code and picture.

`fits` *res adat sdat 'func' 'var'* [*ini=0*]   [MGL command]
`fits` *res xdat adat sdat 'func' 'var'* [*ini=0*]   [MGL command]
`fits` *res xdat ydat adat sdat 'func' 'var'* [*ini=0*]   [MGL command]
`fits` *res xdat ydat zdat adat sdat 'func' 'var'* [*ini=0*]   [MGL command]
`mglData FitS (const mglDataA &`*a*`, const mglDataA &`*s*`,`   [Method on `mglGraph`]
          `const char *`*func*`, const char *`*var*`, const char *`*opt*`="")`
`mglData FitS (const mglDataA &`*a*`, const mglDataA &`*s*`,`   [Method on `mglGraph`]
          `const char *`*func*`, const char *`*var*`, mglData &`*ini*`, const char *`*opt*`="")`
`mglData FitS (const mglDataA &`*x*`, const mglDataA &`*a*`,`   [Method on `mglGraph`]
          `const mglDataA &`*s*`, const char *`*func*`, const char *`*var*`, const char`
          `*`*opt*`="")`
`mglData FitS (const mglDataA &`*x*`, const mglDataA &`*a*`,`   [Method on `mglGraph`]
          `const mglDataA &`*s*`, const char *`*func*`, const char *`*var*`, mglData &`*ini*`,`
          `const char *`*opt*`="")`
`mglData FitS (const mglDataA &`*x*`, const mglDataA &`*y*`,`   [Method on `mglGraph`]
          `const mglDataA &`*a*`, const mglDataA &`*s*`, const char *`*func*`, const char`
          `*`*var*`, const char *`*opt*`="")`
`mglData FitS (const mglDataA &`*x*`, const mglDataA &`*y*`,`   [Method on `mglGraph`]
          `const mglDataA &`*a*`, const mglDataA &`*s*`, const char *`*func*`, const char`
          `*`*var*`, mglData &`*ini*`, const char *`*opt*`="")`
`mglData FitS (const mglDataA &`*x*`, const mglDataA &`*y*`,`   [Method on `mglGraph`]
          `const mglDataA &`*z*`, const mglDataA &`*a*`, const mglDataA &`*s*`, const char`
          `*`*func*`, const char *`*var*`, const char *`*opt*`="")`
`mglData FitS (const mglDataA &`*x*`, const mglDataA &`*y*`,`   [Method on `mglGraph`]
          `const mglDataA &`*z*`, const mglDataA &`*a*`, const mglDataA &`*s*`, const char`
          `*`*func*`, const char *`*var*`, mglData &`*ini*`, const char *`*opt*`="")`
`HMDT mgl_fit_ys (HMGL `*gr*`, HCDT `*a*`, HCDT `*s*`, const char *`*func*`, const`   [C function]
          `char *`*var*`, HMDT `*ini*`, const char *`*opt*`)`
`HMDT mgl_fit_xys (HMGL `*gr*`, HCDT `*x*`, HCDT `*a*`, HCDT `*s*`, const char`   [C function]
          `*`*func*`, const char *`*var*`, HMDT `*ini*`, const char *`*opt*`)`
`HMDT mgl_fit_xyzs (HMGL `*gr*`, HCDT `*x*`, HCDT `*y*`, HCDT `*a*`, HCDT `*s*`, const`   [C function]
          `char *`*func*`, const char *`*var*`, HMDT `*ini*`, const char *`*opt*`)`
`HMDT mgl_fit_xyzas (HMGL `*gr*`, HCDT `*x*`, HCDT `*y*`, HCDT `*z*`, HCDT `*a*`, HCDT`   [C function]
          s`, const char *`*func*`, const char *`*var*`, HMDT `*ini*`, const char *`*opt*`)`
    Fit data along x-, y- and z-directions for array specified parametrically $a[i,j,k](x[i,j,k]$, $y[i,j,k]$, $z[i,j,k]$) with weight factor $s[i,j,k]$.

`fit` *res adat sdat 'func' 'var'* [*ini=0*]   [MGL command]
`fit` *res xdat adat sdat 'func' 'var'* [*ini=0*]   [MGL command]
`fit` *res xdat ydat adat sdat 'func' 'var'* [*ini=0*]   [MGL command]
`fit` *res xdat ydat zdat adat sdat 'func' 'var'* [*ini=0*]   [MGL command]
`mglData Fit (const mglDataA &`*a*`, const char *`*func*`,`   [Method on `mglGraph`]
          `const char *`*var*`, const char *`*opt*`="")`
`mglData Fit (const mglDataA &`*a*`, const char *`*func*`,`   [Method on `mglGraph`]
          `const char *`*var*`, mglData &`*ini*`, const char *`*opt*`="")`

mglData Fit (const mglDataA &*x*, const mglDataA &*a*,   [Method on mglGraph]
        const char *func*, const char *var*, const char *opt*="")
mglData Fit (const mglDataA &*x*, const mglDataA &*a*,   [Method on mglGraph]
        const char *func*, const char *var*, mglData &*ini*, const char *opt*="")
mglData Fit (const mglDataA &*x*, const mglDataA &*y*,   [Method on mglGraph]
        const mglDataA &*a*, const char *func*, const char *var*, const char
        opt="")
mglData Fit (const mglDataA &*x*, const mglDataA &*y*,   [Method on mglGraph]
        const mglDataA &*a*, const char *func*, const char *var*, mglData &*ini*,
        const char *opt*="")
mglData Fit (const mglDataA &*x*, const mglDataA &*y*,   [Method on mglGraph]
        const mglDataA &*z*, const mglDataA &*a*, const char *func*, const char
        var, const char *opt*="")
mglData Fit (const mglDataA &*x*, const mglDataA &*y*,   [Method on mglGraph]
        const mglDataA &*z*, const mglDataA &*a*, const char *func*, const char
        var, mglData &*ini*, const char *opt*="")
HMDT mgl_fit_y (HMGL *gr*, HCDT *a*, const char *func*, const char   [C function]
        var, HMDT *ini*, const char *opt*)
HMDT mgl_fit_xy (HMGL *gr*, HCDT *x*, HCDT *a*, const char *func*,   [C function]
        const char *var*, HMDT *ini*, const char *opt*)
HMDT mgl_fit_xyz (HMGL *gr*, HCDT *x*, HCDT *y*, HCDT *a*, const char   [C function]
        func, const char *var*, HMDT *ini*, const char *opt*)
HMDT mgl_fit_xyza (HMGL *gr*, HCDT *x*, HCDT *y*, HCDT *z*, HCDT *a*, const   [C function]
        char *func*, const char *var*, HMDT *ini*, const char *opt*)
    Fit data along x-, y- and z-directions for array specified parametrically a[i,j,k](x[i,j,k],
    y[i,j,k], z[i,j,k]) with weight factor 1.

mglData Fit2 (const mglDataA &*a*, const char *func*,   [Method on mglGraph]
        const char *var*, const char *opt*="")
mglData Fit2 (mglData &*fit*, const mglDataA &*a*, const   [Method on mglGraph]
        char *func*, const char *var*, mglData &*ini*, const char *opt*="")
mglData Fit3 (mglData &*fit*, const mglDataA &*a*, const   [Method on mglGraph]
        char *func*, const char *var*, const char *opt*="")
mglData Fit3 (mglData &*fit*, const mglDataA &*a*, const   [Method on mglGraph]
        char *func*, const char *var*, mglData &*ini*, const char *opt*="")
HMDT mgl_fit_2 (HMGL *gr*, HCDT *a*, const char *func*, const char   [C function]
        var, HMDT *ini*, const char *opt*)
HMDT mgl_fit_3 (HMGL *gr*, HCDT *a*, const char *func*, const char   [C function]
        var, HMDT *ini*, const char *opt*)
    Fit data along all directions for 2d or 3d arrays *a* with s=1 and *x*, *y*, *z* equidistantly
    distributed in interval [*Min*, *Max*].

putsfit x y ['pre'=" 'fnt'=" size=-1]   [MGL command]
void PutsFit (mglPoint *p*, const char *prefix*="",   [Method on mglGraph]
        const char *font*="", mreal *size*=-1)

void mgl_puts_fit (HMGL *gr*, mreal *x*, mreal *y*, mreal *z*, const   [C function]
        char **prefix, const char **font, mreal *size*)
     Print last fitted formula with found coefficients (as numbers) at position *p0*. The
     string *prefix* will be printed before formula. All other parameters are the same as in
     Section 4.7 [Text printing], page 161.

const char *GetFit ()   [Method on mglGraph]
const char * mgl_get_fit (HMGL *gr*)   [C function]
     Get last fitted formula with found coefficients (as numbers).

4.17 Data manipulation

hist RES *xdat adat*   [MGL command]
hist RES *xdat ydat adat*   [MGL command]
hist RES *xdat ydat zdat adat*   [MGL command]
mglData Hist (const mglDataA &*x*, const mglDataA &*a*,   [Method on mglGraph]
        const char **opt="")
mglData Hist (const mglDataA &*x*, const mglDataA &*y*,   [Method on mglGraph]
        const mglDataA &*a*, const char **opt="")
mglData Hist (const mglDataA &*x*, const mglDataA &*y*,   [Method on mglGraph]
        const mglDataA &*z*, const mglDataA &*a*, const char **opt="")
HMDT mgl_hist_x (HMGL *gr*, HCDT *x*, HCDT *a*, const char **opt)   [C function]
HMDT mgl_hist_xy (HMGL *gr*, HCDT *x*, HCDT *y*, HCDT *a*, const char   [C function]
        **opt)
HMDT mgl_hist_xyz (HMGL *gr*, HCDT *x*, HCDT *y*, HCDT *z*, HCDT *a*, const   [C function]
        char **opt)
     These functions make distribution (histogram) of data. They do not draw the ob-
     tained data themselves. These functions can be useful if user have data defined for
     random points (for example, after PIC simulation) and he want to produce a plot
     which require regular data (defined on grid(s)). The range for grids is always selected
     as axis range. Arrays *x*, *y*, *z* define the positions (coordinates) of random points.
     Array *a* define the data value. Number of points in output array *res* is selected as
     maximal value of *res* size and the value of *mglFitPnts*.

fill *dat 'eq'*   [MGL command]
fill *dat 'eq' vdat*   [MGL command]
fill *dat 'eq' vdat wdat*   [MGL command]
void Fill (mglData &*u*, const char **eq, const char   [Method on mglGraph]
        **opt="")
void Fill (mglData &*u*, const char **eq, const mglDataA   [Method on mglGraph]
        &*v*, const char **opt="")
void Fill (mglData &*u*, const char **eq, const mglDataA   [Method on mglGraph]
        &*v*, const mglDataA &*w*, const char **opt="")
void mgl_data_fill_eq (HMGL *gr*, HMDT *u*, const char **eq, HCDT*v*,   [C function]
        HCDT*w*, const char **opt)
     Fills the value of array 'u' according to the formula in string *eq*. Formula is an
     arbitrary expression depending on variables 'x', 'y', 'z', 'u', 'v', 'w'. Coordinates 'x',
     'y', 'z' are supposed to be normalized in axis range. Variable 'u' is the original value

of the array. Variables 'v' and 'w' are values of arrays *v*, *w* which can be NULL (i.e. can be omitted).

`datagrid` *dat xdat ydat zdat*   [MGL command]
`void DataGrid (mglData &`*u*`, const mglDataA &`*x*`, const`   [Method on `mglGraph`]
     `mglDataA &`*y*`, const mglDataA &`*z*`, const char *`*opt*`="")`
`void mgl_data_grid (HMGL` *gr*`, HMDT` *u*`, HCDT` *x*`, HCDT` *y*`, HCDT` *z,*   [C function]
     `const char *`*opt*`)`
    Fills the value of array 'u' according to the linear interpolation of triangulated surface, found for arbitrary placed points 'x', 'y', 'z'. Interpolation is done at points equidistantly distributed in axis range. NAN value is used for grid points placed outside of triangulated surface.

`pde` RES *'ham' ini_re ini_im* `[dz=0.1 k0=100]`   [MGL command]
`mglData PDE (const char *`*ham*`, const mglDataA &`*ini_re*`,`   [Method on `mglGraph`]
     `const mglDataA &`*ini_im*`, mreal` *dz*`=0.1, mreal` *k0*`=100, const char`
     `*`*opt*`="")`
`HMDT mgl_pde_solve (HMGL` *gr*`, const char *`*ham*`, HCDT` *ini_re*`, HCDT`   [C function]
     ini_im`, mreal` *dz*`, mreal` *k0*`, const char *`*opt*`)`
    Solves equation $du/dz = i*k0*ham(p,q,x,y,z,|u|)[u]$, where $p=-i/k0*d/dx$, $q=-i/k0*d/dy$ are pseudo-differential operators. Parameters *ini_re*, *ini_im* specify real and imaginary part of initial field distribution. Coordinates 'x', 'y', 'z' are supposed to be normalized in axis range. Note, that really this ranges are increased by factor 3/2 for purpose of reducing reflection from boundaries. Parameter *dz* set the step along evolutionary coordinate z. At this moment, simplified form of function *ham* is supported – all "mixed" terms (like 'x*p'->x*d/dx) are excluded. For example, in 2D case this function is effectively $ham = f(p, z) + g(x, z, u)$. However commutable combinations (like 'x*q'->x*d/dy) are allowed. Here variable 'u' is used for field amplitude |u|. This allow one solve nonlinear problems – for example, for nonlinear Shrodinger equation you may set `ham="p^2 + q^2 - u^2"`. You may specify imaginary part for wave absorption, like `ham = "p^2 + i*x*(x>0)"`, but only if dependence on variable 'i' is linear (i.e. $ham = hre + i * him$). See , for sample code and picture.

5 Widget classes

There are set of "window" classes for making a window with MathGL graphics: `mglWindow` and `mglGLUT` for whole window, `Fl_MathGL` and `QMathGL` as widgets. All these classes allow user to show, rotate, export, and change view of the plot using keyboard. Most of them (except `mglGLUT`) also have toolbar and menu for simplifying plot manipulation. All window classes have mostly the same set of functions.

For drawing you can use: `NULL` pointer if you'll update plot manually, global callback function of type `int draw(HMGL gr, void *p)` or `int draw(mglGraph *gr)`, or instance of class derived from `mglDraw` class. This class is defined in `#include <mgl2/window.h>` and have only 2 methods:

```
class mglDraw
{
public:
    virtual int Draw(mglGraph *) { return 0; };
    virtual void Reload() {};
};
```

You should inherit yours class from `mglDraw` and re-implement one or both functions for drawing.

5.1 mglWindow class

This class is derived from mglGraph class (see Chapter 4 [MathGL core], page 135). It is defined in `#include <mgl2/window.h>`. It provide methods for handling window with MathGL graphics. Similar classes are exist for each widget library: `mglQT` in `#include <mgl2/qt.h>`, `mglFLTK` in `#include <mgl2/fltk.h>`, `mglWX` in `#include <mgl2/wx.h>`.

mglWindow (const char *_title_="MathGL")   [Constructor on `mglWindow`]
mglWindow (int (*_draw_)(HMGL _gr_, void *_p_), const   [Constructor on `mglWindow`]
      char *_title_="MathGL", void *_par_=NULL, int _kind_=0, void (*_reload_)(HMGL
      _gr_, void *_p_)=0)
mglWindow (int (*_draw_)(mglGraph *_gr_), const char   [Constructor on `mglWindow`]
      *_title_="MathGL", int _kind_=0)
mglWindow (mglDraw *_draw_, const char   [Constructor on `mglWindow`]
      *_title_="MathGL", int _kind_=0)
HMGL mgl_create_graph_qt (int (*_draw_)(HMGL _gr_, void *_p_), const   [C function]
      char *_title_, void *_par_, void (*_reload_)(HMGL _gr_, void *_p_))
HMGL mgl_create_graph_fltk (int (*_draw_)(HMGL _gr_, void *_p_),   [C function]
      const char *_title_, void *_par_, void (*_reload_)(HMGL _gr_, void *_p_))
HMGL mgl_create_graph_glut (int (*_draw_)(HMGL _gr_, void *_p_),   [C function]
      const char *_title_, void *_par_, void (*_reload_)(HMGL _gr_, void *_p_))
    Creates a window for plotting. Parameter _draw_ sets a pointer to drawing function (this is the name of function) or instance of `mglDraw` class. There is support of a list of plots (frames). So as one can prepare a set of frames at first and redraw it fast later (but it requires more memory). Function should return positive number of frames for the list or zero if it will plot directly. Note, that _draw_ can be `NULL` for displaying static bitmaps only (no animation or slides). Parameter _title_ sets the

title of the window. Parameter *par* contains pointer to data for the plotting function *draw*. Parameter *kind* may have following values: '0' – use FLTK window, '1' – use Qt window.

There are some keys handles for manipulating by the plot: 'a', 'd', 'w', 's' for the rotating; ',', '.' for viewing of the previous or next frames in the list; 'r' for the switching of transparency; 'f' for the switching of lightning; 'x' for hiding (closing) the window.

int RunThr ()   [Method on mglWindow]
int mgl_fltk_thr ()   [C function]
    Run main loop for event handling in separate thread. Note, right now it work for FLTK windows only.

int Run ()   [Method on mglWindow]
int mgl_qt_run ()   [C function]
int mgl_fltk_run ()   [C function]
    Run main loop for event handling. Usually it should be called in a separate thread or as last function call in main().

void SetClickFunc (void (*func)(HMGL gr, void *p))   [Method on mglWindow]
void mgl_set_click_func (void (*func)(HMGL gr, void *p))   [C function]
    Set callback function func which will be called on mouse click.

void ToggleAlpha ()   [Method on mglWindow]
void mgl_wnd_toggle_alpha (HMGL gr)   [C function]
    Switch on/off transparency but do not overwrite switches in user drawing function.

void ToggleLight ()   [Method on mglWindow]
void mgl_wnd_toggle_light (HMGL gr)   [C function]
    Switch on/off lighting but do not overwrite switches in user drawing function.

void ToggleRotate ()   [Method on mglWindow]
void mgl_wnd_toggle_rotate (HMGL gr)   [C function]
    Switch on/off rotation by mouse. Usually, left button is used for rotation, middle button for shift, right button for zoom/perspective.

void ToggleZoom ()   [Method on mglWindow]
void mgl_wnd_toggle_zoom (HMGL gr)   [C function]
    Switch on/off zooming by mouse. Just select rectangular region by mouse and it will be zoomed in.

void ToggleNo ()   [Method on mglWindow]
void mgl_wnd_toggle_no (HMGL gr)   [C function]
    Switch off all zooming and rotation and restore initial state.

void Update ()   [Method on mglWindow]
void mgl_wnd_update (HMGL gr)   [C function]
    Update window contents. This is very useful function for manual updating the plot while long calculation was running in parallel thread.

void ReLoad ()   [Method on `mglWindow`]
void mgl_wnd_reload (HMGL *gr*)   [C function]
> Reload user data and update picture. This function also update number of frames
> which drawing function can create.

void Adjust ()   [Method on `mglWindow`]
void mgl_wnd_adjust (HMGL *gr*)   [C function]
> Adjust size of bitmap to window size.

void NextFrame ()   [Method on `mglWindow`]
void mgl_wnd_next_frame (HMGL *gr*)   [C function]
> Show next frame if one.

void PrevFrame ()   [Method on `mglWindow`]
void mgl_wnd_prev_frame (HMGL *gr*)   [C function]
> Show previous frame if one.

void Animation ()   [Method on `mglWindow`]
void mgl_wnd_animation (HMGL *gr*)   [C function]
> Run/stop slideshow (animation) of frames.

void SetDelay (double *dt*)   [Method on `mglWindow`]
void mgl_wnd_set_delay (HMGL *gr*, double *dt*)   [C function]
> Sets delay for animation in seconds. Default value is 1 sec.

double GetDelay ()   [Method on `mglWindow`]
double mgl_wnd_get_delay (HMGL *gr*)   [C function]
> Gets delay for animation in seconds.

void Setup (bool *clfupd*=`true`, bool *showpos*=`false`)   [Method on `mglWindow`]
void mgl_setup_window (HMGL *gr*, bool *clfupd*, bool *showpos*)   [C function]
> Enable/disable flags for:
>
> - clearing plot before Update();
>
> - showing the last mouse click position in the widget.

mglPoint LastMousePos ()   [Method on `mglWindow`]
void mgl_get_last_mouse_pos (HMGL *gr*, mreal **x*, mreal **y*,   [C function]
        mreal **z*)
> Gets last position of mouse click.

5.2 Fl_MathGL class

Class is FLTK widget which display MathGL graphics. It is defined in `#include`
`<mgl2/fltk.h>`.

void **set_draw** (int (*_draw_)(HMGL _gr_, void *_p_))   [Method on `Fl_MathGL`]
void **set_draw** (int (*_draw_)(mglGraph *_gr_))   [Method on `Fl_MathGL`]
void **set_draw** (mglDraw *_draw_)   [Method on `Fl_MathGL`]
> Sets drawing function as global function or as one from a class `mglDraw`. There is
> support of a list of plots (frames). So as one can prepare a set of frames at first and
> redraw it fast later (but it requires more memory). Function should return positive
> number of frames for the list or zero if it will plot directly. Parameter _par_ contains
> pointer to data for the plotting function _draw_.

void **update** ()   [Method on `Fl_MathGL`]
> Update (redraw) plot.

void **set_angle** (mreal _t_, mreal _p_)   [Method on `Fl_MathGL`]
> Set angles for additional plot rotation

void **set_flag** (int _f_)   [Method on `Fl_MathGL`]
> Set bitwise flags for general state (1-Alpha, 2-Light)

void **set_state** (bool _r_, bool _z_)   [Method on `Fl_MathGL`]
> Set flags for handling mouse: _z_=`true` allow zooming, _r_=`true` allow rota-
> tion/shifting/perspective and so on.

void **set_zoom** (mreal _X1_, mreal _Y1_, mreal _X2_, mreal   [Method on `Fl_MathGL`]
       _Y2_)
> Set zoom in/out region

void **get_zoom** (mreal *_X1_, mreal *_Y1_, mreal *_X2_,   [Method on `Fl_MathGL`]
       mreal *_Y2_)
> Get zoom in/out region

`void` `set_popup` `(const` `Fl_Menu_Item` `*`*pmenu,*   [Method on `Fl_MathGL`]
      `Fl_Widget` `*`*w*, `void` `*`*v*`)`
    Set popup menu pointer

`void` `set_graph` `(mglCanvas` `*`*gr*`)`   [Method on `Fl_MathGL`]
`void` `set_graph` `(mglGraph` `*`*gr*`)`   [Method on `Fl_MathGL`]
    Set new grapher instead of built-in one. Note that Fl_MathGL will automatically
    delete this object at destruction or at new `set_graph()` call.

`HMGL` `get_graph` `()`   [Method on `Fl_MathGL`]
    Get pointer to grapher.

`Fl_Valuator` `*` `tet_val`   [Fl_MathGL option of `Fl_MathGL`]
    Pointer to external tet-angle validator.

`Fl_Valuator` `*` `phi_val`   [Fl_MathGL option of `Fl_MathGL`]
    Pointer to external phi-angle validator.

5.3 QMathGL class

Class is Qt widget which display MathGL graphics. It is defined in `#include <mgl2/qt.h>`.

`void` `setDraw` `(mglDraw` `*`*dr*`)`   [Method on `QMathGL`]
    Sets drawing functions from a class inherited from `mglDraw`.

`void` `setDraw` `(int` `(*`*draw*`)(mglBase` `*`*gr*, `void` `*`*p*`)`, `void`   [Method on `QMathGL`]
    `*`*par*`=NULL)`
`void` `setDraw` `(int` `(*`*draw*`)(mglGraph` `*`*gr*`))`   [Method on `QMathGL`]
    Sets the drawing function *draw*. There is support of a list of plots (frames). So as
    one can prepare a set of frames at first and redraw it fast later (but it requires more

memory). Function should return positive number of frames for the list or zero if it
will plot directly. Parameter *par* contains pointer to data for the plotting function
draw.

void setGraph (mglCanvas **gr*)   [Method on QMathGL]
void setGraph (mglGraph **gr*)   [Method on QMathGL]
     Set pointer to external grapher (instead of built-in one). Note that QMathGL will
     automatically delete this object at destruction or at new `setGraph()` call.

HMGL getGraph ()   [Method on QMathGL]
     Get pointer to grapher.

void setPopup (QMenu **p*)   [Method on QMathGL]
     Set popup menu pointer.

void setSize (int *w*, int *h*)   [Method on QMathGL]
     Set widget/picture sizes

double getRatio ()   [Method on QMathGL]
     Return aspect ratio of the picture.

int getPer ()   [Method on QMathGL]
     Get perspective value in percents.

int getPhi ()   [Method on QMathGL]
     Get Phi-angle value in degrees.

int getTet ()   [Method on QMathGL]
     Get Theta-angle value in degrees.

bool getAlpha ()   [Method on QMathGL]
     Get transparency state.

bool getLight ()   [Method on QMathGL]
     Get lightning state.

bool getZoom ()   [Method on QMathGL]
     Get mouse zooming state.

bool getRotate ()   [Method on QMathGL]
     Get mouse rotation state.

void refresh ()   [Slot on QMathGL]
     Redraw saved bitmap without executing drawing function.

void update ()   [Slot on QMathGL]
     Update picture by executing drawing function.

void copy ()   [Slot on QMathGL]
     Copy graphics to clipboard.

void copyClickCoor ()   [Slot on QMathGL]
     Copy coordinates of click (as text).

void `print` ()   [Slot on `QMathGL`]
    Print current picture.

void `stop` ()   [Slot on `QMathGL`]
    Send signal to stop drawing.

void `adjust` ()   [Slot on `QMathGL`]
    Adjust image size to fit whole widget.

void `nextSlide` ()   [Slot on `QMathGL`]
    Show next slide.

void `prevSlide` ()   [Slot on `QMathGL`]
    Show previous slide.

void `animation` (`bool` st=`true`)   [Slot on `QMathGL`]
    Start/stop animation.

void `setPer` (`int` val)   [Slot on `QMathGL`]
    Set perspective value.

void `setPhi` (`int` val)   [Slot on `QMathGL`]
    Set Phi-angle value.

void `setTet` (`int` val)   [Slot on `QMathGL`]
    Set Theta-angle value.

void `setAlpha` (`bool` val)   [Slot on `QMathGL`]
    Switch on/off transparency.

void `setLight` (`bool` val)   [Slot on `QMathGL`]
    Switch on/off lightning.

void `setGrid` (`bool` val)   [Slot on `QMathGL`]
    Switch on/off drawing of grid for absolute coordinates.

void `setZoom` (`bool` val)   [Slot on `QMathGL`]
    Switch on/off mouse zooming.

void `setRotate` (`bool` val)   [Slot on `QMathGL`]
    Switch on/off mouse rotation.

void `zoomIn` ()   [Slot on `QMathGL`]
    Zoom in graphics.

void `zoomOut` ()   [Slot on `QMathGL`]
    Zoom out graphics.

void `shiftLeft` ()   [Slot on `QMathGL`]
    Shift graphics to left direction.

void `shiftRight` ()   [Slot on `QMathGL`]
    Shift graphics to right direction.

voidshiftUp ()   [Slot on `QMathGL`]
    Shift graphics to up direction.

void shiftDown ()   [Slot on `QMathGL`]
    Shift graphics to down direction.

void restore ()   [Slot on `QMathGL`]
    Restore zoom and rotation to default values.

void exportPNG (QString *fname*="")   [Slot on `QMathGL`]
    Export current picture to PNG file.

void exportPNGs (QString *fname*="")   [Slot on `QMathGL`]
    Export current picture to PNG file (no transparency).

void exportJPG (QString *fname*="")   [Slot on `QMathGL`]
    Export current picture to JPEG file.

void exportBPS (QString *fname*="")   [Slot on `QMathGL`]
    Export current picture to bitmap EPS file.

void exportEPS (QString *fname*="")   [Slot on `QMathGL`]
    Export current picture to vector EPS file.

void exportSVG (QString *fname*="")   [Slot on `QMathGL`]
    Export current picture to SVG file.

void exportGIF (QString *fname*="")   [Slot on `QMathGL`]
    Export current picture to GIF file.

void exportTEX (QString *fname*="")   [Slot on `QMathGL`]
    Export current picture to LaTeX/Tikz file.

void exportTGA (QString *fname*="")   [Slot on `QMathGL`]
    Export current picture to TGA file.

void exportXYZ (QString *fname*="")   [Slot on `QMathGL`]
    Export current picture to XYZ/XYZL/XYZF file.

void exportOBJ (QString *fname*="")   [Slot on `QMathGL`]
    Export current picture to OBJ/MTL file.

void exportSTL (QString *fname*="")   [Slot on `QMathGL`]
    Export current picture to STL file.

void exportOFF (QString *fname*="")   [Slot on `QMathGL`]
    Export current picture to OFF file.

voidsetUsePrimitives (bool *use*)   [Slot on `QMathGL`]
    Enable using list of primitives for frames. This allows frames transformation/zoom
    but requires much more memory. Default value is `true`.

`void setMGLFont (QString path)`   [Slot on `QMathGL`]
  Restore (*path*`=""`) or load font for graphics.

`void about ()`   [Slot on `QMathGL`]
  Show about information.

`void aboutQt ()`   [Slot on `QMathGL`]
  Show information about Qt version.

`void phiChanged (int val)`   [Signal on `QMathGL`]
  Phi angle changed (by mouse or by toolbar).

`void tetChanged (int val)`   [Signal on `QMathGL`]
  Tet angle changed (by mouse or by toolbar).

`void perChanged (int val)`   [Signal on `QMathGL`]
  Perspective changed (by mouse or by toolbar).

`void alphaChanged (bool val)`   [Signal on `QMathGL`]
  Transparency changed (by toolbar).

`void lightChanged (bool val)`   [Signal on `QMathGL`]
  Lighting changed (by toolbar).

`void gridChanged (bool val)`   [Signal on `QMathGL`]
  Grid drawing changed (by toolbar).

`void zoomChanged (bool val)`   [Signal on `QMathGL`]
  Zooming changed (by toolbar).

`void rotateChanged (bool val)`   [Signal on `QMathGL`]
  Rotation changed (by toolbar).

`void mouseClick (mreal x, mreal y, mreal z)`   [Signal on `QMathGL`]
  Mouse click take place at position {x,y,z}.

`void frameChanged (int val)`   [Signal on `QMathGL`]
  Need another frame to show.

`void showWarn (QString warn)`   [Signal on `QMathGL`]
  Need to show warning.

`void posChanged (QString pos)`   [Signal on `QMathGL`]
  Position of mouse click is changed.

`void objChanged (int id)`   [Signal on `QMathGL`]
  Object id is changed (due to mouse click).

`void refreshData ()`   [Signal on `QMathGL`]
  Data can be changed (drawing is finished).

`QString appName`   [QMathGL option of `QMathGL`]
  Application name for message boxes.

`bool autoResize`   [QMathGL option of `QMathGL`]
  Allow auto resizing (default is false).

6 Data processing

This chapter describe classes `mglData` and `mglDataC` for working with data arrays of real and complex numbers. Both classes are derived from abstract class `mglDataA`, and can be used as arguments of any plotting functions (see Chapter 4 [MathGL core], page 135). These classes are defined in `#include <mgl2/data.h>` and `#include <mgl2/datac.h>` correspondingly. The classes have mostly the same set of functions for easy and safe allocation, resizing, loading, saving, modifying of data arrays. Also it can numerically differentiate and integrate data, interpolate, fill data by formula and so on. Classes support data with dimensions up to 3 (like function of 3 variables – x,y,z). The internal representation of numbers is mreal (or dual=std::complex<mreal> for `mglDataC`), which can be configured as float or double by selecting option `--enable-double` at the MathGL configuring (see Section 1.3 [Installation], page 2). Float type have smaller size in memory and usually it has enough precision in plotting purposes. However, double type provide high accuracy what can be important for time-axis, for example. Data arrays are denoted by Small Caps (like DAT) if it can be (re-)created by MGL commands.

6.1 Public variables

`mreal * a`	[Variable of `mglData`]
`dual * a`	[Variable of `mglDataC`]

Data array itself. The flat data representation is used. For example, matrix [nx x ny] is presented as flat (1d-) array with length nx*ny. The element with indexes {i, j, k} is a[i+nx*j+nx*ny*k] (indexes are zero based).

`long nx`	[Variable of `mglData`]
`long nx`	[Variable of `mglDataC`]

Number of points in 1st dimensions ('x' dimension).

`long ny`	[Variable of `mglData`]
`long ny`	[Variable of `mglDataC`]

Number of points in 2nd dimensions ('y' dimension).

`long nz`	[Variable of `mglData`]
`long nz`	[Variable of `mglDataC`]

Number of points in 3d dimensions ('z' dimension).

`std::string id`	[Variable of `mglData`]
`std::string id`	[Variable of `mglDataC`]

Names of column (or slice if nz>1) – one character per column.

`bool link`	[Variable of `mglData`]
`bool link`	[Variable of `mglDataC`]

Flag to use external data, i.e. don't delete it.

`mreal GetVal (long i)`	[Method on `mglData`]
`mreal GetVal (long i)`	[Method on `mglDataC`]
`void SetVal (mreal val, long i)`	[Method on `mglData`]

void SetVal (mreal *val*, long *i*)   [Method on `mglDataC`]
    Gets or sets the value in by "flat" index *i* without border checking. Index *i* should
    be in range [0, nx*ny*nz-1].

long GetNx ()   [Method on `mglData`]
long GetNx ()   [Method on `mglDataC`]
long GetNy ()   [Method on `mglData`]
long GetNy ()   [Method on `mglDataC`]
long GetNz ()   [Method on `mglData`]
long GetNz ()   [Method on `mglDataC`]
long mgl_data_get_nx (HCDT *dat*)   [C function]
long mgl_data_get_ny (HCDT *dat*)   [C function]
long mgl_data_get_nz (HCDT *dat*)   [C function]
    Gets the x-, y-, z-size of the data.

mreal mgl_data_get_value (HCDT *dat*, int *i*, int *j*, int *k*)   [C function]
dual mgl_datac_get_value (HCDT *dat*, int *i*, int *j*, int *k*)   [C function]
mreal * mgl_data_value (HMDT *dat*, int *i*, int *j*, int *k*)   [C function]
dual * mgl_datac_value (HADT *dat*, int *i*, int *j*, int *k*)   [C function]
void mgl_data_set_value (HMDT *dat*, mreal *v*, int *i*, int *j*, int *k*) [C function]
void mgl_datac_set_value (HADT *dat*, dual *v*, int *i*, int *j*, int *k*) [C function]
    Gets or sets the value in specified cell of the data with border checking.

const mreal * mgl_data_data (HCDT *dat*)   [C function]
const dual * mgl_datac_data (HCDT *dat*)   [C function]
    Returns pointer to internal data array.

6.2 Data constructor

new DAT [nx=1 'eq']   [MGL command]
new DAT nx ny ['eq']   [MGL command]
new DAT nx ny nz ['eq']   [MGL command]
mglData (int *mx*=1, int *my*=1, int *mz*=1)   [Constructor on `mglData`]
mglDataC (int *mx*=1, int *my*=1, int *mz*=1)   [Constructor on `mglDataC`]
HMDT mgl_create_data ()   [C function]
HMDT mgl_create_data_size (int *mx*, int *my*, int *mz*)   [C function]
HADT mgl_create_datac ()   [C function]
HADT mgl_create_datac_size (int *mx*, int *my*, int *mz*)   [C function]
    Default constructor. Allocates the memory for data array and initializes it by zero.
    If string *eq* is specified then data will be filled by corresponding formula as in [fill],
    page 221.

copy DAT *dat2* ['eq'="]   [MGL command]
copy DAT val   [MGL command]
mglData (const mglDataA &*dat2*)   [Constructor on `mglData`]
mglData (const mglDataA *dat2*)   [Constructor on `mglData`]
mglData (int *size*, const float *dat2*)   [Constructor on `mglData`]
mglData (int *size*, int *cols*, const float *dat2*)   [Constructor on `mglData`]

mglData (int *size*, const double **dat2*)   [Constructor on `mglData`]
mglData (int *size*, int *cols*, const double **dat2*)   [Constructor on `mglData`]
mglData (const double **dat2*, int *size*)   [Constructor on `mglData`]
mglData (const double **dat2*, int *size*, int *cols*)   [Constructor on `mglData`]
mglDataC (const mglDataA &*dat2*)   [Constructor on `mglDataC`]
mglDataC (const mglDataA **dat2*)   [Constructor on `mglDataC`]
mglDataC (int *size*, const float **dat2*)   [Constructor on `mglDataC`]
mglDataC (int *size*, int *cols*, const float **dat2*)   [Constructor on `mglDataC`]
mglDataC (int *size*, const double **dat2*)   [Constructor on `mglDataC`]
mglDataC (int *size*, int *cols*, const double **dat2*)   [Constructor on `mglDataC`]
mglDataC (int *size*, const dual **dat2*)   [Constructor on `mglDataC`]
mglDataC (int *size*, int *cols*, const dual **dat2*)   [Constructor on `mglDataC`]

   Copy constructor. Allocates the memory for data array and copy values from other
   array. At this, if parameter *eq* is specified then the data will be modified by corre-
   sponding formula similarly to [fill], page 221.

read DAT *'fname'*   [MGL command]
mglData (const char **fname*)   [Constructor on `mglData`]
mglDataC (const char **fname*)   [Constructor on `mglDataC`]
HMDT mgl_create_data_file (const char **fname*)   [C function]
HADT mgl_create_datac_file (const char **fname*)   [C function]

   Reads data from tab-separated text file with auto determining sizes of the data.

delete *dat*   [MGL command]
~mglData ()   [Destructor on `mglData`]
void mgl_delete_data (HMDT *dat*)   [C function]
~mglDataC ()   [Destructor on `mglDataC`]
void mgl_delete_datac (HADT *dat*)   [C function]

   Deletes the instance of class mglData.

6.3 Data resizing

new DAT [nx=1 ny=1 nz=1]   [MGL command]
void Create (int *mx*, int *my*=1, int *mz*=1)   [Method on `mglData`]
void Create (int *mx*, int *my*=1, int *mz*=1)   [Method on `mglDataC`]
void mgl_data_create (HMDT *dat*, int *mx*, int *my*, int *mz*)   [C function]
void mgl_datac_create (HADT *dat*, int *mx*, int *my*, int *mz*)   [C function]

   Creates or recreates the array with specified size and fills it by zero. This function
   does nothing if one of parameters *mx*, *my*, *mz* is zero or negative.

rearrange *dat* mx [my=0 mz=0]   [MGL command]
void Rearrange (int *mx*, int *my*=0, int *mz*=0)   [Method on `mglData`]
void Rearrange (int *mx*, int *my*=0, int *mz*=0)   [Method on `mglDataC`]
void mgl_data_rearrange (HMDT *dat*, int *mx*, int *my*, int *mz*)   [C function]
void mgl_datac_rearrange (HADT *dat*, int *mx*, int *my*, int *mz*)   [C function]

   Rearrange dimensions without changing data array so that resulting sizes should be
   mx*my*mz < nx*ny*nz. If some of parameter *my* or *mz* are zero then it will be

selected to optimal fill of data array. For example, if $my=0$ then it will be change to $my=$nx*ny*nz$/mx$ and $mz=1$.

transpose dat ['dim'='yxz']   [MGL command]
void Transpose (const char *dim="yx")   [Method on mglData]
void Transpose (const char *dim="yx")   [Method on mglDataC]
void mgl_data_transpose (HMDT dat, const char *dim)   [C function]
void mgl_datac_transpose (HADT dat, const char *dim)   [C function]
  Transposes (shift order of) dimensions of the data. New order of dimensions is spec-
  ified in string dim. This function can be useful also after reading of one-dimensional
  data.

extend dat n1 [n2=0]   [MGL command]
void Extend (int $n1$, int $n2$=0)   [Method on mglData]
void Extend (int $n1$, int $n2$=0)   [Method on mglDataC]
void mgl_data_extend (HMDT dat, int $n1$, int $n2$)   [C function]
void mgl_datac_extend (HADT dat, int $n1$, int $n2$)   [C function]
  Increase the dimensions of the data by inserting new ($|n1|$+1)-th slices after (for
  $n1$>0) or before (for $n1$<0) of existed one. It is possible to insert 2 dimensions si-
  multaneously for 1d data by using parameter $n2$. Data to new slices is copy from
  existed one. For example, for $n1$>0 new array will be $a_{ij}^{new} = a_i^{old}$ where j=0...$n1$.
  Correspondingly, for $n1$<0 new array will be $a_{ij}^{new} = a_j^{old}$ where i=0...$|n1|$.

squeeze dat rx [ry=1 rz=1 sm=off]   [MGL command]
void Squeeze (int rx, int ry=1, int rz=1, bool   [Method on mglData]
  $smooth$=false)
void Squeeze (int rx, int ry=1, int rz=1, bool   [Method on mglDataC]
  $smooth$=false)
void mgl_data_squeeze (HMDT dat, int rx, int ry, int rz, int   [C function]
  $smooth$)
void mgl_datac_squeeze (HADT dat, int rx, int ry, int rz, int   [C function]
  $smooth$)
  Reduces the data size by excluding data elements which indexes are not divisible by
  rx, ry, rz correspondingly. Parameter $smooth$ set to use smoothing (i.e. $a_{out}[i] =$
  $\sum_{j=i,i+r} a[j]/r$) or not (i.e. $a_{out}[i] = a[j*r]$).

crop dat n1 n2 'dir'   [MGL command]
void Crop (int $n1$, int $n2$, char dir='x')   [Method on mglData]
void Crop (int $n1$, int $n2$, char dir='x')   [Method on mglDataC]
void mgl_data_crop (HMDT dat, int $n1$, int $n2$, char dir)   [C function]
void mgl_datac_crop (HADT dat, int $n1$, int $n2$, char dir)   [C function]
  Cuts off edges of the data i<$n1$ and i>$n2$ if $n2$>0 or i>n[xyz]-$n2$ if $n2$<=0 along
  direction dir.

insert dat 'dir' [pos=off num=0]   [MGL command]
void Insert (char dir, int pos=0, int num=1)   [Method on mglData]
void Insert (char dir, int pos=0, int num=1)   [Method on mglDataC]
void mgl_data_insert (HMDT dat, char dir, int pos, char num)   [C function]

void `mgl_datac_insert` (HADT *dat*, char *dir*, int *pos*, char *num*)   [C function]
      Insert *num* slices along *dir*-direction at position *pos* and fill it by zeros.

delete *dat 'dir'* [pos=off num=0]   [MGL command]
void `Delete` (char *dir*, int *pos*=0, int *num*=1)   [Method on `mglData`]
void `Delete` (char *dir*, int *pos*=0, int *num*=1)   [Method on `mglDataC`]
void `mgl_data_delete` (HMDT *dat*, char *dir*, int *pos*, char *num*)   [C function]
void `mgl_datac_delete` (HADT *dat*, char *dir*, int *pos*, char *num*)   [C function]
      Delete *num* slices along *dir*-direction at position *pos*.

sort *dat* idx [idy=-1]   [MGL command]
void `Sort` (lond *idx*, long *idy*=-1)   [Method on `mglData`]
void `mgl_data_sort` (HMDT *dat*, lond *idx*, long *idy*)   [C function]
      Sort data rows (or slices in 3D case) by values of specified column *idx* (or cell {*idx,idy*}
      for 3D case). Note, this function is not thread safe!

clean *dat* idx   [MGL command]
void `Clean` (lond *idx*)   [Method on `mglData`]
void `mgl_data_clean` (HMDT *dat*, lond *idx*)   [C function]
      Delete rows which values are equal to next row for given column *idx*.

join *dat vdat*   [MGL command]
void `Join` (const mglDataA &*vdat*)   [Method on `mglData`]
void `Join` (const mglDataA &*vdat*)   [Method on `mglDataC`]
void `mgl_data_join` (HMDT *dat*, HCDT *vdat*)   [C function]
void `mgl_datac_join` (HADT *dat*, HCDT *vdat*)   [C function]
      Join data cells from *vdat* to *dat*. At this, function increase *dat* sizes according fol-
      lowing: z-size for 3D data arrays arrays with equal x-,y-sizes; or y-size for 2D data
      arrays with equal x-sizes; or x-size otherwise.

6.4 Data filling

list DAT v1 ...   [MGL command]
      Creates new variable with name *dat* and fills it by numeric values of command ar-
      guments `v1 ...`. Command can create one-dimensional and two-dimensional arrays
      with arbitrary values. For creating 2d array the user should use delimiter '|' which
      means that the following values lie in next row. Array sizes are [maximal of row sizes
      * number of rows]. For example, command `list 1 | 2 3` creates the array [1 0; 2 3].
      Note, that the maximal number of arguments is 1000.

list DAT d1 ...   [MGL command]
      Creates new variable with name *dat* and fills it by data values of arrays of command
      arguments *d1* .... Command can create two-dimensional or three-dimensional (if ar-
      rays in arguments are 2d arrays) arrays with arbitrary values. Minor dimensions of all
      arrays in arguments should be equal to dimensions of first array d1. In the opposite
      case the argument will be ignored. Note, that the maximal number of arguments is
      1000.

void Set (const float *A, int NX, int NY=1, int NZ=1)   [Method on mglData]
void Set (const double *A, int NX, int NY=1, int   [Method on mglData]
        NZ=1)
void mgl_data_set_float (HMDT dat, const mreal *A, int NX,   [C function]
        int NY, int NZ)
void mgl_data_set_double (HMDT dat, const double *A, int NX,   [C function]
        int NY, int NZ)
void Set (const float *A, int NX, int NY=1, int   [Method on mglDataC]
        NZ=1)
void Set (const double *A, int NX, int NY=1, int   [Method on mglDataC]
        NZ=1)
void Set (const dual *A, int NX, int NY=1, int NZ=1)   [Method on mglDataC]
void mgl_datac_set_float (HADT dat, const mreal *A, int NX,   [C function]
        int NY, int NZ)
void mgl_datac_set_double (HADT dat, const double *A, int NX,   [C function]
        int NY, int NZ)
void mgl_datac_set_complex (HADT dat, const dual *A, int NX,   [C function]
        int NY, int NZ)
        Allocates memory and copies the data from the **flat** float* or double* array.

void Set (const float **A, int N1, int N2)   [Method on mglData]
void Set (const double **A, int N1, int N2)   [Method on mglData]
void mgl_data_set_mreal2 (HMDT dat, const mreal **A, int N1,   [C function]
        int N2)
void mgl_data_set_double2 (HMDT dat, const double **A, int   [C function]
        N1, int N2)
        Allocates memory and copies the data from the float** or double** array with
        dimensions N1, N2, i.e. from array defined as mreal a[N1][N2];.

void Set (const float ***A, int N1, int N2)   [Method on mglData]
void Set (const double ***A, int N1, int N2)   [Method on mglData]
void mgl_data_set_mreal3 (HMDT dat, const mreal ***A, int N1,   [C function]
        int N2)
void mgl_data_set_double3 (HMDT dat, const double ***A, int   [C function]
        N1, int N2)
        Allocates memory and copies the data from the float*** or double*** array with
        dimensions N1, N2, N3, i.e. from array defined as mreal a[N1][N2][N3];.

void Set (gsl_vector *v)   [Method on mglData]
void Set (gsl_vector *v)   [Method on mglDataC]
void mgl_data_set_vector (HMDT dat, gsl_vector *v)   [C function]
void mgl_datac_set_vector (HADT dat, gsl_vector *v)   [C function]
        Allocates memory and copies the data from the gsl_vector * structure.

void Set (gsl_matrix *m)   [Method on mglData]
void Set (gsl_matrix *m)   [Method on mglDataC]
void mgl_data_set_matrix (HMDT dat, gsl_matrix *m)   [C function]
void mgl_datac_set_matrix (HADT dat, gsl_matrix *m)   [C function]
        Allocates memory and copies the data from the gsl_matrix * structure.

void Set (const mglDataA &*from*)   [Method on mglData]
void Set (HCDT *from*)   [Method on mglData]
void mgl_data_set (HMDT *dat*, HCDT *from*)   [C function]
void Set (const mglDataA &*from*)   [Method on mglDataC]
void Set (HCDT *from*)   [Method on mglDataC]
void mgl_datac_set (HADT *dat*, HCDT *from*)   [C function]
   Copies the data from `mglData` (or `mglDataA`) instance *from*.

void Set (const mglDataA &*re*, const mglDataA &*im*)   [Method on mglDataC]
void Set (HCDT *re*, HCDT *im*)   [Method on mglDataC]
void SetAmpl (HCDT *ampl*, const mglDataA &*phase*)   [Method on mglDataC]
void mgl_datac_set_ri (HADT *dat*, HCDT *re*, HCDT *im*)   [C function]
void mgl_datac_set_ap (HADT *dat*, HCDT *ampl*, HCDT *phase*)   [C function]
   Copies the data from `mglData` instances for real and imaginary parts of complex data
   arrays.

void Set (const std::vector<int> &*d*)   [Method on mglData]
void Set (const std::vector<int> &*d*)   [Method on mglDataC]
void Set (const std::vector<float> &*d*)   [Method on mglData]
void Set (const std::vector<float> &*d*)   [Method on mglDataC]
void Set (const std::vector<double> &*d*)   [Method on mglData]
void Set (const std::vector<double> &*d*)   [Method on mglDataC]
void Set (const std::vector<dual> &*d*)   [Method on mglDataC]
   Allocates memory and copies the data from the `std::vector<T>` array.

void Set (const char **str*, int *NX*, int *NY*=1, int *NZ*=1)   [Method on mglData]
void mgl_data_set_values (const char **str*, int *NX*, int *NY*,   [C function]
      int *NZ*)
void Set (const char **str*, int *NX*, int *NY*=1, int   [Method on mglDataC]
      NZ=1)
void mgl_datac_set_values (const char **str*, int *NX*, int *NY*,   [C function]
      int *NZ*)
   Allocates memory and scanf the data from the string.

void Link (mglData &*from*)   [Method on mglData]
void Link (mreal **A*, int *NX*, int *NY*=1, int *NZ*=1)   [Method on mglData]
void mgl_data_link (HMDT *dat*, mreal **A*, int *NX*, int *NY*, int   [C function]
      NZ)
void Link (mglDataC &*from*)   [Method on mglDataC]
void Link (dual **A*, int *NX*, int *NY*=1, int *NZ*=1)   [Method on mglDataC]
void mgl_datac_link (HADT *dat*, dual **A*, int *NX*, int *NY*, int   [C function]
      NZ)
   Links external data array, i.e. don't delete this array at exit.

var DAT num v1 [v2=nan]   [MGL command]
   Creates new variable with name *dat* for one-dimensional array of size *num*. Array
   elements are equidistantly distributed in range [*v1*, *v2*]. If *v2*=nan then *v2*=*v1* is
   used.

`fill` *dat v1 v2* [*'dir'='x'*]   [MGL command]
`void Fill (mreal` *v1*`, mreal` *v2*`, char` *dir*`='x')`   [Method on `mglData`]
`void Fill (dual` *v1*`, dual` *v2*`, char` *dir*`='x')`   [Method on `mglDataC`]
`void mgl_data_fill (HMDT` *dat*`, mreal` *v1*`, mreal` *v2*`, char` *dir*`)`   [C function]
`void mgl_datac_fill (HADT` *dat*`, dual` *v1*`, dual` *v2*`, char` *dir*`)`   [C function]
  Equidistantly fills the data values to range [*v1*, *v2*] in direction *dir*={'x','y','z'}.

`fill` *dat 'eq'*   [MGL command]
`fill` *dat 'eq' vdat*   [MGL command]
`fill` *dat 'eq' vdat wdat*   [MGL command]
`void Fill (HMGL` *gr*`, const char *`*eq*`, const char *`*opt*`="")`   [Method on `mglData`]
`void Fill (HMGL` *gr*`, const char *`*eq*`, const mglDataA`   [Method on `mglData`]
  `&`*vdat*`, const char *`*opt*`="")`
`void Fill (HMGL` *gr*`, const char *`*eq*`, const mglDataA`   [Method on `mglData`]
  `&`*vdat*`, const mglDataA &`*wdat*`, const char *`*opt*`="")`
`void Fill (HMGL` *gr*`, const char *`*eq*`, const char`   [Method on `mglDataC`]
  `*`*opt*`="")`
`void Fill (HMGL` *gr*`, const char *`*eq*`, const mglDataA`   [Method on `mglDataC`]
  `&`*vdat*`, const char *`*opt*`="")`
`void Fill (HMGL` *gr*`, const char *`*eq*`, const mglDataA`   [Method on `mglDataC`]
  `&`*vdat*`, const mglDataA &`*wdat*`, const char *`*opt*`="")`
`void mgl_data_fill_eq (HMGL` *gr*`, HMDT` *dat*`, const char *`*eq*`, HCDT`   [C function]
  vdat`, HCDT` *wdat*`, const char *`*opt*`)`
`void mgl_datac_fill_eq (HMGL` *gr*`, HADT` *dat*`, const char *`*eq*`, HCDT`   [C function]
  vdat`, HCDT` *wdat*`, const char *`*opt*`)`
  Fills the value of array according to the formula in string *eq*. Formula is an arbitrary
  expression depending on variables 'x', 'y', 'z', 'u', 'v', 'w'. Coordinates 'x', 'y', 'z'
  are supposed to be normalized in axis range of canvas *gr* (in difference from `Modify`
  functions). Variable 'u' is the original value of the array. Variables 'v' and 'w' are
  values of *vdat*, *wdat* which can be `NULL` (i.e. can be omitted).

`modify` *dat 'eq'* [`dim=0`]   [MGL command]
`modify` *dat 'eq' vdat*   [MGL command]
`modify` *dat 'eq' vdat wdat*   [MGL command]
`void Modify (const char *`*eq*`, int` *dim*`=0)`   [Method on `mglData`]
`void Modify (const char *`*eq*`, const mglDataA &`*v*`)`   [Method on `mglData`]
`void Modify (const char *`*eq*`, const mglDataA &`*v*`, const`   [Method on `mglData`]
  `mglDataA &`*w*`)`
`void Modify (const char *`*eq*`, int` *dim*`=0)`   [Method on `mglDataC`]
`void Modify (const char *`*eq*`, const mglDataA &`*v*`)`   [Method on `mglDataC`]
`void Modify (const char *`*eq*`, const mglDataA &`*v*`, const`   [Method on `mglDataC`]
  `mglDataA &`*w*`)`
`void mgl_data_modify (HMDT` *dat*`, const char *`*eq*`, int` *dim*`)`   [C function]
`void mgl_data_modify_vw (HMDT` *dat*`, const char *`*eq*`, HCDT` *v*`,`   [C function]
  `HCDT` *w*`)`
`void mgl_datac_modify (HADT` *dat*`, const char *`*eq*`, int` *dim*`)`   [C function]

void `mgl_datac_modify_vw` (HADT *dat*, const char **eq*, HCDT *v*,   [C function]
    HCDT *w*)
    The same as previous ones but coordinates 'x', 'y', 'z' are supposed to be normalized
    in range [0,1]. If *dim*>0 is specified then modification will be fulfilled only for slices
    >=*dim*.

`fillsample` *dat 'how'*   [MGL command]
void `FillSample` (const char **how*)   [Method on `mglData`]
void `mgl_data_fill_sample` (HMDT *a*, const char **how*)   [mglData]
    Fills data by 'x' or 'k' samples for Hankel ('h') or Fourier ('f') transform.

`datagrid` *dat xdat ydat zdat*   [MGL command]
`mglData Grid` (HMGL *gr*, const `mglDataA` &*x*, const   [Method on `mglData`]
    `mglDataA` &*y*, const `mglDataA` &*z*, const char **opt*="")
void `mgl_data_grid` (HMGL *gr*, HMDT *u*, HCDT *x*, HCDT *y*, HCDT *z*,   [C function]
    const char **opt*)
    Fills the value of array according to the linear interpolation of triangulated surface,
    found for arbitrary placed points 'x', 'y', 'z'. NAN value is used for grid points placed
    outside of triangulated surface.

`put` *dat* val [i=: j=: k=:]   [MGL command]
void `Put` (mreal *val*, int *i*=-1, int *j*=-1, int *k*=-1)   [Method on `mglData`]
void `mgl_data_put_val` (HMDT *a*, mreal *val*, int *i*, int *j*, int *k*)   [mglData]
    Sets value(s) of array a[*i*, *j*, *k*] = *val*. Negative indexes *i*, *j*, *k*=-1 set the value *val*
    to whole range in corresponding direction(s). For example, `Put(val,-1,0,-1);` sets
    a[i,0,j]=*val* for i=0...(nx-1), j=0...(nz-1).

`put` *dat vdat* [i=: j=: k=:]   [MGL command]
void `Put` (const `mglDataA` &*v*, int *i*=-1, int *j*=-1, int   [Method on `mglData`]
    k=-1)
void `mgl_data_put_dat` (HMDT *a*, HCDT *v*, int *i*, int *j*, int *k*)   [mglData]
    Copies value(s) from array *v* to the range of original array. Negative indexes *i*, *j*,
    k=-1 set the range in corresponding direction(s). At this minor dimensions of array
    v should be large than corresponding dimensions of this array. For example, `Put(v,-`
    `1,0,-1);` sets a[i,0,j]=v.ny>nz ? v[i,j] : v[i], where i=0...(nx-1), j=0...(nz-1) and
    condition v.nx>=nx is true.

`idset` *dat 'ids'*   [MGL command]
void `SetColumnId` (const char **ids*)   [Method on `mglData`]
void `mgl_data_set_id` (HMDT *a*, const char **ids*)   [mglData]
void `SetColumnId` (const char **ids*)   [Method on `mglDataC`]
void `mgl_datac_set_id` (HADT *a*, const char **ids*)   [mglData]
    Sets the symbol *ids* for data columns. The string should contain one symbol 'a'...'z'
    per column. These ids are used in [column], page 225.

6.5 File I/O

`read` DAT *'fname'*   [MGL command]
bool `Read` (const char **fname*)   [Method on `mglData`]

`bool Read (const char *`*fname*`)`   [Method on `mglDataC`]
`int mgl_data_read (HMDT `*dat*`, const char *`*fname*`)`   [C function]
`int mgl_datac_read (HADT `*dat*`, const char *`*fname*`)`   [C function]
> Reads data from tab-separated text file with auto determining sizes of the data. Double newline means the beginning of new z-slice.

`read` DAT *'fname'* `mx [my=1 mz=1]`   [MGL command]
`bool Read (const char *`*fname*`, int `*mx*`, int `*my*`=1, int`   [Method on `mglData`]
>   `mz=1)`
`bool Read (const char *`*fname*`, int `*mx*`, int `*my*`=1, int`   [Method on `mglDataC`]
>   `mz=1)`
`int mgl_data_read_dim (HMDT `*dat*`, const char *`*fname*`, int `*mx*`,`   [C function]
>   `int `*my*`, int `*mz*`)`
`int mgl_datac_read_dim (HADT `*dat*`, const char *`*fname*`, int `*mx*`,`   [C function]
>   `int `*my*`, int `*mz*`)`
> Reads data from text file with specified data sizes. This function does nothing if one of parameters *mx*, *my* or *mz* is zero or negative.

`readmat` DAT *'fname'* `[dim=2]`   [MGL command]
`bool ReadMat (const char *`*fname*`, int `*dim*`=2)`   [Method on `mglData`]
`bool ReadMat (const char *`*fname*`, int `*dim*`=2)`   [Method on `mglDataC`]
`int mgl_data_read_mat (HMDT `*dat*`, const char *`*fname*`, int `*dim*`)`   [C function]
`int mgl_datac_read_mat (HADT `*dat*`, const char *`*fname*`, int `*dim*`)`   [C function]
> Read data from text file with size specified at beginning of the file by first *dim* numbers. At this, variable *dim* set data dimensions.

`readall` DAT *'templ'* `v1 v2 [dv=1 slice=off]`   [MGL command]
`void ReadRange (const char *`*templ*`, mreal `*from*`, mreal`   [Method on `mglData`]
>   *to*`, mreal `*step*`=1, bool `*as_slice*`=false)`
`void ReadRange (const char *`*templ*`, mreal `*from*`, mreal`   [Method on `mglDataC`]
>   *to*`, mreal `*step*`=1, bool `*as_slice*`=false)`
`int mgl_data_read_range (HMDT `*dat*`, const char *`*templ*`, mreal`   [C function]
>   *from*`, mreal `*to*`, mreal `*step*`, int `*as_slice*`)`
`int mgl_datac_read_range (HADT `*dat*`, const char *`*templ*`, mreal`   [C function]
>   *from*`, mreal `*to*`, mreal `*step*`, int `*as_slice*`)`
> Join data arrays from several text files. The file names are determined by function call `sprintf(fname,templ,val);`, where *val* changes from *from* to *to* with step *step*. The data load one-by-one in the same slice if *as_slice*=`false` or as slice-by-slice if *as_slice*=`true`.

`readall` DAT *'templ'* `[slice=off]`   [MGL command]
`void ReadAll (const char *`*templ*`, bool `*as_slice*`=false)`   [Method on `mglData`]
`void ReadAll (const char *`*templ*`, bool `*as_slice*`=false)`   [Method on `mglDataC`]
`int mgl_data_read_all (HMDT `*dat*`, const char *`*templ*`, int `*as_slice*`)`   [C function]
`int mgl_datac_read_all (HADT `*dat*`, const char *`*templ*`, int`   [C function]
>   *as_slice*`)`
> Join data arrays from several text files which filenames satisfied the template *templ* (for example, *templ*=`"t_*.dat"`). The data load one-by-one in the same slice if *as_slice*=`false` or as slice-by-slice if *as_slice*=`true`.

save *dat 'fname'*   [MGL command]
void Save (const char *fname*, int *ns*=-1) const   [Method on `mglData`]
void Save (const char *fname*, int *ns*=-1) const   [Method on `mglDataC`]
void mgl_data_save (HCDT *dat*, const char *fname*, int *ns*)   [C function]
void mgl_datac_save (HCDT *dat*, const char *fname*, int *ns*)   [C function]
    Saves the whole data array (for *ns*=-1) or only *ns*-th slice to text file.

readhdf DAT *'fname' 'dname'*   [MGL command]
void ReadHDF (const char *fname*, const char *dname*)   [Method on `mglData`]
void ReadHDF (const char *fname*, const char *dname*)   [Method on `mglDataC`]
void mgl_data_read_hdf (HMDT *dat*, const char *fname*, const   [C function]
      char *dname*)
void mgl_datac_read_hdf (HADT *dat*, const char *fname*, const   [C function]
      char *dname*)
    Reads data array named *dname* from HDF5 or HDF4 file. This function does nothing
    if HDF5|HDF4 was disabled during library compilation.

savehdf *dat 'fname' 'dname'*   [MGL command]
void SaveHDF (const char *fname*, const char *dname*,   [Method on `mglData`]
      bool *rewrite*=false) const
void SaveHDF (const char *fname*, const char *dname*,   [Method on `mglDataC`]
      bool *rewrite*=false) const
void mgl_data_save_hdf (HCDT *dat*, const char *fname*, const   [C function]
      char *dname*, int *rewrite*)
void mgl_datac_save_hdf (HCDT *dat*, const char *fname*, const   [C function]
      char *dname*, int *rewrite*)
    Saves data array named *dname* to HDF5 file. This function does nothing if HDF5
    was disabled during library compilation.

datas *'fname'*   [MGL command]
int DatasHDF (const char *fname*, char *buf*, long *size*)   [Method on `mglData`]
      static
int DatasHDF (const char *fname*, char *buf*, long *size*)   [Method on `mglDataC`]
      static
int mgl_datas_hdf (const char *fname*, char *buf*, long *size*)   [C function]
    Put data names from HDF5 file *fname* into *buf* as '\t' separated fields. In MGL
    version the list of data names will be printed as message. This function does nothing
    if HDF5 was disabled during library compilation.

import DAT *'fname' 'sch'* [v1=0 v2=1]   [MGL command]
void Import (const char *fname*, const char *scheme*,   [Method on `mglData`]
      mreal *v1*=0, mreal *v2*=1)
void mgl_data_import (HMDT *dat*, const char *fname*, const char   [C function]
      scheme, mreal *v1*, mreal *v2*)
    Reads data from bitmap file (now support only PNG format). The RGB values of
    bitmap pixels are transformed to mreal values in range [*v1*, *v2*] using color scheme
    scheme (see Section 3.4 [Color scheme], page 128).

export *dat 'fname' 'sch'* [v1=0 v2=0]   [MGL command]
void Export (const char *fname, const char *scheme,   [Method on mglData]
      mreal *v1*=0, mreal *v2*=0, int *ns*=-1) *const*
void mgl_data_export (HMDT *dat*, const char *fname, const char   [C function]
      scheme, mreal *v1*, mreal *v2*, int *ns*) *const*
> Saves data matrix (or `ns`-th slice for 3d data) to bitmap file (now support only PNG
> format). The data values are transformed from range [*v1*, *v2*] to RGB pixels of bitmap
> using color scheme *scheme* (see Section 3.4 [Color scheme], page 128). If *v1>=v2* then
> the values of *v1*, *v2* are automatically determined as minimal and maximal value of
> the data array.

6.6 Make another data

subdata RES *dat* xx [yy=: zz=:]   [MGL command]
mglData SubData (mreal *xx*, mreal *yy*=-1, mreal *zz*=-1)   [Method on mglData]
      const
mglData SubData (mreal *xx*, mreal *yy*=-1, mreal *zz*=-1)   [Method on mglDataC]
      const
HMDT mgl_data_subdata (HCDT *dat*, mreal *xx*, mreal *yy*, mreal *zz*)   [C function]
> Extracts sub-array data from the original data array keeping fixed positive index. For
> example `SubData(-1,2)` extracts 3d row (indexes are zero based), `SubData(4,-1)`
> extracts 5th column, `SubData(-1,-1,3)` extracts 4th slice and so on. If argument(s)
> are non-integer then linear interpolation between slices is used. In MGL version this
> command usually is used as inline one `dat(xx,yy,zz)`.

subdata RES *dat* xdat [ydat=: zdat=:]   [MGL command]
mglData SubData (const mglDataA &*xx*, const mglDataA   [Method on mglData]
      &*yy*, const mglDataA &*zz*) const
mglData SubData (const mglDataA &*xx*, const mglDataA   [Method on mglDataC]
      &*yy*, const mglDataA &*zz*) const
HMDT mgl_data_subdata_ext (HCDT *dat*, HCDT *xx*, HCDT *yy*, HCDT *zz*)   [C function]
> Extracts sub-array data from the original data array for indexes specified by arrays
> *xx*, *yy*, *zz* (indirect access). This function work like previous one for 1D arguments
> or numbers, and resulting array dimensions are equal dimensions of 1D arrays for
> corresponding direction. For 2D and 3D arrays in arguments, the resulting array
> have the same dimensions as input arrays. The dimensions of all argument must be
> the same (or to be scalar 1*1*1) if they are 2D or 3D arrays. In MGL version this
> command usually is used as inline one `dat(xx,yy,zz)`.

column RES *dat 'eq'*   [MGL command]
mglData Column (const char *eq*) const   [Method on mglData]
mglData Column (const char *eq*) const   [Method on mglDataC]
HMDT mgl_data_column (HCDT *dat*, const char *eq*)   [C function]
> Get column (or slice) of the data filled by formula *eq* on column ids. For example,
> `Column("n*w^2/exp(t)");`. The column ids must be defined first by [idset], page 222
> function or read from files. In MGL version this command usually is used as inline
> one `dat('eq')`.

`resize` RES *dat* `mx` [`my=1 mz=1`]   [MGL command]

`mglData Resize (int` *mx*`, int` *my*`=1, int` *mz*`=1, mreal`   [Method on `mglData`]
         x1`=0, mreal` *x2*`=1, mreal` *y1*`=0, mreal` *y2*`=1, mreal` *z1*`=0, mreal` *z2*`=1)`
         `const`

`mglData Resize (int` *mx*`, int` *my*`=1, int` *mz*`=1, mreal`   [Method on `mglDataC`]
         x1`=0, mreal` *x2*`=1, mreal` *y1*`=0, mreal` *y2*`=1, mreal` *z1*`=0, mreal` *z2*`=1)`
         `const`

`HMDT mgl_data_resize (HCDT` *dat*`, int` *mx*`, int` *my*`, int` *mz*`)`   [C function]

`HMDT mgl_data_resize_box (HCDT` *dat*`, int` *mx*`, int` *my*`, int` *mz*`,`   [C function]
         `mreal` *x1*`, mreal` *x2*`, mreal` *y1*`, mreal` *y2*`, mreal` *z1*`, mreal` *z2*`)`

   Resizes the data to new size *mx*, *my*, *mz* from box (part) [*x1*,*x2*] x [*y1*,*y2*] x [*z1*,*z2*]
   of original array. Initially x,y,z coordinates are supposed to be in [0,1].

`evaluate` RES *dat idat* [`norm=on`]   [MGL command]

`evaluate` RES *dat idat jdat* [`norm=on`]   [MGL command]

`evaluate` RES *dat idat jdat kdat* [`norm=on`]   [MGL command]

`mglData Evaluate (const mglDataA &`*idat*`, bool`   [Method on `mglData`]
         norm`=true) const`

`mglData Evaluate (const mglDataA &`*idat*`, const`   [Method on `mglData`]
         `mglDataA &`*jdat*`, bool` *norm*`=true) const`

`mglData Evaluate (const mglDataA &`*idat*`, const`   [Method on `mglData`]
         `mglDataA &`*jdat*`, const mglDataA &`*kdat*`, bool` *norm*`=true) const`

`mglData Evaluate (const mglDataA &`*idat*`, bool`   [Method on `mglDataC`]
         norm`=true) const`

`mglData Evaluate (const mglDataA &`*idat*`, const`   [Method on `mglDataC`]
         `mglDataA &`*jdat*`, bool` *norm*`=true) const`

`mglData Evaluate (const mglDataA &`*idat*`, const`   [Method on `mglDataC`]
         `mglDataA &`*jdat*`, const mglDataA &`*kdat*`, bool` *norm*`=true) const`

`HMDT mgl_data_evaluate (HCDT` *dat*`, HCDT` *idat*`, HCDT` *jdat*`, HCDT`   [C function]
         kdat`, int` *norm*`)`

   Gets array which values is result of interpolation of original array for coordinates from
   other arrays. All dimensions must be the same for data *idat*, *jdat*, *kdat*. Coordinates
   from *idat*, *jdat*, *kdat* are supposed to be normalized in range [0,1] (if *norm*=`true`) or
   in ranges [0,nx], [0,ny], [0,nz] correspondingly.

`solve` RES *dat* `val` '*dir*' [`norm=on`]   [MGL command]

`solve` RES *dat* `val` '*dir*' *idat* [`norm=on`]   [MGL command]

`mglData Solve (mreal` *val*`, char` *dir*`, bool` *norm*`=true)`   [Method on `mglData`]
         `const`

`mglData Solve (mreal` *val*`, char` *dir*`, const mglDataA &`*idat*`,`   [Method on `mglData`]
         `bool` *norm*`=true) const`

`HMDT mgl_data_solve (HCDT` *dat*`, mreal` *val*`, char` *dir*`, HCDT` *idat*`, int`   [C function]
         norm`)`

   Gets array which values is indexes (roots) along given direction *dir*, where interpolated
   values of data *dat* are equal to *val*. Output data will have the sizes of *dat* in directions
   transverse to *dir*. If data *idat* is provided then its values are used as starting points.
   This allows to find several branches by consequentive calls. Indexes are supposed

to be normalized in range [0,1] (if *norm*=`true`) or in ranges [0,nx], [0,ny], [0,nz] correspondingly. See [Solve sample], page 37, for sample code and picture.

`hist` RES *dat* `num v1 v2` [`nsub=0`]   [MGL command]
`hist` RES *dat* *wdat* `num v1 v2` [`nsub=0`]   [MGL command]
`mglData Hist (int` *n*, `mreal` *v1*=0, `mreal` *v2*=1, `int`   [Method on `mglData`]
        nsub=0`) const`
`mglData Hist (const mglDataA &`*w*, `int` *n*, `mreal` *v1*=0,   [Method on `mglData`]
        `mreal` *v2*=1, `int` *nsub*=0`) const`
`mglData Hist (int` *n*, `mreal` *v1*=0, `mreal` *v2*=1, `int`   [Method on `mglDataC`]
        nsub=0`) const`
`mglData Hist (const mglDataA &`*w*, `int` *n*, `mreal` *v1*=0,   [Method on `mglDataC`]
        `mreal` *v2*=1, `int` *nsub*=0`) const`
`HMDT mgl_data_hist (HCDT` *dat*, `int` *n*, `mreal` *v1*, `mreal` *v2*, `int`   [C function]
        nsub)
`HMDT mgl_data_hist_w (HCDT` *dat*, `HCDT` *w*, `int` *n*, `mreal` *v1*, `mreal`   [C function]
        v2, `int` *nsub*)
    Creates *n*-th points distribution of the data values in range [*v1*, *v2*]. Array *w* specifies
    weights of the data elements (by default is 1). Parameter *nsub* define the number of
    additional interpolated points (for smoothness of histogram). See also Section 4.17
    [Data manipulation], page 203

`momentum` RES *dat* '*how*' ['*dir*'='*z*']   [MGL command]
`mglData Momentum (char` *dir*, `const char *`*how*`) const`   [Method on `mglData`]
`mglData Momentum (char` *dir*, `const char *`*how*`) const`   [Method on `mglDataC`]
`HMDT mgl_data_momentum (HCDT` *dat*, `char` *dir*, `const char *`*how*)   [C function]
    Gets momentum (1d-array) of the data along direction *dir*. String *how* contain kind
    of momentum. The momentum is defined like as $res_k = \sum_{ij} how(x_i, y_j, z_k) a_{ij} / \sum_{ij} a_{ij}$
    if *dir*='z' and so on. Coordinates 'x', 'y', 'z' are data indexes normalized in range
    [0,1].

`sum` RES *dat* '*dir*'   [MGL command]
`mglData Sum (const char *`*dir*`) const`   [Method on `mglData`]
`mglData Sum (const char *`*dir*`) const`   [Method on `mglDataC`]
`HMDT mgl_data_sum (HCDT` *dat*, `const char *`*dir*)   [C function]
    Gets array which is the result of summation in given direction or direction(s).

`max` RES *dat* '*dir*'   [MGL command]
`mglData Max (const char *`*dir*`) const`   [Method on `mglData`]
`mglData Max (const char *`*dir*`) const`   [Method on `mglDataC`]
`HMDT mgl_data_max_dir (HCDT` *dat*, `const char *`*dir*)   [C function]
    Gets array which is the maximal data values in given direction or direction(s).

`min` RES *dat* '*dir*'   [MGL command]
`mglData Min (const char *`*dir*`) const`   [Method on `mglData`]
`mglData Min (const char *`*dir*`) const`   [Method on `mglDataC`]
`HMDT mgl_data_min_dir (HCDT` *dat*, `const char *`*dir*)   [C function]
    Gets array which is the maximal data values in given direction or direction(s).

combine RES *adat bdat*   [MGL command]
`mglData Combine (const mglDataA &`*a*`) const`   [Method on `mglData`]
`mglData Combine (const mglDataA &`*a*`) const`   [Method on `mglDataC`]
`HMDT mgl_data_combine (HCDT `*dat*`, HCDT `*a*`)`   [C function]
    Returns direct multiplication of arrays (like, res[i,j] = this[i]*a[j] and so on).

trace RES *dat*   [MGL command]
`mglData Trace () const`   [Method on `mglData`]
`mglData Trace () const`   [Method on `mglDataC`]
`HMDT mgl_data_trace (HCDT `*dat*`)`   [C function]
    Gets array of diagonal elements a[i,i] (for 2D case) or a[i,i,i] (for 3D case) where
    i=0...nx-1. Function return copy of itself for 1D case. Data array must have dimen-
    sions ny,nz `>=` nx or ny,nz = 1.

`mglData Real () const`   [Method on `mglDataC`]
`HMDT mgl_datac_real (HCDT `*dat*`)`   [C function]
    Gets array of real parts of the data.

`mglData Imag () const`   [Method on `mglDataC`]
`HMDT mgl_datac_imag (HCDT `*dat*`)`   [C function]
    Gets array of imaginary parts of the data.

`mglData Abs () const`   [Method on `mglDataC`]
`HMDT mgl_datac_abs (HCDT `*dat*`)`   [C function]
    Gets array of absolute values of the data.

`mglData Arg () const`   [Method on `mglDataC`]
`HMDT mgl_datac_arg (HCDT `*dat*`)`   [C function]
    Gets array of arguments of the data.

roots RES *'func' ini* ['var'='x']   [MGL command]
roots RES *'func'* `ini` ['var'='x']   [MGL command]
`mglData Roots (const char *`*func*`, char `*var*`) const`   [Method on `mglData`]
`HMDT mgl_data_roots (const char *`*func*`, HCDT `*ini*`, char `*var*`)`   [C function]
`mreal mgl_find_root_txt (const char *`*func*`, mreal `*ini*`, char `*var*`)`   [C function]
    Find roots of equation 'func'=0 for variable *var* with initial guess *ini*. Secant method
    is used for root finding.

6.7 Data changing

These functions change the data in some direction like differentiations, integrations and
so on. The direction in which the change will applied is specified by the string parameter,
which may contain 'x', 'y' or 'z' characters for 1-st, 2-nd and 3-d dimension correspondingly.

cumsum *dat 'dir'*   [MGL command]
`void CumSum (const char *`*dir*`)`   [Method on `mglData`]
`void CumSum (const char *`*dir*`)`   [Method on `mglDataC`]
`void mgl_data_cumsum (HMDT `*dat*`, const char *`*dir*`)`   [C function]
`void mgl_datac_cumsum (HADT `*dat*`, const char *`*dir*`)`   [C function]
    Cumulative summation of the data in given direction or directions.

```
integrate dat 'dir'                                                    [MGL command]
void Integral (const char *dir)                                   [Method on mglData]
void Integral (const char *dir)                                  [Method on mglDataC]
void mgl_data_integral (HMDT dat, const char *dir)                    [C function]
void mgl_datac_integral (HADT dat, const char *dir)                   [C function]
```
> Integrates (like cumulative summation) the data in given direction or directions.

```
diff dat 'dir'                                                         [MGL command]
void Diff (const char *dir)                                       [Method on mglData]
void Diff (const char *dir)                                      [Method on mglDataC]
void mgl_data_diff (HMDT dat, const char *dir)                        [C function]
void mgl_datac_diff (HADT dat, const char *dir)                       [C function]
```
> Differentiates the data in given direction or directions.

```
diff dat xdat ydat [zdat=0]                                           [MGL command]
void Diff (const mglDataA &x, const mglDataA &y)                  [Method on mglData]
void Diff (const mglDataA &x, const mglDataA &y, const           [Method on mglData]
        mglDataA &z)
void mgl_data_diff_par (HMDT dat, HCDT x, HCDTy, HCDTz)               [C function]
```
> Differentiates the data specified parametrically in direction x with y, z=constant. Parametrical differentiation uses the formula (for 2D case): $da/dx = (a_j * y_i - a_i * y_j)/(x_j * y_i - x_i * y_j)$ where $a_i = da/di, a_j = da/dj$ denotes usual differentiation along 1st and 2nd dimensions. The similar formula is used for 3D case. Note, that you may change the order of arguments – for example, if you have 2D data a(i,j) which depend on coordinates $\{x(i,j), y(i,j)\}$ then usual derivative along 'x' will be `Diff(x,y);` and usual derivative along 'y' will be `Diff(y,x);`.

```
diff2 dat 'dir'                                                       [MGL command]
void Diff2 (const char *dir)                                      [Method on mglData]
void Diff2 (const char *dir)                                     [Method on mglDataC]
void mgl_data_diff2 (HMDT dat, const char *dir)                       [C function]
void mgl_datac_diff2 (HADT dat, const char *dir)                      [C function]
```
> Double-differentiates (like Laplace operator) the data in given direction.

```
sinfft dat 'dir'                                                      [MGL command]
void SinFFT (const char *dir)                                     [Method on mglData]
void mgl_data_sinfft (HMDT dat, const char *dir)                      [C function]
```
> Do Sine transform of the data in given direction or directions. The Sine transform is $\sum a_j \sin(kj)$ (see http://en.wikipedia.org/wiki/Discrete_sine_transform#DST-I).

```
cosfft dat 'dir'                                                      [MGL command]
void CosFFT (const char *dir)                                     [Method on mglData]
void mgl_data_cosfft (HMDT dat, const char *dir)                      [C function]
```
> Do Cosine transform of the data in given direction or directions. The Cosine transform is $\sum a_j \cos(kj)$ (see http://en.wikipedia.org/wiki/Discrete_cosine_transform#DCT-I).

void FFT (const char *`dir`)   [Method on `mglDataC`]
void mgl_datac_fft (HADT `dat`, const char *`dir`)   [C function]
>   Do Fourier transform of the data in given direction or directions. If `dir` contain 'i'
>   then inverse Fourier is used. The Fourier transform is $\sum a_j \exp(ikj)$ (see [http://en.](http://en.wikipedia.org/wiki/Discrete_Fourier_transform)
>   [wikipedia.org/wiki/Discrete_Fourier_transform](http://en.wikipedia.org/wiki/Discrete_Fourier_transform)).

hankel `dat` '`dir`'   [MGL command]
void Hankel (const char *`dir`)   [Method on `mglData`]
void Hankel (const char *`dir`)   [Method on `mglDataC`]
void mgl_data_hankel (HMDT `dat`, const char *`dir`)   [C function]
void mgl_datac_hankel (HADT `dat`, const char *`dir`)   [C function]
>   Do Hankel transform of the data in given direction or directions. The Hankel trans-
>   form is $\sum a_j J_0(kj)$ (see http://en.wikipedia.org/wiki/Hankel_transform).

swap `dat` '`dir`'   [MGL command]
void Swap (const char *`dir`)   [Method on `mglData`]
void Swap (const char *`dir`)   [Method on `mglDataC`]
void mgl_data_swap (HMDT `dat`, const char *`dir`)   [C function]
void mgl_datac_swap (HADT `dat`, const char *`dir`)   [C function]
>   Swaps the left and right part of the data in given direction (useful for Fourier spec-
>   trum).

roll `dat` '`dir`' `num`   [MGL command]
void Roll (char `dir`, num)   [Method on `mglData`]
void Roll (char `dir`, num)   [Method on `mglDataC`]
void mgl_data_roll (HMDT `dat`, char `dir`, num)   [C function]
void mgl_datac_roll (HADT `dat`, char `dir`, num)   [C function]
>   Rolls the data along direction `dir`. Resulting array will be out[i] = ini[(i+`num`)%nx]
>   if dir='x'.

mirror `dat` '`dir`'   [MGL command]
void Mirror (const char *`dir`)   [Method on `mglData`]
void Mirror (const char *`dir`)   [Method on `mglDataC`]
void mgl_data_mirror (HMDT `dat`, const char *`dir`)   [C function]
void mgl_datac_mirror (HADT `dat`, const char *`dir`)   [C function]
>   Mirror the left-to-right part of the data in given direction. Looks like change the value
>   index *i->n-i*. Note, that the similar effect in graphics you can reach by using options
>   (see Section 3.7 [Command options], page 132), for example, surf dat; xrange 1 -1.

sew `dat` ['`dir`'='`xyz`' da=2*pi]   [MGL command]
void Sew (const char *`dir`, mreal `da`=2*M_PI)   [Method on `mglData`]
void mgl_data_sew (HMDT `dat`, const char *`dir`, mreal `da`)   [C function]
>   Remove value steps (like phase jumps after inverse trigonometric functions) with
>   period `da` in given direction.

smooth `data` type ['`dir`'='`xyz`']   [MGL command]
void Smooth (const char *`dir`="xyz", mreal `delta`=0)   [Method on `mglData`]
void Smooth (const char *`dir`="xyz", mreal `delta`=0)   [Method on `mglDataC`]
void mgl_data_smooth (HMDT `dat`, const char *`dir`, mreal `delta`)   [C function]

void `mgl_datac_smooth` (HADT *dat*, const char *dir, mreal *delta*)   [C function]
> Smooths the data on specified direction or directions. String *dirs* specifies the dimensions which will be smoothed. It may contain characters: 'x' for 1st dimension, 'y' for 2nd dimension, 'z' for 3d dimension. If string *dir* contain: '0' then does nothing, '3' – linear averaging over 3 points, '5' – linear averaging over 5 points. By default quadratic averaging over 5 points is used.

envelop *dat* ['*dir*'='*x*']   [MGL command]
void `Envelop` (char *dir*='x')   [Method on `mglData`]
void `mgl_data_envelop` (HMDT *dat*, char *dir*)   [C function]
> Find envelop for data values along direction *dir*.

norm *dat* v1 v2 [sym=off dim=0]   [MGL command]
void `Norm` (mreal *v1*=0, mreal *v2*=1, bool *sym*=false,   [Method on `mglData`]
  int *dim*=0)
> Normalizes the data to range [*v1,v2*]. If flag *sym*=true then symmetrical interval [-max(|v1|,|v2|), max(|v1|,|v2|)] is used. Modification will be applied only for slices >=*dim*.

normsl *dat* v1 v2 ['*dir*'='*z*' keep=on sym=off]   [MGL command]
void `NormSl` (mreal *v1*=0, mreal *v2*=1, char *dir*='z',   [Method on `mglData`]
  bool *keep_en*=true, bool *sym*=false)
void `mgl_data_norm_slice` (HMDT *dat*, mreal *v1*, mreal *v2*, char   [C function]
  dir, int *keep_en*, int *sym*)
> Normalizes data slice-by-slice along direction *dir* the data in slices to range [*v1,v2*]. If flag *sym*=true then symmetrical interval [-max(|v1|,|v2|), max(|v1|,|v2|)] is used. If *keep_en* is set then maximal value of k-th slice will be limited by $\sqrt{\sum a_{ij}(k)/\sum a_{ij}(0)}$.

6.8 Interpolation

MGL scripts can use linear interpolation by [subdata], page 225 command, or spline interpolation by [evaluate], page 226 command. Also you can use [resize], page 226 for obtaining a data array with new sizes.

However, there are much special faster functions in other modes (C/C++/Fortran/Python/...). ∎

mreal `Spline` (mreal *x*, mreal *y*=0, mreal *z*=0) const   [Method on `mglData`]
mreal `mgl_data_spline` (HCDT *dat*, mreal *x*, mreal *y*, mreal *z*)   [C function]
> Interpolates data by cubic spline to the given point *x* in [0...nx-1], *y* in [0...ny-1], *z* in [0...nz-1].

mreal `Spline1` (mreal *x*, mreal *y*=0, mreal *z*=0) const   [Method on `mglData`]
> Interpolates data by cubic spline to the given point *x*, *y*, *z* which assumed to be normalized in range [0, 1].

`mreal Spline (mglPoint` *&dif*`, mreal` *x*`, mreal` *y*`=0, mreal`   [Method on `mglData`]
    z`=0) const`
`mreal mgl_data_spline_ext (HCDT` *dat*`, mreal` *x*`, mreal` *y*`, mreal` *z*,   [C function]
    `mreal *`*dx*`, mreal *`*dy*`, mreal *`*dz*`)`
> Interpolates data by cubic spline to the given point *x* in [0...nx-1], *y* in [0...ny-1], *z* in [0...nz-1]. The values of derivatives at the point are saved in *dif*.

`mreal Spline1 (mglPoint` *&dif*`, mreal` *x*`, mreal` *y*`=0,`   [Method on `mglData`]
    `mreal` *z*`=0) const`
> Interpolates data by cubic spline to the given point *x*, *y*, *z* which assumed to be normalized in range [0, 1]. The values of derivatives at the point are saved in *dif*.

`mreal Linear (mreal` *x*`, mreal` *y*`=0, mreal` *z*`=0) const`   [Method on `mglData`]
`dual Linear (mreal` *x*`, mreal` *y*`=0, mreal` *z*`=0) const`   [Method on `mglDataC`]
`mreal mgl_data_linear (HCDT` *dat*`, mreal` *x*`, mreal` *y*`, mreal` *z*`)`   [C function]
`dual mgl_datac_linear (HCDT` *dat*`, mreal` *x*`, mreal` *y*`, mreal` *z*`)`   [C function]
> Interpolates data by linear function to the given point *x* in [0...nx-1], *y* in [0...ny-1], *z* in [0...nz-1].

`mreal Linear1 (mreal` *x*`, mreal` *y*`=0, mreal` *z*`=0) const`   [Method on `mglData`]
`dual Linear1 (mreal` *x*`, mreal` *y*`=0, mreal` *z*`=0) const`   [Method on `mglDataC`]
> Interpolates data by linear function to the given point *x*, *y*, *z* which assumed to be normalized in range [0, 1].

`mreal Linear (mglPoint` *&dif*`, mreal` *x*`, mreal` *y*`=0, mreal`   [Method on `mglData`]
    z`=0) const`
`dual Linear (mglPoint` *&dif*`, mreal` *x*`, mreal` *y*`=0, mreal`   [Method on `mglDataC`]
    z`=0) const`
`mreal mgl_data_linear_ext (HCDT` *dat*`, mreal` *x*`, mreal` *y*`, mreal` *z*,   [C function]
    `mreal *`*dx*`, mreal *`*dy*`, mreal *`*dz*`)`
`dual mgl_datac_linear_ext (HCDT` *dat*`, mreal` *x*`, mreal` *y*`, mreal` *z*,   [C function]
    `dual *`*dx*`, dual *`*dy*`, dual *`*dz*`)`
> Interpolates data by linear function to the given point *x* in [0...nx-1], *y* in [0...ny-1], *z* in [0...nz-1]. The values of derivatives at the point are saved in *dif*.

`mreal Linear1 (mglPoint` *&dif*`, mreal` *x*`, mreal` *y*`=0,`   [Method on `mglData`]
    `mreal` *z*`=0) const`
`dual Linear1 (mglPoint` *&dif*`, mreal` *x*`, mreal` *y*`=0, mreal`   [Method on `mglDataC`]
    z`=0) const`
> Interpolates data by linear function to the given point *x*, *y*, *z* which assumed to be normalized in range [0, 1]. The values of derivatives at the point are saved in *dif*.

6.9 Data information

There are a set of functions for obtaining data properties in MGL language. However most of them can be found using "suffixes". Suffix can get some numerical value of the data array (like its size, maximal or minimal value, the sum of elements and so on) as number. Later it can be used as usual number in command arguments. The suffixes start from point '.' right after (without spaces) variable name or its sub-array. For example, `a.nx` give the

x-size of data a, `b(1).max` give maximal value of second row of variable b, `(c(:,0)^2).sum` give the sum of squares of elements in the first column of c and so on.

`info` *dat*	[MGL command]
`const char * PrintInfo () const`	[Method on `mglData`]
`void PrintInfo (FILE *`*fp*`) const`	[Method on `mglData`]
`const char * PrintInfo () const`	[Method on `mglDataC`]
`void PrintInfo (FILE *`*fp*`) const`	[Method on `mglDataC`]
`const char * mgl_data_info (HCDT` *dat*`)`	[C function]

     Gets or prints to file *fp* or as message (in MGL) information about the data (sizes, maximum/minimum, momentums and so on).

`info` *'txt'*	[MGL command]

     Prints string *txt* as message.

`info` *val*	[MGL command]

     Prints value of number *val* as message.

`(dat) .nx`	[MGL suffix]
`(dat) .ny`	[MGL suffix]
`(dat) .nz`	[MGL suffix]
`long GetNx ()`	[Method on `mglData`]
`long GetNy ()`	[Method on `mglData`]
`long GetNz ()`	[Method on `mglData`]
`long GetNx ()`	[Method on `mglDataC`]
`long GetNy ()`	[Method on `mglDataC`]
`long GetNz ()`	[Method on `mglDataC`]
`long mgl_data_get_nx (HCDT` *dat*`)`	[C function]
`long mgl_data_get_ny (HCDT` *dat*`)`	[C function]
`long mgl_data_get_nz (HCDT` *dat*`)`	[C function]

     Gets the x-, y-, z-size of the data.

`(dat) .max`	[MGL suffix]
`mreal Maximal () const`	[Method on `mglData`]
`mreal Maximal () const`	[Method on `mglDataC`]
`mreal mgl_data_max (HCDT` *dat*`)`	[C function]

     Gets maximal value of the data.

`(dat) .min`	[MGL suffix]
`mreal Minimal () const`	[Method on `mglData`]
`mreal Minimal () const`	[Method on `mglDataC`]
`mreal mgl_data_min (HMDT` *dat*`) const`	[C function]

     Gets minimal value of the data.

`mreal Minimal (int &`*i*`, int &`*j*`, int &`*k*`) const`	[Method on `mglData`]
`mreal Minimal (int &`*i*`, int &`*j*`, int &`*k*`) const`	[Method on `mglDataC`]
`mreal mgl_data_min_int (HCDT` *dat*`, int *`*i*`, int *`*j*`, int *`*k*`)`	[C function]

     Gets position of minimum to variables i, j, k and returns the minimal value.

mreal **Maximal** (int &*i*, int &*j*, int &*k*) const   [Method on mglData]
mreal **Maximal** (int &*i*, int &*j*, int &*k*) const   [Method on mglDataC]
mreal **mgl_data_max_int** (HCDT *dat*, int **i*, int **j*, int **k*)   [C function]
    Gets position of maximum to variables *i*, *j*, *k* and returns the maximal value.

mreal **Minimal** (mreal &*x*, mreal &*y*, mreal &*z*) const   [Method on mglData]
mreal **Minimal** (mreal &*x*, mreal &*y*, mreal &*z*) const   [Method on mglDataC]
mreal **mgl_data_min_real** (HCDT *dat*, mreal **x*, mreal **y*, mreal **z*)   [C function]
    Gets approximated (interpolated) position of minimum to variables *x*, *y*, *z* and returns
    the minimal value.

(dat) **.mx**   [MGL suffix]
(dat) **.my**   [MGL suffix]
(dat) **.mz**   [MGL suffix]
mreal **Maximal** (mreal &*x*, mreal &*y*, mreal &*z*) const   [Method on mglData]
mreal **Maximal** (mreal &*x*, mreal &*y*, mreal &*z*) const   [Method on mglDataC]
mreal **mgl_data_max_real** (HCDT *dat*, mreal **x*, mreal **y*, mreal **z*)   [C function]
    Gets approximated (interpolated) position of maximum to variables *x*, *y*, *z* and returns
    the maximal value.

(dat) **.sum**   [MGL suffix]
(dat) **.ax**   [MGL suffix]
(dat) **.ay**   [MGL suffix]
(dat) **.az**   [MGL suffix]
(dat) **.aa**   [MGL suffix]
(dat) **.wx**   [MGL suffix]
(dat) **.wy**   [MGL suffix]
(dat) **.wz**   [MGL suffix]
(dat) **.wa**   [MGL suffix]
(dat) **.sx**   [MGL suffix]
(dat) **.sy**   [MGL suffix]
(dat) **.sz**   [MGL suffix]
(dat) **.sa**   [MGL suffix]
(dat) **.kx**   [MGL suffix]
(dat) **.ky**   [MGL suffix]
(dat) **.kz**   [MGL suffix]
(dat) **.ka**   [MGL suffix]
mreal **Momentum** (char *dir*, mreal &*a*, mreal &*w*) const   [Method on mglData]
mreal **Momentum** (char *dir*, mreal &*m*, mreal &*w*, mreal   [Method on mglData]
    &*s*, mreal &*k*) const
mreal **mgl_data_momentum_val** (HCDT *dat*, char *dir*, mreal **a*,   [C function]
    mreal **w*, mreal **s*, mreal **k*)
    Gets zero-momentum (energy, $I = \sum dat_i$) and write first momentum (median, $a =
\sum \xi_i dat_i / I$), second momentum (width, $w^2 = \sum (\xi_i - a)^2 dat_i / I$), third momentum
(skewness, $s = \sum (\xi_i - a)^3 dat_i / I w^3$) and fourth momentum (kurtosis, $k = \sum (\xi_i -
a)^4 dat_i / 3 I w^4$) to variables. Here ξ is corresponding coordinate if *dir* is ''x'', ''y'' or
''z''. Otherwise median is $a = \sum dat_i / N$, width is $w^2 = \sum (dat_i - a)^2 / N$ and so on.

(dat) `.fst`   [MGL suffix]
`mreal Find (const char *`*cond*`, int &`*i*`, int &`*j*`, int &`*k*`)`   [Method on `mglData`]
          `const`
`mreal mgl_data_first (HCDT `*dat*`, const char *`*cond*`, int *`*i*`, int *`*j*`,`   [C function]
          `int *`*k*`)`
     Find position (after specified in *i*, *j*, *k*) of first nonzero value of formula *cond*. Function
     return the data value at found position.

(dat) `.lst`   [MGL suffix]
`mreal Last (const char *`*cond*`, int &`*i*`, int &`*j*`, int &`*k*`)`   [Method on `mglData`]
          `const`
`mreal mgl_data_last (HCDT `*dat*`, const char *`*cond*`, int *`*i*`, int *`*j*`,`   [C function]
          `int *`*k*`)`
     Find position (before specified in *i*, *j*, *k*) of last nonzero value of formula *cond*. Func-
     tion return the data value at found position.

`int Find (const char *`*cond*`, char `*dir*`, int `*i*`=0, int `*j*`=0,`   [Method on `mglData`]
          `int `*k*`=0) const`
`mreal mgl_data_find (HCDT `*dat*`, const char *`*cond*`, int `*i*`, int `*j*`,`   [C function]
          `int `*k*`)`
     Return position of first in direction *dir* nonzero value of formula *cond*. The search is
     started from point {i,j,k}.

`bool FindAny (const char *`*cond*`) const`   [Method on `mglData`]
`mreal mgl_data_find_any (HCDT `*dat*`, const char *`*cond*`)`   [C function]
     Determines if any nonzero value of formula in the data array.

(dat) `.a`   [MGL suffix]
     Give first (for `.a`, i.e. `dat->a[0]`).

6.10 Operators

`copy` DAT *dat2* [`'eq'=`"]   [MGL command]
`void operator= (const mglDataA &`*d*`)`   [Method on `mglData`]
     Copies data from other variable.

`copy` *dat* `val`   [MGL command]
`void operator= (mreal `*val*`)`   [Method on `mreal`]
     Set all data values equal to *val*.

`multo` *dat* *dat2*   [MGL command]
`multo` *dat* `val`   [MGL command]
`void operator*= (const mglDataA &`*d*`)`   [Method on `mglData`]
`void operator*= (mreal `*d*`)`   [Method on `mglData`]
`void mgl_data_mul_dat (HMDT `*dat*`, HCDT `*d*`)`   [C function]
`void mgl_data_mul_num (HMDT `*dat*`, mreal `*d*`)`   [C function]
     Multiplies data element by the other one or by value.

`divto` *dat dat2*	[MGL command]
`divto` *dat* `val`	[MGL command]
`void operator/= (const mglDataA &`*d*`)`	[Method on `mglData`]
`void operator/= (mreal `*d*`)`	[Method on `mglData`]
`void mgl_data_div_dat (HMDT `*dat*`, HCDT `*d*`)`	[C function]
`void mgl_data_div_num (HMDT `*dat*`, mreal `*d*`)`	[C function]

   Divides each data element by the other one or by value.

`addto` *dat dat2*	[MGL command]
`addto` *dat* `val`	[MGL command]
`void operator+= (const mglDataA &`*d*`)`	[Method on `mglData`]
`void operator+= (mreal `*d*`)`	[Method on `mglData`]
`void mgl_data_add_dat (HMDT `*dat*`, HCDT `*d*`)`	[C function]
`void mgl_data_add_num (HMDT `*dat*`, mreal `*d*`)`	[C function]

   Adds to each data element the other one or the value.

`subto` *dat dat2*	[MGL command]
`subto` *dat* `val`	[MGL command]
`void operator-= (const mglDataA &`*d*`)`	[Method on `mglData`]
`void operator-= (mreal `*d*`)`	[Method on `mglData`]
`void mgl_data_sub_dat (HMDT `*dat*`, HCDT `*d*`)`	[C function]
`void mgl_data_sub_num (HMDT `*dat*`, mreal `*d*`)`	[C function]

   Subtracts from each data element the other one or the value.

`mglData operator+ (const mglDataA &`*a*`, const mglDataA &`*b*`)`	[Library Function]
`mglData operator+ (mreal `*a*`, const mglDataA &`*b*`)`	[Library Function]
`mglData operator+ (const mglDataA &`*a*`, mreal `*b*`)`	[Library Function]

   Adds the other data or the number.

`mglData operator- (const mglDataA &`*a*`, const mglDataA &`*b*`)`	[Library Function]
`mglData operator- (mreal `*a*`, const mglDataA &`*b*`)`	[Library Function]
`mglData operator- (const mglDataA &`*a*`, mreal `*b*`)`	[Library Function]

   Subtracts the other data or the number.

`mglData operator* (const mglDataA &`*a*`, const mglDataA &`*b*`)`	[Library Function]
`mglData operator* (mreal `*a*`, const mglDataA &`*b*`)`	[Library Function]
`mglData operator* (const mglDataA &`*a*`, mreal `*b*`)`	[Library Function]

   Multiplies by the other data or the number.

`mglData operator/ (const mglDataA &`*a*`, const mglDataA &`*b*`)`	[Library Function]
`mglData operator/ (const mglDataA &`*a*`, mreal `*b*`)`	[Library Function]

   Divides by the other data or the number.

6.11 Global functions

These functions are not methods of `mglData` class. However it provide additional functionality to handle data. So I put it in this chapter.

`transform` DAT *'type' real imag*   [MGL command]
`mglData mglTransform (const mglDataA &`*real*`, const`   [Global function]
        `mglDataA &`*imag*`, const char *`*type*`)`
`HMDT mgl_transform (HCDT` *real*`, HCDT` *imag*`, const char *`*type*`)`   [C function]
   Does integral transformation of complex data *real*, *imag* on specified direction. The
   order of transformations is specified in string *type*: first character for x-dimension,
   second one for y-dimension, third one for z-dimension. The possible character are:
   'f' is forward Fourier transformation, 'i' is inverse Fourier transformation, 's' is Sine
   transform, 'c' is Cosine transform, 'h' is Hankel transform, 'n' or ' ' is no transformation.

`transforma` DAT *'type' ampl phase*   [MGL command]
`mglData mglTransformA const mglDataA &`*ampl*`, const`   [Global function]
        `mglDataA &`*phase*`, const char *`*type*`)`
`HMDT mgl_transform_a HCDT` *ampl*`, HCDT` *phase*`, const char *`*type*`)`   [C function]
   The same as previous but with specified amplitude *ampl* and phase *phase* of complex
   numbers.

`fourier` *reDat imDat 'dir'*   [MGL command]
`void mglFourier const mglDataA &`*re*`, const mglDataA &`*im*`,`   [Global function]
        `const char *`*dir*`)`
`void mgl_data_fourier HCDT` *re*`, HCDT` *im*`, const char *`*dir*`)`   [C function]
   Does Fourier transform of complex data *re*+i*im* in directions *dir*. Result is placed
   back into *re* and *im* data arrays.

`stfad` RES *real imag* `dn` ['dir'='x']   [MGL command]
`mglData mglSTFA (const mglDataA &`*real*`, const mglDataA`   [Global function]
        `&`*imag*`, int` *dn*`, char` *dir*`='x')`
`HMDT mgl_data_stfa (HCDT` *real*`, HCDT` *imag*`, int` *dn*`,char` *dir*`)`   [C function]
   Short time Fourier transformation for real and imaginary parts. Output is ampli-
   tude of partial Fourier of length *dn*. For example if *dir*='x', result will have size
   {int(nx/dn), dn, ny} and it will contain $res[i, j, k] = |\sum_d^d nexp(I * j * d) * (real[i *$
   $dn + d, k] + I * imag[i * dn + d, k])|/dn$.

`pde` RES *'ham' ini_re ini_im* [dz=0.1 k0=100]   [MGL command]
`mglData mglPDE (HMGL` *gr*`, const char *`*ham*`, const mglDataA`   [Global function]
        `&`*ini_re*`, const mglDataA &`*ini_im*`, mreal` *dz*`=0.1, mreal` *k0*`=100, const`
        `char *`*opt*`="")`
`HMDT mgl_pde_solve (HMGL` *gr*`, const char *`*ham*`, HCDT` *ini_re*`, HCDT`   [C function]
        ini_im`, mreal` *dz*`, mreal` *k0*`, const char *`*opt*`)`
   Solves equation du/dz = i*k0*ham(p,q,x,y,z,|u|)[u], where p=-i/k0*d/dx,
   q=-i/k0*d/dy are pseudo-differential operators. Parameters *ini_re*, *ini_im* specify
   real and imaginary part of initial field distribution. Parameters *Min*, *Max* set
   the bounding box for the solution. Note, that really this ranges are increased by

factor 3/2 for purpose of reducing reflection from boundaries. Parameter *dz* set the step along evolutionary coordinate z. At this moment, simplified form of function *ham* is supported – all "mixed" terms (like 'x*p'->x*d/dx) are excluded. For example, in 2D case this function is effectively $ham = f(p,z) + g(x,z,u)$. However commutable combinations (like 'x*q'->x*d/dy) are allowed. Here variable 'u' is used for field amplitude |u|. This allow one solve nonlinear problems – for example, for nonlinear Shrodinger equation you may set ham="p^2 + q^2 - u^2". You may specify imaginary part for wave absorption, like ham = "p^2 + i*x*(x>0)", but only if dependence on variable 'i' is linear (i.e. $ham = hre + i*him$). See Section 2.9.12 [PDE solving hints], page 115, for sample code and picture.

ray RES *'ham'* x0 y0 z0 p0 q0 v0 [dt=0.1 tmax=10]   [MGL command]
mglData mglRay (const char *ham, mglPoint r0, mglPoint p0,   [Global function]
        mreal *dt*=0.1, mreal *tmax*=10)
HMDT mgl_ray_trace (const char *ham, mreal x0, mreal y0, mreal   [C function]
        z0, mreal px, mreal py, mreal pz, mreal dt, mreal tmax)
   Solves GO ray equation like dr/dt = d *ham*/dp, dp/dt = -d *ham*/dr. This is Hamiltonian equations for particle trajectory in 3D case. Here *ham* is Hamiltonian which may depend on coordinates 'x', 'y', 'z', momentums 'p'=px, 'q'=py, 'v'=pz and time 't': $ham = H(x,y,z,p,q,v,t)$. The starting point (at t=0) is defined by variables r0, p0. Parameters *dt* and *tmax* specify the integration step and maximal time for ray tracing. Result is array of {x,y,z,p,q,v,t} with dimensions {7 * int(*tmax*/*dt*+1) }.

qo2d RES *'ham'* *ini_re* *ini_im* *ray* [r=1 k0=100 *xx* *yy*]   [MGL command]
mglData mglQO2d (const char *ham, const mglDataA &*ini_re*,   [Global function]
        const mglDataA &*ini_im*, const mglDataA &*ray*, mreal *r*=1, mreal
        k0=100, mglData *xx*=0, mglData *yy*=0)
mglData mglQO2d (const char *ham, const mglDataA &*ini_re*,   [Global function]
        const mglDataA &*ini_im*, const mglDataA &*ray*, mglData &*xx*, mglData
        &*yy*, mreal *r*=1, mreal *k0*=100)
HMDT mgl_qo2d_solve (const char *ham, HCDT *ini_re*, HCDT *ini_im*,   [C function]
        HCDT *ray*, mreal *r*, mreal *k0*, HMDT *xx*, HMDT *yy*)
   Solves equation du/dt = i*k0*ham(p,q,x,y,|u|)[u], where p=-i/k0*d/dx, q=-i/k0*d/dy are pseudo-differential operators (see mglPDE() for details). Parameters *ini_re*, *ini_im* specify real and imaginary part of initial field distribution. Parameters *ray* set the reference ray, i.e. the ray around which the accompanied coordinate system will be maked. You may use, for example, the array created by mglRay() function. Note, that the reference ray **must be** smooth enough to make accompanied coodrinates unambiguity. Otherwise errors in the solution may appear. If *xx* and *yy* are non-zero then Cartesian coordinates for each point will be written into them. See also mglPDE(). See Section 2.9.12 [PDE solving hints], page 115, for sample code and picture.

jacobian RES *xdat* *ydat* [*zdat*]   [MGL command]
mglData mglJacobian (const mglDataA &*x*, const mglDataA   [Global function]
        &*y*)
mglData mglJacobian (const mglDataA &*x*, const mglDataA   [Global function]
        &*y*, const mglDataA &*z*)

HMDT **mgl_jacobian_2d** (HCDT *x*, HCDT *y*)   [C function]
HMDT **mgl_jacobian_3d** (HCDT *x*, HCDT *y*, HCDT *z*)   [C function]
> Computes the Jacobian for transformation {i,j,k} to {x,y,z} where initial coordinates {i,j,k} are data indexes normalized in range [0,1]. The Jacobian is determined by formula det$||dr_\alpha/d\xi_\beta||$ where r={x,y,z} and ξ={i,j,k}. All dimensions must be the same for all data arrays. Data must be 3D if all 3 arrays {x,y,z} are specified or 2D if only 2 arrays {x,y} are specified.

triangulation RES *xdat ydat*   [MGL command]
mglData mglTriangulation (const **mglDataA** &*x*, const   [Global function]
         mglDataA &*y*)
HMDT **mgl_triangulation_2d** (HCDT *x*, HCDT *y*)   [C function]
> Computes triangulation for arbitrary placed points with coordinates {x,y} (i.e. finds triangles which connect points). MathGL use s-hull code for triangulation. The sizes of 1st dimension **must be equal** for all arrays x.nx=y.nx. Resulting array can be used in [triplot], page 198 or [tricont], page 199 functions for visualization of reconstructed surface.

6.12 Evaluate expression

MathGL have a special classes **mglExpr** and **mglExprC** for evaluating of formula specified by the string for real and complex numbers correspondingly. These classes are defined in `#include <mgl2/mgl.h>`. It is the fast variant of formula evaluation. At creation it will be recognized and compiled to tree-like internal code. At evaluation stage only fast calculations are performed. There is no difference between lower or upper case in formulas. If argument value lie outside the range of function definition then function returns NaN. See Section 3.6 [Textual formulas], page 131.

 mglExpr (const char **expr)   [Constructor on **mglExpr**]
 mglExprC (const char **expr)   [Constructor on **mglExprC**]
HMEX **mgl_create_expr** (const char **expr)   [C function]
HAEX **mgl_create_cexpr** (const char **expr)   [C function]
> Parses the formula *expr* and creates formula-tree. Constructor recursively parses the formula and creates a tree-like structure containing functions and operators for fast further evaluating by `Calc()` or `CalcD()` functions.

 ~mglExpr ()   [Destructor on **mglExpr**]
 ~mglExprC ()   [Destructor on **mglExprC**]
void **mgl_delete_expr** (HMEX *ex*)   [C function]
void **mgl_delete_cexpr** (HAEX *ex*)   [C function]
> Deletes the instance of class mglExpr.

mreal **Eval** (mreal *x*, mreal *y*, mreal *z*)   [Method on **mglExpr**]
dual **Eval** (dual *x*, dual *y*, dual *z*)   [Method on **mglExprC**]
mreal **mgl_expr_eval** (HMEX *ex*, mreal *x*, mreal *y*, mreal *z*)   [C function]
dual **mgl_cexpr_eval** (HAEX *ex*, dual *x*, dual *y*, dual *z*)   [C function]
> Evaluates the formula for 'x','r'=x, 'y','n'=y, 'z','t'=z, 'a','u'=u.

mreal **Eval** (mreal *var*[*26*])   [Method on **mglExpr**]
dual **Eval** (dual *var*[*26*])   [Method on **mglExprC**]

`mreal mgl_expr_eval_v (HMEX `*`ex`*`, mreal *`*`var`*`)` [C function]
`dual mgl_expr_eval_v (HAEX `*`ex`*`, dual *`*`var`*`)` [C function]
> Evaluates the formula for variables in array *var*[0,...,'z'-'a'].

`mreal Diff (char `*`dir`*`, mreal `*`x`*`, mreal `*`y`*`, mreal `*`z`*`)` [Method on `mglExpr`]
`mreal mgl_expr_diff (HMEX `*`ex`*`, char `*`dir`*`, mreal `*`x`*`, mreal `*`y`*`, mreal` [C function]
> `z`)
> Evaluates the formula derivation respect to *dir* for 'x','r'=*x*, 'y','n'=*y*,
> 'z','t'=*z*, 'a','u'=*u*.

`mreal Diff (char `*`dir`*`, mreal `*`var`*`[26])` [Method on `mglExpr`]
`mreal mgl_expr_diff_v (HMEX `*`ex`*`, char `*`dir`*`, mreal *`*`var`*`)` [C function]
> Evaluates the formula derivation respect to *dir* for variables in array *var*[0,...,'z'-'a'].

6.13 MGL variables

Class mglVar represent MGL variables. It is needed for parsing MGL scripts (see Section 7.3
[mglParse class], page 244). This class is derived from `mglData` and is defined in `#include`
`<mgl2/mgl.h>`.

`std::wstring s` [Variable of `mglVar`]
> Name of variable.

`mglVar * next` [Variable of `mglVar`]
`mglVar * prev` [Variable of `mglVar`]
> Next and previous variable in the list.

`bool temp` [Variable of `mglVar`]
> Flag of the temporary variable. If `true` the this variable will be removed after script
> execution.

`void void (*func)(void *)` [Variable of `mglVar`]
> Callback function, which will be called at variable destroying.

`void * o` [Variable of `mglVar`]
> Pointer to external object for callback function.

` mglVar ()` [Constructor on `mglVar`]
> Create variable with size 1*1*1.

` ~mglVar ()` [Destructor on `mglVar`]
> Deletes the instance of class mglVar.

`void MoveAfter (mglVar *`*`var`*`)` [Method on `mglVar`]
> Evaluates the formula for 'x','r'=*x*, 'y','n'=*y*, 'z','t'=*z*, 'a','u'=*u*.

7 MGL scripts

MathGL library supports the simplest scripts for data handling and plotting. These scripts can be used independently (with the help of UDAV, mglconv, mglview programs and others , see Section 1.6 [Utilities], page 4) or in the frame of the library using.

7.1 MGL definition

MGL script language is rather simple. Each string is a command. First word of string is the name of command. Other words are command arguments. Command may have up to 1000 arguments (at least for now). Words are separated from each other by space or tabulation symbol. The upper or lower case of words is important, i.e. variables *a* and *A* are different variables. Symbol '#' starts the comment (all characters after # will be ignored). The exception is situation when '#' is a part of some string. Also options can be specified after symbol ';' (see Section 3.7 [Command options], page 132). Symbol ':' starts new command (like new line character) if it is not placed inside a string or inside brackets.

If string contain references to external parameters (substrings '$0', '$1' ... '$9') or definitions (substrings '$a', '$b' ... '$z') then before execution the values of parameter/definition will be substituted instead of reference. It allows to use the same MGL script for different parameters (filenames, paths, condition and so on).

Argument can be a string, a variable (data arrays) or a number (scalars).

- The string is any symbols between ordinary marks ' '. Long strings can be concatenated from several lines by '\' symbol. I.e. the string ''a +'\
' b'' will give string ''a + b'' (here '<br>' is newline). Also you can concatenate strings and numbers using ',' with out spaces (for example, ''max(u)=',u.max,' a.u.'').

- Usually variable have a name which is arbitrary combination of symbols (except spaces and ' ') started from a letter and with length less than 64. A temporary array can be used as variable:

  - sub-arrays (like in [subdata], page 225 command) as command argument. For example, a(1) or a(1,:) or a(1,:,:) is second row, a(:,2) or a(:,2,:) is third column, a(:,:,0) is first slice and so on. Also you can extract a part of array from m-th to n-th element by code a(m:n,:,:) or just a(m:n).

  - any column combinations defined by formulas, like a('n*w^2/exp(t)') if names for data columns was specified (by [idset], page 222 command or in the file at string started with ##).

  - any expression (without spaces) of existed variables produce temporary variable. For example, 'sqrt(dat(:,5)+1)' will produce temporary variable with data values equal to tmp[i,j] = sqrt(dat[i,5,j]+1).

  - temporary variable of higher dimensions by help of []. For example, '[1,2,3]' will produce a temporary vector of 3 elements {1, 2, 3}; '[[11,12],[21,22]]' will produce matrix 2*2 and so on. Here you can join even an arrays of the same dimensions by construction like '[v1,v2,...,vn]'.

  - result of code for making new data (see Section 6.6 [Make another data], page 225) inside {}. For example, '{sum dat 'x'}' produce temporary variable which contain result of summation of *dat* along direction 'x'. This is the same array *tmp* as

produced by command '`sum tmp dat 'x'`'. You can use nested constructions, like
'`{sum {max dat 'z'} 'x'}`'.

Temporary variables can not be used as 1st argument for commands which create
(return) the data (like '`new`', '`read`', '`hist`' and so on).

- Special names `nan=#QNAN`, `pi=3.1415926...`, `on=1`, `off=0`, `:=-1` are treated as number if they were not redefined by user. Variables with suffixes are treated as numbers (see Section 6.9 [Data information], page 232). Names defined by [define], page 242 command are treated as number. Also results of formulas with sizes 1x1x1 are treated as number (for example, '`pi/dat.nx`').

Before the first using all variables must be defined with the help of commands, like, [new], page 215, [var], page 220, [list], page 218, [copy], page 215, [read], page 222, [hist], page 227, [sum], page 227 and so on (see sections Section 6.2 [Data constructor], page 215, Section 6.4 [Data filling], page 218 and Section 6.6 [Make another data], page 225).

Command may have several set of possible arguments (for example, `plot ydat` and `plot xdat ydat`). All command arguments for a selected set must be specified. However, some arguments can have default values. These argument are printed in [], like `text ydat ['stl'='']` or `text x y 'txt' ['fnt'='' size=-1]`. At this, the record `[arg1 arg2 arg3 ...]` means `[arg1 [arg2 [arg3 ...]]]`, i.e. you can omit only tailing arguments if you agree with its default values. For example, `text x y 'txt' '' 1` or `text x y 'txt' ''` is correct, but `text x y 'txt' 1` is incorrect (argument `'fnt'` is missed).

7.2 Program flow commands

Below I show commands to control program flow, like, conditions, loops, define script arguments and so on. Other commands can be found in chapters Chapter 4 [MathGL core], page 135 and Chapter 6 [Data processing], page 214. Note, that some of program flow commands (like [define], page 242, [ask], page 242, [call], page 243, [for], page 243, [func], page 243) should be placed alone in the string.

`chdir` *'path'*   [MGL command]
    Changes the current directory to *path*.

`ask` *$N 'question'*   [MGL command]
    Sets *N*-th script argument to answer which give the user on the *question*. Usually this show dialog with question where user can enter some text as answer. Here *N* is digit (0...9) or alpha (a...z).

`define` *$N smth*   [MGL command]
    Sets *N*-th script argument to *smth*. Note, that *smth* is used as is (with '' symbols if present). Here *N* is digit (0...9) or alpha (a...z).

`define` *name smth*   [MGL command]
    Create scalar variable `name` which have the numeric value of `smth`. Later you can use this variable as usual number. Here *N* is digit (0...9) or alpha (a...z).

`defchr` *$N smth*   [MGL command]
    Sets *N*-th script argument to character with value evaluated from *smth*. Here *N* is digit (0...9) or alpha (a...z).

defnum *$N smth*   [MGL command]
    Sets *N*-th script argument to number with value evaluated from *smth*. Here *N* is digit
    (0...9) or alpha (a...z).

defpal *$N smth*   [MGL command]
    Sets *N*-th script argument to palette character at position evaluated from *smth*. Here
    N is digit (0...9) or alpha (a...z).

call *'fname'* [*ARG1 ARG2 ... ARG9*]   [MGL command]
    Executes function *fname* (or script if function is not found). Optional arguments will
    be passed to functions. See also [func], page 243.

func *'fname'* [*narg=0*]   [MGL command]
    Define the function *fname* and number of required arguments. The arguments will
    be placed in script parameters $1, $2, ... $9. Note, you should stop script execution
    before function definition(s) by command [stop], page 244. See also [return], page 243.

return   [MGL command]
    Return from the function. See also [func], page 243.

if *dat 'cond'*   [MGL command]
    Starts block which will be executed if *dat* satisfy to *cond*.

if val   [MGL command]
    Starts block which will be executed if `val` is nonzero.

elseif *dat 'cond'*   [MGL command]
    Starts block which will be executed if previous `if` or `elseif` is false and *dat* satisfy
    to *cond*.

elseif val   [MGL command]
    Starts block which will be executed if previous `if` or `elseif` is false and `val` is nonzero.

else   [MGL command]
    Starts block which will be executed if previous `if` or `elseif` is false.

endif   [MGL command]
    Finishes `if/elseif/else` block.

for *$N* `v1 v2` [`dv=1`]   [MGL command]
    Starts cycle with *$N*-th argument changing from *v1* to *v2* with the step *dv*. Here *N*
    is digit (0...9) or alpha (a...z).

for *$N dat*   [MGL command]
    Starts cycle with *$N*-th argument changing for *dat* values. Here *N* is digit (0...9) or
    alpha (a...z).

next   [MGL command]
    Finishes `for` cycle.

once val   [MGL command]
    The code between `once on` and `once off` will be executed only once. Useful for large
    data manipulation in programs like UDAV.

`stop`   [MGL command]
>   Terminate execution.

7.3 mglParse class

Class for parsing and executing MGL script. This class is defined in `#include <mgl2/mgl.h>`.

Class mglParse is the interpreter for MGL scripts. The main function of mglParse class is `Execute()`. Exactly this function parses and executes the script string-by-string. Also there are subservient functions for the finding and creation of a variable. These functions can be useful for displaying values of variables (arrays) in some external program (in window, for example). Function `AllowSetSize()` allows one to prevent changing the size of the picture inside the script (forbids the MGL command `setsize`).

`mglParse (bool `*setsize*`=false)`   [Constructor on `mglParse`]
`mglParse (HMPR `*pr*`)`   [Constructor on `mglParse`]
`mglParse (mglParse &`*pr*`)`   [Constructor on `mglParse`]
`HMPR mgl_create_parser ()`   [C function]
>   Constructor initializes all values with zero and set *AllowSetSize* value.

`~mglParse ()`   [Destructor on `mglParse`]
`void mgl_delete_parser (HMPR `*p*`)`   [C function]
>   Destructor delete parser

`HMPR Self ()`   [Method on `mglParse`]
>   Returns the pointer to internal object of type `HMPR`.

`void Execute (mglGraph *`*gr*`, const char *`*text*`)`   [Method on `mglParse`]
`void Execute (mglGraph *`*gr*`, const wchar_t *`*text*`)`   [Method on `mglParse`]
`void mgl_parse_text (HMGL `*gr*`, HMPR `*p*`, const char *`*text*`)`   [C function]
`void mgl_parse_textw (HMGL `*gr*`, HMPR `*p*`, const wchar_t *`*text*`)`   [C function]
>   Main function in the class. Function parse and execute line-by-line MGL script in
>   array *text*. Lines are separated by newline symbol '`\n`' as usual.

`void Execute (mglGraph *`*gr*`, FILE *`*fp*`, bool`   [Method on `mglParse`]
>   *print*`=false)`
`void mgl_parse_file (HMGL `*gr*`, HMPR `*p*`, FILE *`*fp*`, int `*print*`)`   [C function]
>   The same as previous but read script from the file *fp*. If *print*=`true` then all warnings
>   and information will be printed in stdout.

`int Parse (mglGraph *`*gr*`, const char *`*str*`, long `*pos*`=0)`   [Method on `mglParse`]
`int Parse (mglGraph *`*gr*`, const wchar_t *`*str*`, long`   [Method on `mglParse`]
>   *pos*`=0)`
`int mgl_parse_line (HMGL `*gr*`, HMPR `*p*`, const char *`*str*`, int `*pos*`)`   [C function]
`int mgl_parse_linew (HMGL `*gr*`, HMPR `*p*`, const wchar_t *`*str*`, int`   [C function]
>   *pos*`)`
>   Function parses the string *str* and executes it by using *gr* as a graphics plotter.
>   Returns the value depending on an error presence in the string *str*: 0 – no error, 1 –
>   wrong command argument(s), 2 – unknown command, 3 – string is too long. Optional

argument *pos* allows to save the string position in the document (or file) for using
`for|next` command.

`mglData Calc (const char *`*formula*`)`	[Method on `mglParse`]
`mglData Calc (const wchar_t *`*formula*`)`	[Method on `mglParse`]
`HMDT mgl_parser_calc (HMPR `*p*`, const char *`*formula*`)`	[C function]
`HMDT mgl_parser_calcw (HMPR `*p*`, const wchar_t *`*formula*`)`	[C function]

Function parses the string *formula* and return resulting data array. In difference to
`AddVar()` or `FindVar()`, it is usual data array which should be deleted after usage.

`void AddParam (int `*n*`, const char *`*str*`)`	[Method on `mglParse`]
`void AddParam (int `*n*`, const wchar_t *`*str*`)`	[Method on `mglParse`]
`void mgl_parser_add_param (HMPR `*p*`, int `*id*`, const char *`*val*`)`	[C function]
`void mgl_parser_add_paramw (HMPR `*p*`, int `*id*`, const wchar_t` `*`*val*`)`	[C function]

Function set the value of *n*-th parameter as string *str* (*n*=0, 1 ... 'z'-'a'+10). String
str shouldn't contain '$' symbol.

`mglVar * FindVar (const char *`*name*`)`	[Method on `mglParse`]
`mglVar * FindVar (const wchar_t *`*name*`)`	[Method on `mglParse`]
`HMDT mgl_parser_find_var (HMPR `*p*`, const char *`*name*`)`	[C function]
`HMDT mgl_parser_find_varw (HMPR `*p*`, const wchar_t *`*name*`)`	[C function]

Function returns the pointer to variable with name *name* or zero if variable is absent.
Use this function to put external data array to the script or get the data from the
script. You must **not delete** obtained data arrays!

`mglVar * AddVar (const char *`*name*`)`	[Method on `mglParse`]
`mglVar * AddVar (const wchar_t *`*name*`)`	[Method on `mglParse`]
`HMDT mgl_parser_add_var (HMPR `*p*`, const char *`*name*`)`	[C function]
`HMDT mgl_parser_add_varw (HMPR `*p*`, const wchar_t *`*name*`)`	[C function]

Function returns the pointer to variable with name *name*. If variable is absent then
new variable is created with name *name*. Use this function to put external data array
to the script or get the data from the script. You must **not delete** obtained data
arrays!

`void DeleteVar (const char *`*name*`)`	[Method on `mglParse` (C++)]
`void DeleteVar (const wchar_t *`*name*`)`	[Method on `mglParse` (C++)]
`void mgl_parser_del_var (HMPR `*p*`, const char *`*name*`)`	[C function]
`void mgl_parser_del_varw (HMPR `*p*`, const wchar_t *`*name*`)`	[C function]

Function delete the variable specified by its name or by its pointer.

`void DeleteAll ()`	[Method on `mglParse` (C++)]
`void mgl_parser_del_all (HMPR `*p*`)`	[C function]

Function delete all variables in this parser.

`void RestoreOnce ()`	[Method on `mglParse`]
`void mgl_parser_restore_once (HMPR `*p*`)`	[C function]

Restore Once flag.

void AllowSetSize (bool *a*)   [Method on `mglParse`]
void mgl_parser_allow_setsize (HMPR *p*, int *a*)   [C function]
> Allow to parse 'setsize' command or not.

void AllowFileIO (bool *a*)   [Method on `mglParse`]
void mgl_parser_allow_file_io (HMPR *p*, int *a*)   [C function]
> Allow reading/saving files or not.

void Stop ()   [Method on `mglParse`]
void mgl_parser_stop (HMPR *p*)   [C function]
> Sends stop signal which terminate execution at next command.

long GetCmdNum ()   [Method on `mglParse`]
long mgl_parser_cmd_num (HMPR *p*)   [C function]
> Return the number of registered MGL commands.

const char * GetCmdName (long *id*)   [Method on `mglParse`]
const char * mgl_parser_cmd_name (HMPR *p*, long *id*)   [C function]
> Return the name of command with given *id*.

int CmdType (const char **name*)   [Method on `mglParse`]
int mgl_parser_cmd_type (HMPR *p*, const char **name*)   [C function]
> Return the type of MGL command *name*. Type of commands are: 0 – not the
> command, 1 - data plot, 2 - other plot, 3 - setup, 4 - data handle, 5 - data create, 6
> - subplot, 7 - program, 8 - 1d plot, 9 - 2d plot, 10 - 3d plot, 11 - dd plot, 12 - vector
> plot, 13 - axis, 14 - primitives, 15 - axis setup, 16 - text/legend, 17 - data transform.

const char * CmdFormat (const char **name*)   [Method on `mglParse`]
const char * mgl_parser_cmd_frmt (HMPR *p*, const char **name*)   [C function]
> Return the format of arguments for MGL command *name*.

const char * CmdDesc (const char **name*)   [Method on `mglParse`]
const char * mgl_parser_cmd_desc (HMPR *p*, const char **name*)   [C function]
> Return the description of MGL command *name*.

8 UDAV

UDAV (Universal Data Array Visualizator) is cross-platform program for data arrays visualization based on MathGL library. It support wide spectrum of graphics, simple script language and visual data handling and editing. It has window interface for data viewing, changing and plotting. Also it can execute MGL scripts, setup and rotate graphics and so on. UDAV hot-keys can be found in the appendix Section A.3 [Hot-keys for UDAV], page 273.

8.1 UDAV overview

UDAV have main window divided by 2 parts in general case and optional bottom panel(s). Left side contain tabs for MGL script and data arrays. Right side contain tabs with graphics itself, with list of variables and with help on MGL. Bottom side may contain the panel with MGL messages and warnings, and the panel with calculator.

Main window is shown on the figure above. You can see the script (at left) with current line highlighted by light-yellow, and result of its execution at right. Each panel have its own set of toolbuttons.

Editor toolbuttons allow: open and save script from/to file; undo and redo changes; cut, copy and paste selection; find/replace text; show dialogs for command arguments and for plot setup; show calculator at bottom.

Graphics toolbuttons allow: enable/disable additional transparency and lighting; show grid of absolute coordinates; enable mouse rotation; restore image view; refresh graphics (execute the script); stop calculation; copy graphics into clipboard; add primitives (line, curve, box, rhombus, ellipse, mark, text) to the image; change view angles manually. Vertical toolbuttons allow: shift and zoom in/out of image as whole; show next and previous frame of animation, or start animation (if one present).

Graphics panel support plot editing by mouse.

- Axis range can be changed by mouse wheel or by dragging image by middle mouse button. Right button show popup menu. Left button show the coordinates of mouse

click. At this double click will highlight plot under mouse and jump to the corresponded string of the MGL script.

- Pressing "mouse rotation" toolbutton will change mouse actions: dragging by left button will rotate plot, middle button will shift the plot as whole, right button will zoom in/out plot as whole and add perspective, mouse wheel will zoom in/out plot as whole.

- Manual primitives can be added by pressing corresponding toolbutton. They can be shifted as whole at any time by mouse dragging. At this double click open dialog with its properties. If toolbutton "grid of absolute coordinates" is pressed then editing of active points for primitives is enabled.

Short command description and list of its arguments are shown at the status-bar, when you move cursor to the new line of code. You can press F1 to see more detailed help on special panel.

Also you can look the current list of variables, its dimensions and its size in the memory (right side of above figure). Toolbuttons allow: create new variable, edit variable, delete variable, preview variable plot and its properties, refresh list of variables. Pressing on any column will sort table according its contents. Double click on a variable will open panel with data cells of the variable, where you can view/edit each cell independently or apply a set of transformations.

Finally, pressing `F2` or `F4` you can show/hide windows with messages/warnings and with calculator. Double click on a warning in message window will jump to corresponding line in editor. Calculator allow you type expression by keyboard as well as by toolbuttons. It know about all current variables, so you can use them in formulas.

8.2 UDAV dialogs

There are a set of dialogs, which allow change/add a command, setup global plot properties, or setup UDAV itself.

One of most interesting dialog (hotkey `Meta-C` or `Win-C`) is dialog which help to enter new command or change arguments of existed one. It allows consequently select the category of command, command name in category and appropriate set of command arguments. At

this right side show detailed command description. Required argument(s) are denoted by bold text. Strings are placed in apostrophes, like 'txt'. Buttons below table allow to call dialogs for changing style of command (if argument 'fmt' is present in the list of command arguments); to set variable or expression for argument(s); to add options for command.

Dialog for changing style can be called independently, but usually is called from *New command* dialog or by double click on primitive. It contain 3 tabs: one for pen style, one for color scheme, one for text style. You should select appropriate one. Resulting string of style and sample picture are shown at bottom of dialog.

Dialog for entering variable allow to select variable or expression which can be used as argument of a command. Here you can select the variable name; range of indexes in each directions; operation which will be applied (like, summation, finding minimal/maximal values and so on).

Dialog for command options allow to change Section 3.7 [Command options], page 132.

There is dialog for setting general plot properties, including tab for setting lighting properties. It can be called by called by hotkey **???** and put setup commands at the beginning of MGL script.

Also you can set or change script parameters ('`$0`' ... '`$9`', see Section 7.1 [MGL definition], page 241).

Finally, there is dialog for UDAV settings. It allow to change most of things in UDAV appearance and working, including colors of keywords and numbers, default font and image size, and so on (see figure above).

There are also a set of dialogs for data handling, but they are too simple and clear. So, I will not put them here.

8.3 UDAV hints

- You can shift axis range by pressing middle button and moving mouse. Also, you can zoom in/out axis range by using mouse wheel.
- You can rotate/shift/zoom whole plot by mouse. Just press 'Rotate' toolbutton, click image and hold a mouse button: left button for rotation, right button for zoom/perspective, middle button for shift.
- You may quickly draw the data from file. Just use: udav 'filename.dat' in command line.
- You can copy the current image to clipboard by pressing `Ctrl-Shift-C`. Later you can paste it directly into yours document or presentation.
- You can export image into a set of format (EPS, SVG, PNG, JPEG) by pressing right mouse button inside image and selecting 'Export as ...'.
- You can setup colors for script highlighting in Property dialog. Just select menu item 'Settings/Properties'.
- You can save the parameter of animation inside MGL script by using comment started from '##a ' or '##c ' for loops.
- New drawing never clears things drawn already. For example, you can make a surface with contour lines by calling commands 'surf' and 'cont' one after another (in any order).
- You can put several plots in the same image by help of commands 'subplot' or 'inplot'.
- All indexes (of data arrays, subplots and so on) are always start from 0.
- You can edit MGL file in any text editor. Also you can run it in console by help of commands: `mglconv`, `mglview`.

- You can use command 'once on|off' for marking the block which should be executed only once. For example, this can be the block of large data reading/creating/handling. Press F9 (or menu item 'Graphics/Reload') to re-execute this block.

- You can use command 'stop' for terminating script parsing. It is useful if you don't want to execute a part of script.

- You can type arbitrary expression as input argument for data or number. In last case (for numbers), the first value of data array is used.

- There is powerful calculator with a lot of special functions. You can use buttons or keyboard to type the expression. Also you can use existed variables in the expression.

- The calculator can help you to put complex expression in the script. Just type the expression (which may depend on coordinates x,y,z and so on) and put it into the script.

- You can easily insert file or folder names, last fitted formula or numerical value of selection by using menu Edit|Insert.

- The special dialog (Edit|Insert|New Command) help you select the command, fill its arguments and put it into the script.

- You can put several plotting commands in the same line or in separate function, for highlighting all of them simultaneously.

9 Other classes

There are few end-user classes: `mglGraph` (see Chapter 4 [MathGL core], page 135), `mglWindow` and `mglGLUT` (see Chapter 5 [Widget classes], page 205), `mglData` (see Chapter 6 [Data processing], page 214), `mglParse` (see Chapter 7 [MGL scripts], page 241). Exactly these classes I recommend to use in most of user programs. All methods in all of these classes are inline and have exact C/Fortran analogue functions. This give compiler independent binary libraries for MathGL.

However, sometimes you may need to extend MathGL by writing yours own plotting functions or handling yours own data structures. In these cases you may need to use low-level API. This chapter describes it.

The internal structure of MathGL is rather complicated. There are C++ classes `mglBase`, `mglCanvas`, ... for drawing primitives and positioning the plot (blue ones in the figure). There is a layer of C functions, which include interface for most important methods of these classes. Also most of plotting functions are implemented as C functions. After it, there are "inline" front-end classes which are created for user convenience (yellow ones in the figure). Also there are widgets for FLTK and Qt libraries (green ones in the figure).

Below I show how this internal classes can be used.

9.1 Define new kind of plot (mglBase class)

Basically most of new kinds of plot can be created using just MathGL primitives (see Section 4.6 [Primitives], page 158). However the usage of `mglBase` methods can give you higher speed of drawing and better control of plot settings.

All plotting functions should use a pointer to `mglBase` class (or `HMGL` type in C functions) due to compatibility issues. Exactly such type of pointers are used in front-end classes (`mglGraph, mglWindow`) and in widgets (`QMathGL, Fl_MathGL`).

MathGL tries to remember all vertexes and all primitives and plot creation stage, and to use them for making final picture by demand. Basically for making plot, you need to add vertexes by `AddPnt()` function, which return index for new vertex, and call one of primitive drawing function (like `mark_plot()`, `arrow_plot()`, `line_plot()`, `trig_plot()`, `quad_plot()`, `text_plot()`), using vertex indexes as argument(s). `AddPnt()` function use 2

mreal numbers for color specification. First one is positioning in textures – integer part is texture index, fractional part is relative coordinate in the texture. Second number is like a transparency of plot (or second coordinate in the 2D texture).

I don't want to put here detailed description of `mglBase` class. It was rather well documented in `mgl2/base.h` file. I just show and example of its usage on the base of circle drawing.

First, we should prototype new function `circle()` as C function.

```
#ifdef __cplusplus
extern "C" {
#endif
void circle(HMGL gr, mreal x, mreal y, mreal z, mreal r, const char *stl, const char *opt);
#ifdef __cplusplus
}
#endif
```

This is done for generating compiler independent binary. Because only C-functions have standard naming mechanism, the same for any compilers.

Now, we create a C++ file and put the code of function. I'll write it line by line and try to comment all important points.

```
void circle(HMGL gr, mreal x, mreal y, mreal z, mreal r, const char *stl, const char *opt)
{
```

First, we need to check all input arguments and send warnings if something is wrong. In our case it is negative value of r argument. We just send warning, since it is not critical situation – other plot still can be drawn.

```
  if(r<=0)  { gr->SetWarn(mglWarnNeg,"Circle"); return; }
```

Next step is creating a group. Group keep some general setting for plot (like options) and useful for export in 3d files.

```
  static int cgid=1;  gr->StartGroup("Circle",cgid++);
```

Now let apply options. Options are rather useful things, generally, which allow one easily redefine axis range(s), transparency and other settings (see Section 3.7 [Command options], page 132).

```
  gr->SaveState(opt);
```

I use global setting for determining the number of points in circle approximation. Note, that user can change `MeshNum` by options easily.

```
  const int n = gr->MeshNum>1?gr->MeshNum : 41;
```

Let try to determine plot specific flags. MathGL functions expect that most of flags will be sent in string. In our case it is symbol '@' which set to draw filled circle instead of border only (last will be default). Note, you have to handle `NULL` as string pointer.

```
  bool fill = mglchr(stl,'@');
```

Now, time for coloring. I use palette mechanism because circle have few colors: one for filling and another for border. `SetPenPal()` function parse input string and write resulting texture index in *pal*. Function return the character for marker, which can be specified in string *str*. Marker will be plotted at the center of circle. I'll show on next sample how you can use color schemes (smooth colors) too.

```
long pal=0;
char mk=gr->SetPenPal(stl,&pal);
```

Next step, is determining colors for filling and for border. First one for filling.

```
mreal c=gr->NextColor(pal), d;
```

Second one for border. I use black color (call `gr->AddTexture('k')`) if second color is not specified.

```
mreal k=(gr->GetNumPal(pal)>1)?gr->NextColor(pal):gr->AddTexture('k');
```

If user want draw only border (`fill=false`) then I use first color for border.

```
if(!fill) k=c;
```

Now we should reserve space for vertexes. This functions need `n` for border, `n+1` for filling and `1` for marker. So, maximal number of vertexes is `2*n+2`. Note, that such reservation is not required for normal work but can sufficiently speed up the plotting.

```
gr->Reserve(2*n+2);
```

We've done with setup and ready to start drawing. First, we need to add vertex(es). Let define NAN as normals, since I don't want handle lighting for this plot,

```
mglPoint q(NAN,NAN);
```

and start adding vertexes. First one for central point of filling. I use `-1` if I don't need this point. The arguments of `AddPnt()` function is: `mglPoint(x,y,z)` – coordinate of vertex, `c` – vertex color, `q` – normal at vertex, `-1` – vertex transparency (`-1` for default), `3` bitwise flag which show that coordinates will be scaled (`0x1`) and will not be cutted (`0x2`).

```
long n0,n1,n2,m1,m2,i;
n0 = fill ? gr->AddPnt(mglPoint(x,y,z),c,q,-1,3):-1;
```

Similar for marker, but we use different color *k*.

```
n2 = mk ? gr->AddPnt(mglPoint(x,y,z),k,q,-1,3):-1;
```

Draw marker.

```
if(mk)  gr->mark_plot(n2,mk);
```

Time for drawing circle itself. I use `-1` for *m1*, *n1* as sign that primitives shouldn't be drawn for first point `i=0`.

```
for(i=0,m1=n1=-1;i<n;i++)
{
```

Each function should check `Stop` variable and return if it is non-zero. It is done for interrupting drawing for system which don't support multi-threading.

```
  if(gr->Stop)  return;
```

Let find coordinates of vertex.

```
  mreal t = i*2*M_PI/(n-1.);
  mglPoint p(x+r*cos(t), y+r*sin(t), z);
```

Save previous vertex and add next one

```
  n2 = n1;  n1 = gr->AddPnt(p,c,q,-1,3);
```

and copy it for border but with different color. Such copying is much faster than adding new vertex using `AddPnt()`.

```
   m2 = m1;   m1 = gr->CopyNtoC(n1,k);
```

Now draw triangle for filling internal part

```
   if(fill)  gr->trig_plot(n0,n1,n2);
```

and draw line for border.

```
   gr->line_plot(m1,m2);
 }
```

Drawing is done. Let close group and return.

```
 gr->EndGroup();
}
```

Another sample I want to show is exactly the same function but with smooth coloring using color scheme. So, I'll add comments only in the place of difference.

```
void circle_cs(HMGL gr, mreal x, mreal y, mreal z, mreal r, const char *stl, const char *op
{
```

In this case let allow negative radius too. Formally it is not the problem for plotting (formulas the same) and this allow us to handle all color range.

```
//if(r<=0)  { gr->SetWarn(mglWarnNeg,"Circle"); return; }

 static int cgid=1;  gr->StartGroup("CircleCS",cgid++);
 gr->SaveState(opt);
 const int n = gr->MeshNum>1?gr->MeshNum : 41;
 bool fill = mglchr(stl,'@');
```

Here is main difference. We need to create texture for color scheme specified by user

```
 long ss = gr->AddTexture(stl);
```

But we need also get marker and color for it (if filling is enabled). Let suppose that marker and color is specified after ':'. This is standard delimiter which stop color scheme entering. So, just lets find it and use for setting pen.

```
 const char *pen=0;
 if(stl) pen = strchr(stl,':');
 if(pen) pen++;
```

The substring is placed in *pen* and it will be used as line style.

```
 long pal=0;
 char mk=gr->SetPenPal(pen,&pal);
```

Next step, is determining colors for filling and for border. First one for filling.

```
 mreal c=gr->GetC(ss,r);
```

Second one for border.

```
 mreal k=gr->NextColor(pal);
```

The rest part is the same as in previous function.

```
 if(!fill) k=c;

 gr->Reserve(2*n+2);
 mglPoint q(NAN,NAN);
 long n0,n1,n2,m1,m2,i;
```

```
  n0 = fill ? gr->AddPnt(mglPoint(x,y,z),c,q,-1,3):-1;
  n2 = mk ? gr->AddPnt(mglPoint(x,y,z),k,q,-1,3):-1;
  if(mk)  gr->mark_plot(n2,mk);
  for(i=0,m1=n1=-1;i<n;i++)
  {
    if(gr->Stop)  return;
    mreal t = i*2*M_PI/(n-1.);
    mglPoint p(x+r*cos(t), y+r*sin(t), z);
    n2 = n1;  n1 = gr->AddPnt(p,c,q,-1,3);
    m2 = m1;  m1 = gr->CopyNtoC(n1,k);
    if(fill)  gr->trig_plot(n0,n1,n2);
    gr->line_plot(m1,m2);
  }
  gr->EndGroup();
}
```

The last thing which we can do is derive our own class with new plotting functions. Good idea is to derive it from `mglGraph` (if you don't need extended window), or from `mglWindow` (if you need to extend window). So, in our case it will be

```
class MyGraph : public mglGraph
{
public:
  inline void Circle(mglPoint p, mreal r, const char *stl="", const char *opt="")█
  { circle(p.x,p.y,p.z, r, stl, opt); }
  inline void CircleCS(mglPoint p, mreal r, const char *stl="", const char *opt="")█
  { circle_cs(p.x,p.y,p.z, r, stl, opt); }
};
```

Note, that I use `inline` modifier for using the same binary code with different compilers.

So, the complete sample will be

```
#include <mgl2/mgl.h>
//----------------------------------------------------------
#ifdef __cplusplus
extern "C" {
#endif
void circle(HMGL gr, mreal x, mreal y, mreal z, mreal r, const char *stl, const char *opt);
void circle_cs(HMGL gr, mreal x, mreal y, mreal z, mreal r, const char *stl, const char *op
#ifdef __cplusplus
}
#endif
//----------------------------------------------------------
class MyGraph : public mglGraph
{
public:
  inline void CircleCF(mglPoint p, mreal r, const char *stl="", const char *opt="")█
  { circle(p.x,p.y,p.z, r, stl, opt); }
  inline void CircleCS(mglPoint p, mreal r, const char *stl="", const char *opt="")█
  { circle_cs(p.x,p.y,p.z, r, stl, opt); }
```

```
};
//-----------------------------------------------------------
void circle(HMGL gr, mreal x, mreal y, mreal z, mreal r, const char *stl, const char *opt)
{
  if(r<=0)  { gr->SetWarn(mglWarnNeg,"Circle"); return; }
  static int cgid=1;  gr->StartGroup("Circle",cgid++);
  gr->SaveState(opt);
  const int n = gr->MeshNum>1?gr->MeshNum : 41;
  bool fill = mglchr(stl,'@');
  long pal=0;
  char mk=gr->SetPenPal(stl,&pal);
  mreal c=gr->NextColor(pal), d;
  mreal k=(gr->GetNumPal(pal)>1)?gr->NextColor(pal):gr->AddTexture('k');
  if(!fill) k=c;
  gr->Reserve(2*n+2);
  mglPoint q(NAN,NAN);
  long n0,n1,n2,m1,m2,i;
  n0 = fill ? gr->AddPnt(mglPoint(x,y,z),c,q,-1,3):-1;
  n2 = mk ? gr->AddPnt(mglPoint(x,y,z),k,q,-1,3):-1;
  if(mk)  gr->mark_plot(n2,mk);
  for(i=0,m1=n1=-1;i<n;i++)
  {
    if(gr->Stop)  return;
    mreal t = i*2*M_PI/(n-1.);
    mglPoint p(x+r*cos(t), y+r*sin(t), z);
    n2 = n1;  n1 = gr->AddPnt(p,c,q,-1,3);
    m2 = m1;  m1 = gr->CopyNtoC(n1,k);
    if(fill)  gr->trig_plot(n0,n1,n2);
    gr->line_plot(m1,m2);
  }
  gr->EndGroup();
}
//-----------------------------------------------------------
void circle_cs(HMGL gr, mreal x, mreal y, mreal z, mreal r, const char *stl, const char *opt)
{
  static int cgid=1;  gr->StartGroup("CircleCS",cgid++);
  gr->SaveState(opt);
  const int n = gr->MeshNum>1?gr->MeshNum : 41;
  bool fill = mglchr(stl,'@');
  long ss = gr->AddTexture(stl);
  const char *pen=0;
  if(stl) pen = strchr(stl,':');
  if(pen) pen++;
  long pal=0;
  char mk=gr->SetPenPal(pen,&pal);
  mreal c=gr->GetC(ss,r);
  mreal k=gr->NextColor(pal);
```

```
  if(!fill) k=c;

  gr->Reserve(2*n+2);
  mglPoint q(NAN,NAN);
  long n0,n1,n2,m1,m2,i;
  n0 = fill ? gr->AddPnt(mglPoint(x,y,z),c,q,-1,3):-1;
  n2 = mk ? gr->AddPnt(mglPoint(x,y,z),k,q,-1,3):-1;
  if(mk)  gr->mark_plot(n2,mk);
  for(i=0,m1=n1=-1;i<n;i++)
  {
    if(gr->Stop)  return;
    mreal t = i*2*M_PI/(n-1.);
    mglPoint p(x+r*cos(t), y+r*sin(t), z);
    n2 = n1;  n1 = gr->AddPnt(p,c,q,-1,3);
    m2 = m1;  m1 = gr->CopyNtoC(n1,k);
    if(fill)  gr->trig_plot(n0,n1,n2);
    gr->line_plot(m1,m2);
  }
  gr->EndGroup();
}
//------------------------------------------------------------
int main()
{
  MyGraph gr;
  gr.Box();
  // first let draw circles with fixed colors
  for(int i=0;i<10;i++)
    gr.CircleCF(mglPoint(2*mgl_rnd()-1, 2*mgl_rnd()-1), mgl_rnd());
  // now let draw circles with color scheme
  for(int i=0;i<10;i++)
    gr.CircleCS(mglPoint(2*mgl_rnd()-1, 2*mgl_rnd()-1), 2*mgl_rnd()-1);
}
```

9.2 User defined types (mglDataA class)

mglData class have abstract predecessor class mglDataA. Exactly the pointers to mglDataA instances are used in all plotting functions and some of data processing functions. This was done for taking possibility to define yours own class, which will handle yours own data (for example, complex numbers, or differently organized data). And this new class will be almost the same as mglData for plotting purposes.

However, the most of data processing functions will be slower as if you used mglData instance. This is more or less understandable – I don't know how data in yours particular class will be organized, and couldn't optimize the these functions generally.

There are few virtual functions which must be provided in derived classes. This functions give:

- the sizes of the data (GetNx, GetNy, GetNz),

- give data value and numerical derivatives for selected cell (v, dvx, dvy, dvz),

- give maximal and minimal values (Maximal, Minimal) – you can use provided functions (like mgl_data_max and mgl_data_min), but yours own realization can be more efficient,

- give access to all element as in single array (vthr) – you need this only if you want using MathGL's data processing functions.

Let me, for example define class mglComplex which will handle complex number and draw its amplitude or phase, depending on flag *use_abs*:

```
#include <complex>
#include <mgl2/mgl.h>
#define dual std::complex<double>
class mglComplex : public mglDataA
{
public:
  long nx;       ///< number of points in 1st dimensions ('x' dimension)
  long ny;       ///< number of points in 2nd dimensions ('y' dimension)
  long nz;       ///< number of points in 3d dimensions ('z' dimension)
  dual *a;       ///< data array
  bool use_abs; ///< flag to use abs() or arg()

  inline mglComplex(long xx=1,long yy=1,long zz=1)
  { a=0;  use_abs=true; Create(xx,yy,zz); }
  virtual ~mglComplex()  { if(a)  delete []a; }

  /// Get sizes
  inline long GetNx() const { return nx;  }
  inline long GetNy() const { return ny;  }
  inline long GetNz() const { return nz;  }
  /// Create or recreate the array with specified size and fill it by zero
  inline void Create(long mx,long my=1,long mz=1)
  { nx=mx;  ny=my;  nz=mz;  if(a) delete []a;
  a = new dual[nx*ny*nz]; }
  /// Get maximal value of the data
  inline mreal Maximal() const  { return mgl_data_max(this);  }
  /// Get minimal value of the data
  inline mreal Minimal() const  { return mgl_data_min(this);  }

protected:
  inline mreal v(long i,long j=0,long k=0) const
  { return use_abs ? abs(a[i+nx*(j+ny*k)]) : arg(a[i+nx*(j+ny*k)]);  }
  inline mreal vthr(long i) const
  { return use_abs ? abs(a[i]) : arg(a[i]);  }
  inline mreal dvx(long i,long j=0,long k=0) const
  { register long i0=i+nx*(j+ny*k);
    std::complex<double> res=i>0? (i<nx-1? (a[i0+1]-a[i0-1])/2.:a[i0]-a[i0-1]) : a[i0+1]-a[
    return use_abs? abs(res) : arg(res);  }
```

```
  inline mreal dvy(long i,long j=0,long k=0) const
  { register long i0=i+nx*(j+ny*k);
    std::complex<double> res=j>0? (j<ny-1? (a[i0+nx]-a[i0-nx])/2.:a[i0]-a[i0-nx]) : a[i0+nx
    return use_abs? abs(res) : arg(res);  }
  inline mreal dvz(long i,long j=0,long k=0) const
  { register long i0=i+nx*(j+ny*k), n=nx*ny;
    std::complex<double> res=k>0? (k<nz-1? (a[i0+n]-a[i0-n])/2.:a[i0]-a[i0-n]) : a[i0+n]-a[
    return use_abs? abs(res) : arg(res);  }
};
int main()
{
  mglComplex dat(20);
  for(long i=0;i<20;i++)
    dat.a[i] = 3*exp(-0.05*(i-10)*(i-10))*dual(cos(M_PI*i*0.3), sin(M_PI*i*0.3));█
  mglGraph gr;
  gr.SetRange('y', -M_PI, M_PI);  gr.Box();

  gr.Plot(dat,"r","legend 'abs'");
  dat.use_abs=false;
  gr.Plot(dat,"b","legend 'arg'");
  gr.Legend();
  gr.WritePNG("complex.png");
  return 0;
}
```

9.3 mglColor class

Structure for working with colors. This structure is defined in `#include <mgl2/type.h>`.

There are two ways to set the color in MathGL. First one is using of mreal values of red, green and blue channels for precise color definition. The second way is the using of character id. There are a set of characters specifying frequently used colors. Normally capital letter gives more dark color than lowercase one. See Section 3.3 [Line styles], page 127.

mreal r, g, b, a   [Parameter of mglColor]
  Reg, green and blue component of color.

 mglColor (mreal *R*, mreal *G*, mreal *B*, mreal *A*=1)   [Method on mglColor]
  Constructor sets the color by mreal values of Red, Green, Blue and Alpha channels.
  These values should be in interval [0,1].

 mglColor (char *c*='k', mreal *bright*=1)   [Method on mglColor]
  Constructor sets the color from character id. The black color is used by default.
  Parameter *br* set additional "lightness" of color.

void Set (mreal *R*, mreal *G*, mreal *B*, mreal *A*=1)   [Method on mglColor]
  Sets color from values of Red, Green, Blue and Alpha channels. These values should
  be in interval [0,1].

void Set (mglColor *c*, mreal *bright*=1)   [Method on mglColor]
  Sets color as "lighted" version of color *c*.

`void Set (char `*p*`, mreal `*bright*`=1)`   [Method on `mglColor`]
    Sets color from symbolic id.

`bool Valid ()`   [Method on `mglColor`]
    Checks correctness of the color.

`mreal Norm ()`   [Method on `mglColor`]
    Gets maximal of spectral component.

`bool operator== (const mglColor &`*c*`)`   [Method on `mglColor`]
`bool operator!= (const mglColor &`*c*`)`   [Method on `mglColor`]
    Compare with another color

`bool operator*= (mreal `*v*`)`   [Method on `mglColor`]
    Multiplies color components by number *v*.

`bool operator+= (const mglColor &`*c*`)`   [Method on `mglColor`]
    Adds color *c* component by component.

`bool operator-= (const mglColor &`*c*`)`   [Method on `mglColor`]
    Subtracts color *c* component by component.

`mglColor operator+ (const mglColor &`*a*`, const mglColor`   [Library Function]
    `&`*b*`)`
    Adds colors by its RGB values.

`mglColor operator- (const mglColor &`*a*`, const mglColor`   [Library Function]
    `&`*b*`)`
    Subtracts colors by its RGB values.

`mglColor operator* (const mglColor &`*a*`, mreal `*b*`)`   [Library Function]
`mglColor operator* (mreal `*a*`, const mglColor &`*b*`)`   [Library Function]
    Multiplies color by number.

`mglColor operator/ (const mglColor &`*a*`, mreal `*b*`)`   [Library Function]
    Divide color by number.

`mglColor operator! (const mglColor &`*a*`)`   [Library Function]
    Return inverted color.

9.4 mglPoint class

Structure describes point in space. This structure is defined in `#include <mgl2/type.h>`

`mreal x, y, z, c`   [Parameter of `mglPoint`]
    Point coordinates {x,y,z} and one extra value *c* used for amplitude, transparency and
    so on. By default all values are zero.

`mglPoint (mreal `*X*`=0, mreal `*Y*`=0, mreal `*Z*`=0, mreal`   [Method on `mglPoint`]
    C`=0)`
    Constructor sets the color by mreal values of Red, Green, Blue and Alpha channels.
    These values should be in interval [0,1].

`bool IsNAN ()`   [Method on `mglPoint`]
    Returns `true` if point contain NAN values.

`mreal norm ()`   [Method on `mglPoint`]
    Returns the norm $\sqrt{\{x^2 + y^2 + z^2\}}$ of vector.

`void Normalize ()`   [Method on `mglPoint`]
    Normalizes vector to be unit vector.

`mreal val (int i)`   [Method on `mglPoint`]
    Returns point component: x for $i=0$, y for $i=1$, z for $i=2$, c for $i=3$.

`mglPoint operator+ (const mglPoint &a, const mglPoint`   [Library Function]
    `&b)`
    Point of summation (summation of vectors).

`mglPoint operator- (const mglPoint &a, const mglPoint`   [Library Function]
    `&b)`
    Point of difference (difference of vectors).

`mglPoint operator* (mreal a, const mglPoint &b)`   [Library Function]
`mglPoint operator* (const mglPoint &a, mreal b)`   [Library Function]
    Multiplies (scale) points by number.

`mglPoint operator/ (const mglPoint &a, mreal b)`   [Library Function]
    Multiplies (scale) points by number 1/b.

`mreal operator* (const mglPoint &a, const mglPoint &b)`   [Library Function]
    Scalar product of vectors.

`mglPoint operator/ (const mglPoint &a, const mglPoint`   [Library Function]
    `&b)`
    Return vector of element-by-element product.

`mglPoint operator^ (const mglPoint &a, const mglPoint`   [Library Function]
    `&b)`
    Cross-product of vectors.

`mglPoint operator& (const mglPoint &a, const mglPoint`   [Library Function]
    `&b)`
    The part of a which is perpendicular to vector b.

`mglPoint operator| (const mglPoint &a, const mglPoint`   [Library Function]
    `&b)`
    The part of a which is parallel to vector b.

`mglPoint operator! (const mglPoint &a)`   [Library Function]
    Return vector perpendicular to vector a.

`mreal mgl_norm (const mglPoint &a)`   [Library Function]
    Return the norm sqrt(|a|^2) of vector a.

`bool operator==` (const `mglPoint` &*a*, const `mglPoint` &*b*)   [Library Function]
    Return true if points are the same.

`bool operator!=` (const `mglPoint` &*a*, const `mglPoint` &*b*)   [Library Function]
    Return true if points are different.

Appendix A Symbols and hot-keys

This appendix contain the full list of symbols (characters) used by MathGL for setting up plot. Also it contain sections for full list of hot-keys supported by mglview tool and by UDAV program.

A.1 Symbols for styles

Below is full list of all characters (symbols) which MathGL use for setting up the plot.

'space ' ''

empty line style (see Section 3.3 [Line styles], page 127);

empty color in [chart], page 171.

'!'   set to use new color from palette for each point (not for each curve, as default) in Section 4.10 [1D plotting], page 167.

'#'   set to use solid marks (see Section 3.3 [Line styles], page 127) or solid [error], page 173 boxes;

set to draw wired plot for [axial], page 182, [surf3], page 183, [surf3a], page 188, [surf3c], page 187, [triplot], page 198, [quadplot], page 199, [area], page 169, [bars], page 170, [barh], page 170, [tube], page 176, [tape], page 168, [cone], page 160, [boxs], page 178 and draw boundary only for [circle], page 160, [ellipse], page 161, [rhomb], page 161;

set to draw also mesh lines for [surf], page 177, [surfc], page 187, [surfa], page 188, [dens], page 179, [densx], page 195, [densy], page 195, [densz], page 195, [dens3], page 184, or boundary for [chart], page 171, [facex], page 159, [facey], page 159, [facez], page 159, [rect], page 159;

set to draw boundary and box for [legend], page 166, [title], page 148, or grid lines for [table], page 175;

set to draw grid for [radar], page 167;

set to start flow threads and pipes from edges only for [flow], page 192, [pipe], page 194;

set to use whole are for axis range in [subplot], page 147, [inplot], page 148;

change text color inside a string (see Section 3.5 [Font styles], page 130);

start comment in Chapter 7 [MGL scripts], page 241 or in Section 3.7 [Command options], page 132.

'$'   denote parameter of Chapter 7 [MGL scripts], page 241.

'&'   operation in Section 3.6 [Textual formulas], page 131.

'''   denote string in Chapter 7 [MGL scripts], page 241 or in Section 3.7 [Command options], page 132.

'*'   one of marks (see Section 3.3 [Line styles], page 127);

operation in Section 3.6 [Textual formulas], page 131.

'+'   one of marks (see Section 3.3 [Line styles], page 127) or kind of [error], page 173
                boxes;

                operation in Section 3.6 [Textual formulas], page 131.

','   separator for color positions (see Section 3.2 [Color styles], page 127) or items
                in a list.

'−'   solid line style (see Section 3.3 [Line styles], page 127);

                place entries horizontally in [legend], page 166;

                operation in Section 3.6 [Textual formulas], page 131.

'.'   one of marks (see Section 3.3 [Line styles], page 127);

                set to draw hachures instead of arrows for [vect], page 191, [vect3], page 191;

                set to use dots instead of faces for [cloud], page 184, [torus], page 176, [axial],
                page 182, [surf3], page 183, [surf3a], page 188, [surf3c], page 187, [surf],
                page 177, [surfa], page 188, [surfc], page 187, [dens], page 179, [map], page 189;

                delimiter of fractional parts for numbers.

'/'   operation in Section 3.6 [Textual formulas], page 131.

':'   line dashing style (see Section 3.3 [Line styles], page 127);

                stop color scheme parsing (see Section 3.4 [Color scheme], page 128);

                range operation in Chapter 7 [MGL scripts], page 241.

';'   line dashing style (see Section 3.3 [Line styles], page 127);

                end of an option in Chapter 7 [MGL scripts], page 241 or in Section 3.7 [Command options], page 132.

'<'   one of marks (see Section 3.3 [Line styles], page 127);

                style of [subplot], page 147 and [inplot], page 148;

                set position of [colorbar], page 164;

                style of [vect], page 191, [vect3], page 191;

                operation in Section 3.6 [Textual formulas], page 131.

'>'   one of marks (see Section 3.3 [Line styles], page 127);

                style of [subplot], page 147 and [inplot], page 148;

                set position of [colorbar], page 164;

                style of [vect], page 191, [vect3], page 191;

                operation in Section 3.6 [Textual formulas], page 131.

'='   line dashing style (see Section 3.3 [Line styles], page 127);

                set to use equidistant columns for [table], page 175;

                set to use color gradient for [vect], page 191, [vect3], page 191;

                operation in Section 3.6 [Textual formulas], page 131.

'@'   set to draw box around text for [text], page 162 and similar functions;

                set to draw boundary and fill it for [circle], page 160, [ellipse], page 161, [rhomb],
                page 161;

             set to fill faces for [box], page 165;

             set to draw large semitransparent mark instead of error box for [error], page 173;

             set to draw edges for [cone], page 160;

             set to draw filled boxes for [boxs], page 178;

             reduce text size inside a string (see Section 3.5 [Font styles], page 130).

'^'   one of marks (see Section 3.3 [Line styles], page 127);

             style of [subplot], page 147 and [inplot], page 148;

             set position of [colorbar], page 164;

             switch to upper index inside a string (see Section 3.5 [Font styles], page 130);

             operation in Section 3.6 [Textual formulas], page 131.

'_'   empty arrow style (see Section 3.3 [Line styles], page 127);

             disable drawing of tick labels for [axis], page 163;

             style of [subplot], page 147 and [inplot], page 148;

             set position of [colorbar], page 164;

             set to draw contours at bottom for [cont], page 179, [contf], page 180, [contd], page 180, [contv], page 181, [tricont], page 199;

             switch to lower index inside a string (see Section 3.5 [Font styles], page 130).

'[]'   contain symbols excluded from color scheme parsing (see Section 3.4 [Color scheme], page 128).

'{}'   contain extended color specification (see Section 3.2 [Color styles], page 127);

             denote special operation in Chapter 7 [MGL scripts], page 241;

             denote 'meta-symbol' for LaTeX like string parsing (see Section 3.5 [Font styles], page 130).

'|'   line dashing style (see Section 3.3 [Line styles], page 127);

             set to use sharp color scheme (see Section 3.4 [Color scheme], page 128);

             set to limit width by subplot width for [table], page 175;

             delimiter in [list], page 218 command;

             operation in Section 3.6 [Textual formulas], page 131.

'\'   string continuation symbol on next line for Chapter 7 [MGL scripts], page 241.

'0,1,2,3,4,5,6,7,8,9'

             line width (see Section 3.3 [Line styles], page 127);

             brightness of a color (see Section 3.2 [Color styles], page 127);

             kind of smoothing (for digits 1,3,5) in [smooth], page 230;

             digits for a value.

'A,B,C,D,E,F,a,b,c,d,e,f'

             can be hex-digit for color specification if placed inside {} (see Section 3.2 [Color styles], page 127).

'A'   arrow style (see Section 3.3 [Line styles], page 127);

                set to use absolute position in whole picture for [text], page 162, [colorbar], page 164, [legend], page 166.

'a'   set to use absolute position in subplot for [text], page 162;

                style of [bars], page 170, [barh], page 170.

'B'   dark blue color (see Section 3.2 [Color styles], page 127).

'b'   blue color (see Section 3.2 [Color styles], page 127);

                bold font face if placed after ':' (see Section 3.5 [Font styles], page 130).

'C'   dark cyan color (see Section 3.2 [Color styles], page 127);

                align text to center if placed after ':' (see Section 3.5 [Font styles], page 130).

'c'   cyan color (see Section 3.2 [Color styles], page 127);

                name of color axis;

                cosine transform for [transform], page 237.

'D'   arrow style (see Section 3.3 [Line styles], page 127).

'd'   one of marks (see Section 3.3 [Line styles], page 127) or kind of [error], page 173 boxes.

'E'   dark green-yellow color (see Section 3.2 [Color styles], page 127).

'e'   green-yellow color (see Section 3.2 [Color styles], page 127).

'f'   style of [bars], page 170, [barh], page 170;

                style of [vect], page 191, [vect3], page 191;

                Fourier transform for [transform], page 237.

'G'   dark green color (see Section 3.2 [Color styles], page 127).

'g'   green color (see Section 3.2 [Color styles], page 127).

'H'   dark gray color (see Section 3.2 [Color styles], page 127).

'h'   gray color (see Section 3.2 [Color styles], page 127);

                Hankel transform for [transform], page 237.

'I'   arrow style (see Section 3.3 [Line styles], page 127);

                set [colorbar], page 164 position near boundary.

'i'   line dashing style (see Section 3.3 [Line styles], page 127);

                italic font face if placed after ':' (see Section 3.5 [Font styles], page 130).

                set to use inverse values for [cloud], page 184, [pipe], page 194, [dew], page 192;

                set to fill only area with y1<y<y2 for [region], page 169;

                inverse Fourier transform for [transform], page 237.

'j'   line dashing style (see Section 3.3 [Line styles], page 127);

'K'   arrow style (see Section 3.3 [Line styles], page 127).

'k'   black color (see Section 3.2 [Color styles], page 127).

'L'   dark green-blue color (see Section 3.2 [Color styles], page 127);

               align text to left if placed after ':' (see Section 3.5 [Font styles], page 130).

'l'   green-blue color (see Section 3.2 [Color styles], page 127).

'M'   dark magenta color (see Section 3.2 [Color styles], page 127).

'm'   magenta color (see Section 3.2 [Color styles], page 127).

'N'   dark sky-blue color (see Section 3.2 [Color styles], page 127).

'n'   sky-blue color (see Section 3.2 [Color styles], page 127).

'O'   arrow style (see Section 3.3 [Line styles], page 127).

'o'   one of marks (see Section 3.3 [Line styles], page 127) or kind of [error], page 173
               boxes;

               over-line text if placed after ':' (see Section 3.5 [Font styles], page 130).

'P'   dark purple color (see Section 3.2 [Color styles], page 127).

'p'   purple color (see Section 3.2 [Color styles], page 127).

'Q'   dark orange or brown color (see Section 3.2 [Color styles], page 127).

'q'   orange color (see Section 3.2 [Color styles], page 127).

'R'   dark red color (see Section 3.2 [Color styles], page 127);

               align text to right if placed after ':' (see Section 3.5 [Font styles], page 130).

'r'   red color (see Section 3.2 [Color styles], page 127).

'S'   arrow style (see Section 3.3 [Line styles], page 127);

's'   one of marks (see Section 3.3 [Line styles], page 127) or kind of [error], page 173
               boxes;

               sine transform for [transform], page 237.

'T'   arrow style (see Section 3.3 [Line styles], page 127);

               place text under the curve for [text], page 162, [cont], page 179, [cont3],
               page 184.

't'   set to draw text labels for [cont], page 179, [cont3], page 184;

               name of t-axis (one of ternary axis);

               variable in Section 3.6 [Textual formulas], page 131, which usually is varied in
               range [0,1].

'U'   dark blue-violet color (see Section 3.2 [Color styles], page 127);

               disable rotation of tick labels for [axis], page 163.

'u'   blue-violet color (see Section 3.2 [Color styles], page 127);

               under-line text if placed after ':' (see Section 3.5 [Font styles], page 130);

               name of u-axis (one of ternary axis);

               variable in Section 3.6 [Textual formulas], page 131, which usually denote array
               itself.

'V'   arrow style (see Section 3.3 [Line styles], page 127).

'v'   one of marks (see Section 3.3 [Line styles], page 127);

           set to draw vectors on flow threads for [flow], page 192.

'W'   bright gray color (see Section 3.2 [Color styles], page 127).

'w'   white color (see Section 3.2 [Color styles], page 127);

           wired text if placed after ':' (see Section 3.5 [Font styles], page 130);

           name of w-axis (one of ternary axis);

'x'   one of marks (see Section 3.3 [Line styles], page 127) or kind of [error], page 173
           boxes;

           name of x-axis or x-direction or 1st dimension of a data array;

           start hex-color described if placed inside {} (see Section 3.2 [Color styles],
           page 127);

           style of [tape], page 168.

'Y'   dark yellow or gold color (see Section 3.2 [Color styles], page 127).

'y'   yellow color (see Section 3.2 [Color styles], page 127);

           name of y-axis or y-direction or 2nd dimension of a data array.

'z'

           name of z-axis or z-direction or 3d dimension of a data array;

           style of [tape], page 168.

A.2 Hot-keys for mglview

Key	Description
Ctrl-P	Open printer dialog and print graphics.
Ctrl-W	Close window.
Ctrl-T	Switch on/off transparency for the graphics.
Ctrl-L	Switch on/off additional lightning for the graphics.
Ctrl-Space	Restore default graphics rotation, zoom and perspective.
F5	Execute script and redraw graphics.
F6	Change canvas size to fill whole region.
Ctrl-F5	Run slideshow. If no parameter specified then the dialog with slideshow options will appear.

`Ctrl-Comma`, `Ctrl-Period`	Show next/previous slide. If no parameter specified then the dialog with slideshow options will appear.
`Ctrl-Shift-G`	Copy graphics to clipboard.
`Alt-P`	Export as semitransparent PNG.
`Alt-F`	Export as solid PNG.
`Alt-J`	Export as JPEG.
`Alt-E`	Export as vector EPS.
`Alt-S`	Export as vector SVG.
`Alt-L`	Export as LaTeX/Tikz image.
`Alt-M`	Export as MGLD.
`Alt-D`	Export as PRC/PDF.
`Alt-O`	Export as OBJ.

A.3 Hot-keys for UDAV

Key	Description
`Ctrl-N`	Create new window with empty script. Note, all scripts share variables. So, second window can be used to see some additional information of existed variables.
`Ctrl-O`	Open and execute/show script or data from file. You may switch off automatic exection in UDAV properties
`Ctrl-S`	Save script to a file.
`Ctrl-P`	Open printer dialog and print graphics.
`Ctrl-Z`	Undo changes in script editor.
`Ctrl-Shift-Z`	Redo changes in script editor.
`Ctrl-X`	Cut selected text into clipboard.
`Ctrl-C`	Copy selected text into clipboard.

`Ctrl-V`	Paste selected text from clipboard.
`Ctrl-A`	Select all text in editor.
`Ctrl-F`	Show dialog for text finding.
`F3`	Find next occurrence of the text.
`Win-C` or `Meta-C`	Show dialog for new command and put it into the script.
`Win-F` or `Meta-F`	Insert last fitted formula with found coefficients.
`Win-S` or `Meta-S`	Show dialog for styles and put it into the script. Styles define the plot view (color scheme, marks, dashing and so on).
`Win-O` or `Meta-O`	Show dialog for options and put it into the script. Options are used for additional setup the plot.
`Win-N` or `Meta-N`	Replace selected expression by its numerical value.
`Win-P` or `Meta-P`	Select file and insert its file name into the script.
`Win-G` or `Meta-G`	Show dialog for plot setup and put resulting code into the script. This dialog setup axis, labels, lighting and other general things.
`Ctrl-Shift-O`	Load data from file. Data will be deleted only at exit but UDAV will not ask to save it.
`Ctrl-Shift-S`	Save data to a file.
`Ctrl-Shift-C`	Copy range of numbers to clipboard.
`Ctrl-Shift-V`	Paste range of numbers from clipboard.
`Ctrl-Shift-N`	Recreate the data with new sizes and fill it by zeros.
`Ctrl-Shift-R`	Resize (interpolate) the data to specified sizes.
`Ctrl-Shift-T`	Transform data along dimension(s).
`Ctrl-Shift-M`	Make another data.
`Ctrl-Shift-H`	Find histogram of data.
`Ctrl-T`	Switch on/off transparency for the graphics.

`Ctrl-L`	Switch on/off additional lightning for the graphics.
`Ctrl-G`	Switch on/off grid of absolute coordinates.
`Ctrl-Space`	Restore default graphics rotation, zoom and perspective.
`F5`	Execute script and redraw graphics.
`F6`	Change canvas size to fill whole region.
`F7`	Stop script execution.
`F9`	Restore status for 'once' command and reload data.
`Ctrl-F5`	Run slideshow. If no parameter specified then the dialog with slideshow options will appear.
`Ctrl-Comma`, `Ctrl-Period`	Show next/previous slide. If no parameter specified then the dialog with slideshow options will appear.
`Ctrl-W`	Open dialog with slideshow options.
`Ctrl-Shift-G`	Copy graphics to clipboard.
`F1`	Show help on MGL commands
`F2`	Show/hide tool window with messages and information.
`F4`	Show/hide calculator which evaluate and help to type textual formulas. Textual formulas may contain data variables too.
`Meta-Shift-Up`, `Meta-Shift-Down`	Change view angle θ.
`Meta-Shift-Left`, `Meta-Shift-Right`	Change view angle ϕ.
`Alt-Minus`, `Alt-Equal`	Zoom in/out whole image.
`Alt-Up`, `Alt-Down`, `Alt-Right`, `Alt-Left`	Shift whole image.
`Alt-P`	Export as semitransparent PNG.
`Alt-F`	Export as solid PNG.
`Alt-J`	Export as JPEG.
`Alt-E`	Export as vector EPS.

`Alt-S`	Export as vector SVG.
`Alt-L`	Export as LaTeX/Tikz image.
`Alt-M`	Export as MGLD.
`Alt-D`	Export as PRC/PDF.
`Alt-O`	Export as OBJ.

Appendix B File formats

This appendix contain description of file formats used by MathGL.

B.1 Font files

Starting from v.1.6 the MathGL library uses new font files. The font is defined in 4 files with suffixes '`*.vfm`', '`*_b.vfm`', '`*_i.vfm`', '`*_bi.vfm`'. These files are text files containing the data for roman font, bold font, italic font and bold italic font. The files (or some symbols in the files) for bold, italic or bold italic fonts can be absent. In this case the roman glyph will be used for them. By analogy, if the bold italic font is absent but the bold font is present then bold glyph will be used for bold italic. You may create these font files by yourself from *.ttf, *.otf files with the help of program `font_tools`. This program can be found at MathGL home site.

The format of font files (*.vfm – vector font for MathGL) is the following.

1. First string contains human readable comment and is always ignored.
2. Second string contains 3 numbers, delimited by space or tabulation. The order of numbers is the following: *numg* – the number of glyphs in the file (integer), *fact* – the factor for glyph sizing (mreal), *size* – the size of buffer for glyph description (integer).
3. After it *numg*-th strings with glyphs description are placed. Each string contains 6 positive numbers, delimited by space of tabulation. The order of numbers is the following: Unicode glyph ID, glyph width, number of lines in glyph, position of lines coordinates in the buffer (length is 2*number of lines), number of triangles in glyph, position of triangles coordinates in the buffer (length is 6*number of triangles).
4. The end of file contains the buffer with point coordinates at lines or triangles vertexes. The size of buffer (the number of integer) is *size*.

Each font file can be compressed by gzip.

Note: the closing contour line is done automatically (so the last segment may be absent). For starting new contour use a point with coordinates `{0x3fff, 0x3fff}`.

B.2 MGLD format

MGLD is textual file, which contain all required information for drawing 3D image, i.e. it contain vertexes with colors and normales, primitives with all properties, textures, and glyph descriptions. MGLD file can be imported or viewed separately, without parsing data files itself.

MGLD file start from string

`MGLD npnts nprim ntxtr nglfs # optional description`

which contain signature '`MGLD`' and number of points *npnts*, number of primitives *nprim*, number of textures *ntxtr*, number of glyph descriptions *nglfs*, and optional description. Empty strings and string with '`#`' are ignored.

Next, file contain *npnts* strings with points coordinates and colors. The format of each string is

`x y z c t ta u v w r g b a`

Here *x*, *y*, *z* are coordinates, *c*, *t* are color indexes in texture, *ta* is normalized *t* according to current alpha setting, *u*, *v*, *w* are coordinates of normal vector (can be `NAN` if disabled), *r*, *g*, *b*, *a* are RGBA color values.

Next, file contain *nprim* strings with properties of primitives. The format of each string is

```
type n1 n2 n3 n4 id s w p
```

Here *type* is kind of primitive (0 - mark, 1 - line, 2 - triangle, 3 - quadrangle, 4 - glyph), *n1...n4* is index of point for vertexes, *id* is primitive identification number, *s* and *w* are size and width if applicable, *p* is scaling factor for glyphs.

Next, file contain *ntxtr* strings with descriptions of textures. The format of each string is

```
smooth alpha colors
```

Here *smooth* set to enable smoothing between colors, *alpha* set to use half-transparent texture, *colors* contain color scheme itself as it described in Section 3.4 [Color scheme], page 128.

Finally, file contain *nglfs* entries with description of each glyph used in the figure. The format of entries are

```
nT nL
xA yA xB yB xC yC ...
xP yP ...
```

Here nT is the number of triangles; nL is the number of line vertexes; xA, yA, xB, yB, xC, yC are coordinates of triangles; and xP, yP, xQ, yQ are coordinates of lines. Line coordinate xP=0x3fff, yP=0x3fff denote line breaking.

B.3 JSON format

MathGL can save points and primitives of 3D object. It contain a set of variables listed below.

'`width`'   width of the image;

'`height`'   height of the image

'`depth`'   depth of the image, usually =sqrt(width*height);

'`npnts`'   number of points (vertexes);

'`pnts`'   array of coordinates of points (vertexes), each element is array in form [x, y, z];

'`nprim`'   number of primitives;

'`prim`'   array of primitives, each element is array in form [type, n1, n2, n3, n4, id, s, w, p, z, color].

Here *type* is kind of primitive (0 - mark, 1 - line, 2 - triangle, 3 - quadrangle, 4 - glyph), *n1...n4* is index of point for vertexes and *n2* can be index of glyph coordinate, *s* and *w* are size and width if applicable, *z* is average z-coordinate, *id* is primitive identification number, *p* is scaling factor for glyphs.

'`ncoor`'   number of glyph positions

'coor'   array of glyph positions, each element is array in form [dx,dy]

'nglfs'   number of glyph descriptions

'glfs'   array of glyph descriptions, each element is array in form [nT, nL, [xA0, yA0,
            xB0, yB0, xC0, yC0, xA1, yA1, xB1, yB1, xC1, yC1 ...], [xP0, yP0, xP1, yP1
            ...]]. Here nT is the number of triangles; nL is the number of line vertexes;
            xA, yA, xB, yB, xC, yC are coordinates of triangles; and xP, yP, xQ, yQ are
            coordinates of lines. Line coordinate xP=0x3fff, yP=0x3fff denote line breaking.

Appendix C TeX-like symbols

The full list of TeX-like commands recognizable by MathGL is shown below. If command is not recognized then it will be printed as is by ommitting '\' symbol. For example, '\#' produce "#", '\\' produce "\", '\qq' produce "qq".

Change case: _, ^, @.

Text style: \big, \b, \textbf, \i, \textit, \bi, \r, \textrm, \a, \overline, \u, \underline, \w, \wire, #, \color[wkrgbcymhRGBCYMHWlenupqLENUPQ]

Roots: \sqrt, \sqrt3, \sqrt4

Fractions: \frac, \stack, \overset, \underset, \stackr, \stackl

Accents: \hat, \tilde, \dot, \ddot, \dddot, \ddddot, \acute, \check, \grave, \vec, \bar, \breve

Special symbols:

\# (#), \% (%), \& (&), \^ (^).

\AA (), \AE (), \APLboxquestion (), \APLboxupcaret (), \APLnotbackslash (), \APLnotslash (), \Alpha (), \And (&), \Angstrom (), \Barv (), \BbbC (), \BbbGamma (), \BbbH (), \BbbN (), \BbbP (), \BbbPi (), \BbbQ (), \BbbR (), \BbbZ (), \Bbbgamma (), \Bbbpi (), \Bbbsum (), \Beta (), \Bumpeq (), \Cap (), \Chi (), \Colon (), \Coloneq (), \Cup (), \DDownarrow (), \DH (), \DJ (), \DashV (), \DashVDash (), \Dashv (), \Ddownarrow (), \Delta (), \Digamma (), \Doteq (), \Downarrow (), \Epsilon (), \Equiv (), \Eta (), \Eulerconst (), \Exclam (), \Finv (), \Game (), \Gamma (), \Gt (), \Hermaphrodite (), \Im (), \Iota (), \Kappa (), \Koppa (), \L (), \LLeftarrow (), \Lambda (), \Lbrbrak (), \Ldsh (), \Leftarrow (), \Leftrightarrow (), \Lleftarrow (), \Longleftarrow (), \Longleftrightarrow (), \Longmapsfrom (), \Longmapsto (), \Longrightarrow (), \Lparengtr (), \Lsh (), \Lt (), \Lvzigzag (), \Mapsfrom (), \Mapsto (), \Mu (), \NG (), \Nearrow (), \Not (), \Nu (), \Nwarrow (), \O (), \OE (), \Ohorn (), \Omega (), \Omicron (), \Otimes (), \P (), \Phi (), \Pi (), \Planckconst (), \Prec (), \PropertyLine (), \Psi (), \QED (), \Question (), \RRightarrow (), \Rbrbrak (), \Rdsh (), \Re (), \Rho (), \Rightarrow (), \Rparenless (), \Rrightarrow (), \Rsh (), \Rvzigzag (), \S (), \Sc (), \Searrow (), \Sigma (), \Sqcap (), \Sqcup (), \Stigma (), \Subset (), \Supset (), \Swarrow (), \TH (), \Tau (), \Theta (), \UUparrow (), \Uhorn (), \Uparrow (), \Updownarrow (), \Uuparrow (), \VDash (), \Vbar (), \Vdash (), \Vee (), \Vert (), \Vvdash (), \Vvert (), \Wedge (), \XBox (), \Xi (), \Yup (), \Zbar (), \Zeta ().

\aa (), \ac (), \accurrent (), \acidfree (), \acwcirclearrow (), \acwgapcirclearrow (), \acwleftarcarrow (), \acwopencirclearrow (), \acwoverarcarrow (), \acwundercurvearrow (), \adots (), \ae (), \aleph (), \alpha (), \amalg (), \angdnr (), \angle (), \angles (), \angleubar (), \approx (), \approxeq (), \approxeqq (), \approxident (), \arceq (), \aries (), \assert (), \ast (), \asteq (), \astrosun (), \asymp (), \awint ().

\bNot (), \backcong (), \backdprime (), \backepsilon (), \backprime (), \backsim (), \backsimeq (), \backslash (\), \backtrprime (), \bagmember (), \barV (), \barcap (), \barcup (), \bardownharpoonleft (), \bardownharpoonright (), \barleftarrow (), \barleftarrowrightarrowbar (), \barleftharpoondown (), \barleftharpoonup (), \barovernorthwestarrow (), \barrightarrowdiamond (), \barrightharpoondown (), \barrightharpoonup (), \baruparrow (), \barupharpoonleft (), \barupharpoonright (), \barvee (), \barwedge (),

\bbrktbrk (), \bdHrule (), \bdVrule (), \bdbVbH (), \bdbVbh (), \bdbVlH (), \bdbVlh (), \bdbVrH (), \bdbVrh (), \bdbvbH (), \bdbvbh (), \bdbvlH (), \bdbvlh (), \bdbvrH (), \bdbvrh (), \bddVbH (), \bddVbh (), \bddVlH (), \bddVlh (), \bddVrH (), \bddVrh (), \bddvbH (), \bddvbh (), \bddvlH (), \bddvlh (), \bddvrH (), \bddvrh (), \bdhrule (), \bdnesw (), \bdnwse (), \bdquadhdash (), \bdquadvdash (), \bdtriplevdash (), \bduVbH (), \bduVbh (), \bduVlH (), \bduVlh (), \bduVrH (), \bduVrh (), \bduvbH (), \bduvbh (), \bduvlH (), \bduvlh (), \bduvrH (), \bduvrh (), \bdvrule (), \because (), \benzenr (), \beta (), \beth (), \between (), \bigblacktriangledown (), \bigblacktriangleup (), \bigbot (), \bigcap (), \bigcup (), \bigslopedvee (), \bigslopedwedge (), \bigstar (), \bigtop (), \bigtriangledown (), \bigtriangleup (), \bigvee (), \bigwedge (), \bigwhitestar (), \black-circledownarrow (), \blackcircledrightdot (), \blackcircledsanseight (), \blackcircledsans-five (), \blackcircledsansfour (), \blackcircledsansnine (), \blackcircledsansone (), \black-circledsansseven (), \blackcircledsanssix (), \blackcircledsansten (), \blackcircledsansthree (), \blackcircledsanstwo (), \blackcircledtwodots (), \blackcircleulquadwhite (), \blackdia-monddownarrow (), \blackhourglass (), \blackinwhitediamond (), \blackinwhitesquare (), \blacklefthalfcircle (), \blackpointerleft (), \blackpointerright (), \blackrighthalfcircle (), \blacksmiley (), \blacktriangle (), \blacktriangledown (), \blacktriangleleft (), \blacktri-angleright (), \blkhorzoval (), \blkvertoval (), \blockfull (), \blockhalfshaded (), \block-lefthalf (), \blocklowhalf (), \blockqtrshaded (), \blockrighthalf (), \blockthreeqtrshaded (), \blockuphalf (), \bot (), \botsemicircle (), \bowtie (), \box (), \boxast (), \boxbar (), \boxbox (), \boxbslash (), \boxcircle (), \boxdiag (), \boxdot (), \boxminus (), \boxonbox (), \boxplus (), \boxtimes (), \bsimilarleftarrow (), \bsimilarrightarrow (), \bsolhsub (), \btimes (), \bullet (), \bullseye (), \bumpeq (), \bumpeqq ().

\calB (), \calE (), \calF (), \calH (), \calM (), \calR (), \cap (), \capdot (), \cap-wedge (), \caretinsert (), \carreturn (), \carriagereturn (), \ccwundercurvearrow (), \cdot (), \cdotp (), \cdots (), \cdprime (), \checkmark (), \chi (), \cirE (), \cirbot (), \circ (), \circeq (), \circfint (), \circlebottomhalfblack (), \circledA (), \circledB (), \circledC (), \circledD (), \circledE (), \circledF (), \circledG (), \circledH (), \circledI (), \circledJ (), \circledK (), \circledL (), \circledM (), \circledN (), \circledO (), \circledP (), \cir-cledQ (), \circledR (), \circledS (), \circledT (), \circledU (), \circledV (), \circledW (), \circledX (), \circledY (), \circledZ (), \circleda (), \circledast (), \circledb (), \circledbul-let (), \circledc (), \circledcirc (), \circledd (), \circleddash (), \circlede (), \circledeight (), \circledequal (), \circledf (), \circledfive (), \circledfour (), \circledg (), \circledh (), \circledi (), \circledj (), \circledk (), \circledl (), \circledm (), \circledn (), \circlednine (), \circledo (), \circledone (), \circledownarrow (), \circledp (), \circledparallel (), \cir-cledq (), \circledr (), \circledrightdot (), \circleds (), \circledsanseight (), \circledsansfive (), \circledsansfour (), \circledsansnine (), \circledsansone (), \circledsansseven (), \cir-cledsanssix (), \circledsansten (), \circledsansthree (), \circledsanstwo (), \circledseven (), \circledsix (), \circledstar (), \circledt (), \circledthree (), \circledtwo (), \circledtwodots (), \circledu (), \circledv (), \circledvert (), \circledw (), \circledwhitebullet (), \circledx (), \circledy (), \circledz (), \circledzero (), \circlehbar (), \circlelefthalfblack (), \cir-clellquad (), \circlelrquad (), \circleonleftarrow (), \circleonrightarrow (), \circlerighthalf-black (), \circletophalfblack (), \circleulquad (), \circleurquad (), \circleurquadblack (), \circlevertfill (), \cirmid (), \cirscir (), \clangle (), \closedvarcap (), \closedvarcup (), \closedvarcupsmashprod (), \closure (), \cloverleaf (), \clubsuit (), \colon (:), \colon (), \coloneq (), \commaminus (), \complement (), \concavediamond (), \concavediamondtick-

left (), \concavediamondtickright (), \cong (), \congdot (), \conictaper (), \conjunction (), \coprod (), \cprime (), \crangle (), \csub (), \csube (), \csup (), \csupe (), \cuberoot (), \cup (), \cupdot (), \cupleftarrow (), \cupvee (), \curlyeqprec (), \curlyeqsucc (), \curlyvee (), \curlywedge (), \curvearrowleft (), \curvearrowleftplus (), \curvearrowright (), \curvearrowrightminus (), \cwcirclearrow (), \cwgapcirclearrow (), \cwopencirclearrow (), \cwrightarcarrow (), \cwundercurvearrow (), \cylcty ().

\dag (), \dagger (), \daleth (), \danger (), \dashV (), \dashVdash (), \dashcolon (), \dashleftharpoondown (), \dashrightharpoondown (), \dashv (), \dbkarow (), \ddag (), \ddagger (), \ddots (), \ddotseq (), \delta (), \dh (), \diameter (), \diamond (), \diamondbotblack (), \diamondcdot (), \diamondleftarrow (), \diamondleftarrowbar (), \diamondleftblack (), \diamondrightblack (), \diamondsuit (), \diamondtopblack (), \dicei (), \diceii (), \diceiii (), \diceiv (), \dicev (), \dicevi (), \digamma (), \dingasterisk (), \dircurrent (), \disin (), \div (), \divideontimes (), \dj (), \dlcrop (), \doteq (), \dotequiv (), \dotminus (), \dotplus (), \dots (), \dotsim (), \dotsminusdots (), \dottedcircle (), \dottedsquare (), \dottimes (), \doublebarvee (), \doublebarwedge (), \doubleplus (), \downarrow (), \downarrowbar (), \downarrowbarred (), \downdasharrow (), \downdownarrows (), \downfishtail (), \downharpoonleft (), \downharpoonleftbar (), \downharpoonright (), \downharpoonrightbar (), \downharpoonsleftright (), \downrightcurvedarrow (), \downtriangleleftblack (), \downtrianglerightblack (), \downuparrows (), \downupharpoonsleftright (), \downwhitearrow (), \downzigzagarrow (), \dprime (), \draftingarrow (), \drbkarow (), \drcrop (), \dsol (), \dsub (), \dualmap ().

\earth (), \egsdot (), \eighthnote (), \elinters (), \ell (), \elsdot (), \emdash (), \emptyset (), \emptysetoarr (), \emptysetoarrl (), \emptysetobar (), \emptysetocirc (), \endash (), \enleadertwodots (), \envelope (), \eparsl (), \epsilon (), \eqcirc (), \eqcolon (), \eqdef (), \eqdot (), \eqeq (), \eqeqeq (), \eqgtr (), \eqless (), \eqqgtr (), \eqqless (), \eqqplus (), \eqqsim (), \eqqslantgtr (), \eqqslantless (), \eqsim (), \eqslantgtr (), \eqslantless (), \equalleftarrow (), \equalparallel (), \equalrightarrow (), \equiv (), \equivDD (), \equivVert (), \equivVvert (), \eqvparsl (), \errbarblackcircle (), \errbarblackdiamond (), \errbarblacksquare (), \errbarcircle (), \errbardiamond (), \errbarsquare (), \eta (), \euro (), \exists ().

\fallingdotseq (), \fbowtie (), \fcmp (), \fdiagovnearrow (), \fdiagovrdiag (), \female (), \figdash (), \fint (), \fisheye (), \flat (), \fltns (), \forall (), \forks (), \forksnot (), \forkv (), \fourthroot (), \fourvdots (), \fracfiveeighths (), \fracfivesixths (), \fracfourfifths (), \fraconeeighth (), \fraconefifth (), \fraconesixth (), \fraconethird (), \fracseveneights (), \fracslash (), \fracthreeeighths (), \fracthreefifths (), \fractwofifths (), \fractwothirds (), \frakC (), \frakH (), \frakZ (), \frown (), \frownie (), \fullouterjoin ().

\gamma (), \ge (), \geq (), \geqq (), \geqslant (), \gescc (), \gesdot (), \gesdoto (), \gesdotol (), \gesles (), \gets (), \gg (), \ggg (), \gggnest (), \gimel (), \glE (), \gla (), \gleichstark (), \glj (), \gnapprox (), \gneq (), \gneqq (), \gnsim (), \greater (>), \gsime (), \gsiml (), \gtcc (), \gtcir (), \gtlpar (), \gtquest (), \gtrapprox (), \gtrarr (), \gtrdot (), \gtreqless (), \gtreqqless (), \gtrless (), \gtrsim (), \guillemotleft (), \guillemotright (), \guilsingllleft (), \guilsinglright ().

\harrowextender (), \hatapprox (), \hbar (), \heartsuit (), \hermitmatrix (), \hexagon (), \hexagonblack (), \hiraganano (), \hknearrow (), \hknwarrow (), \hksearow (), \hkswarow (), \hookleftarrow (), \hookrightarrow (), \horizbar (), \hourglass (), \house (), \hrectangle (), \hrectangleblack (), \hslash (), \hyphenbullet (), \hzigzag ().

\iiiint (), \iiint (), \iinfin (), \iint (), \imageof (), \in (), \incare (), \increment (), \infty (), \int (), \intBar (), \intbar (), \intbottom (), \intcap (), \intclockwise (), \intcup (), \intercal (), \interleave (), \intextender (), \intlharhk (), \intprod (), \intprodr (), \inttop (), \intx (), \inversebullet (), \inversewhitecircle (), \invnot (), \invwhitelowerhalfcircle (), \invwhiteupperhalfcircle (), \iota (), \ipasupgamma (), \ipasupl (), \ipasuprerglotstpp (), \ipasups (), \ipasupx (), \ipaunaspirated (), \ipavoicing (), \isinE (), \isindot (), \isinobar (), \isins (), \isinvb (), \itBbbD (), \itBbbd (), \itBbbe (), \itBbbi (), \itBbbj ().

\jupiter (), \kappa (), \kernelcontraction (), \koppa ().

\l (), \lAngle (), \lBrace (), \lBrack (), \lParen (), \lambda (), \lambdabar (), \langle (), \langledot (), \laplac (), \lasp (), \lat (), \late (), \lbag (), \lblkbrbrak (), \lbrace ({), \lbracelend (), \lbracemid (), \lbraceuend (), \lbrack ([), \lbrackextender (), \lbracklend (), \lbracklltick (), \lbrackubar (), \lbrackuend (), \lbrackultick (), \lbrbrak (), \lceil (), \lcurvyangle (), \ldasharrhead (), \le (), \leadsto (), \leftarrow (), \leftarrowapprox (), \leftarrowbackapprox (), \leftarrowbsimilar (), \leftarrowless (), \leftarrowonoplus (), \leftarrowplus (), \leftarrowshortrightarrow (), \leftarrowsimilar (), \leftarrowsubset (), \leftarrowtail (), \leftarrowtriangle (), \leftarrowx (), \leftbkarrow (), \leftcurvedarrow (), \leftdasharrow (), \leftdasharrowhead (), \leftdbkarrow (), \leftdbltail (), \leftdotarrow (), \leftdowncurvedarrow (), \leftfishtail (), \leftharpoondown (), \leftharpoondownbar (), \leftharpoonsupdown (), \leftharpoonup (), \leftharpoonupbar (), \leftharpoonupdash (), \leftleftarrows (), \leftmoon (), \leftouterjoin (), \leftrightarrow (), \leftrightarrowcircle (), \leftrightarrows (), \leftrightarrowtriangle (), \leftrightharpoondowndown (), \leftrightharpoondownup (), \leftrightharpoons (), \leftrightharpoonsdown (), \leftrightharpoonsup (), \leftrightharpoonupdown (), \leftrightharpoonupup (), \leftrightsquigarrow (), \leftsquigarrow (), \leftsquigarrow (), \lefttail (), \leftthreearrows (), \leftthreetimes (), \leftwhitearrow (), \leq (), \leqq (), \leqqslant (), \leqqslant (), \leqslant (), \lescc (), \lesdot (), \lesdoto (), \lesdotor (), \lesges (), \less (<), \lessapprox (), \lessdot (), \lesseqgtr (), \lesseqqgtr (), \lessgtr (), \lesssim (), \lfbowtie (), \lfloor (), \lftimes (), \lgE (), \lgblkcircle (), \lgblksquare (), \lgwhtcircle (), \lgwhtsquare (), \lhd (), \linefeed (), \ll (), \llangle (), \llarc (), \llblacktriangle (), \llcorner (), \lll (), \lllnest (), \llparenthesis (), \lltriangle (), \lmoustache (), \lnapprox (), \lneq (), \lneqq (), \lnsim (), \longdashv (), \longdivision (), \longleftarrow (), \longleftrightarrow (), \longleftsquigarrow (), \longmapsfrom (), \longmapsto (), \longrightarrow (), \longrightsquigarrow (), \looparrowleft (), \looparrowright (), \lowint (), \lozenge (), \lozengeminus (), \lparenextender (), \lparenlend (), \lparenless (), \lparenuend (), \lq (), \lrarc (), \lrblacktriangle (), \lrcorner (), \lrtriangle (), \lrtriangleeq (), \lsime (), \lsimg (), \lsqhook (), \ltcc (), \ltcir (), \ltimes (), \ltlarr (), \ltquest (), \ltrivb (), \lvboxline (), \lvzigzag ().

\male (), \maltese (), \mapsdown (), \mapsfrom (), \mapsto (), \mapsup (), \mdblkdiamond (), \mdblklozenge (), \mdblkrcl (), \mdblksquare (), \mdlgblkcircle (), \mdlgblkdiamond (), \mdlgblklozenge (), \mdlgblksquare (), \mdlgwhtcircle (), \mdlgwhtdiamond (), \mdlgwhtsquare (), \mdsmblkcircle (), \mdsmblksquare (), \mdsmwhtcircl (), \mdsmwhtsquare (), \mdwhtcircl (), \mdwhtdiamond (), \mdwhtlozenge (), \mdwhtsquare (), \measangledltosw (), \measangledrtose (), \measangleldtosw (), \measanglelutonw (), \measanglerdtose (), \measanglerutone (), \measangleultonw (), \measangleurtone (), \measeq (), \measuredangle (), \measuredangleleft (), \measuredrightangle (), \medblackstar (), \medmathspace (), \medwhitestar (), \mercury (), \mho (), \mid (),

\midbarvee (), \midbarwedge (), \midcir (), \minus (), \minusdot (), \minusfdots (), \minusrdots (), \mlcp (), \models (), \mp (), \mu (), \multimap (), \multimapinv ().

\nHdownarrow (), \nHuparrow (), \nLeftarrow (), \nLeftrightarrow (), \nRightarrow (), \nVDash (), \nVdash (), \nVleftarrow (), \nVleftarrowtail (), \nVleftrightarrow (), \nVrightarrow (), \nVrightarrowtail (), \nVtwoheadleftarrow (), \nVtwoheadleftarrowtail (), \nVtwoheadrightarrow (), \nVtwoheadrightarrowtail (), \nabla (), \napprox (), \nasymp (), \natural (), \ncong (), \ne (), \nearrow (), \neg (), \neovnwarrow (), \neovsearrow (), \neptune (), \neq (), \nequiv (), \neswarrow (), \neuter (), \nexists (), \ng (), \ngeq (), \ngtr (), \ngtrless (), \ngtrsim (), \nhVvert (), \nhpar (), \ni (), \niobar (), \nis (), \nisd (), \nleftarrow (), \nleftrightarrow (), \nleq (), \nless (), \nlessgtr (), \nlesssim (), \nmid (), \nni (), \nobreakhyphen (), \notin (), \nparallel (), \npolint (), \nprec (), \npreccurlyeq (), \nrightarrow (), \nsim (), \nsime (), \nsqsubseteq (), \nsqsupseteq (), \nsubset (), \nsubseteq (), \nsucc (), \nsucccurlyeq (), \nsupset (), \nsupseteq (), \ntriangleleft (), \ntrianglelefteq (), \ntriangleright (), \ntrianglerighteq (), \nu (), \nvDash (), \nvLeftarrow (), \nvLeftrightarrow (), \nvRightarrow (), \nvdash (), \nvinfty (), \nvleftarrow (), \nvleftarrowtail (), \nvleftrightarrow (), \nvrightarrow (), \nvrightarrowtail (), \nvtwoheadleftarrow (), \nvtwoheadleftarrowtail (), \nvtwoheadrightarrow (), \nvtwoheadrightarrowtail (), \nwarrow (), \nwovnearrow (), \nwsearrow ().

\o (), \obar (), \obot (), \obrbrak (), \obslash (), \odiv (), \odot (), \odotslashdot (), \oe (), \ogreaterthan (), \ohorn (), \oiiint (), \oiint (), \oint (), \ointctrclockwise (), \olcross (), \oldKoppa (), \oldkoppa (), \olessthan (), \omega (), \omicron (), \ominus (), \operp (), \oplus (), \opluslhrim (), \oplusrhrim (), \origof (), \oslash (), \otimes (), \otimeshat (), \otimeslhrim (), \otimesrhrim (), \overbrace (), \overbracket (), \overline (), \overparen (), \owns ().

\parallel (), \parallelogram (), \parallelogramblack (), \parsim (), \partial (), \partialmeetcontraction (), \pentagon (), \pentagonblack (), \perp (), \perps (), \phi (), \phone (), \pi (), \pitchfork (), \plusdot (), \pluseqq (), \plushat (), \plussim (), \plussubtwo (), \plustrif (), \pluto (), \pm (), \pointnt (), \postalmark (), \prec (), \precapprox (), \preccurlyeq (), \preceq (), \preceqq (), \precnapprox (), \precneq (), \precneqq (), \precnsim (), \precsim (), \prime (), \prod (), \profalar (), \profline (), \profsurf (), \propto (), \prurel (), \psi (), \pullback (), \pushout ().

\qprime (), \quarternote (), \questeq (), \quotdblbase (), \quotdblright (), \quotsinglbase (), \quotsinglright ().

\rAngle (), \rBrace (), \rBrack (), \rParen (), \rangle (), \rangledot (), \rangledownzigzagarrow (), \rasp (), \rbag (), \rblkbrbrak (), \rbrace (}), \rbracelend (), \rbracemid (), \rbraceuend (), \rbrack (]), \rbrackextender (), \rbracklend (), \rbracklrtick (), \rbrackubar (), \rbrackuend (), \rbrackurtick (), \rbrbrak (), \rceil (), \rcurvyangle (), \rdiagovfdiag (), \rdiagovsearrow (), \recorder (), \revangle (), \revangleubar (), \revemptyset (), \revnmid (), \rfbowtie (), \rfloor (), \rftimes (), \rhd (), \rho (), \righarrowbsimilar (), \rightangle (), \rightanglemdot (), \rightanglesqr (), \rightarrow (), \rightarrowapprox (), \rightarrowbackapprox (), \rightarrowbar (), \rightarrowdiamond (), \rightarrowgtr (), \rightarrowonoplus (), \rightarrowplus (), \rightarrowshortleftarrow (), \rightarrowsimilar (), \rightarrowsupset (), \rightarrowtail (), \rightarrowtriangle (), \rightarrowx (), \rightbkarrow (), \rightcurvedarrow (), \rightdasharrow (), \rightdbltail (), \rightdotarrow (), \rightdowncurvedarrow (), \rightfishtail (), \rightharpoondown (), \rightharpoondownbar (), \rightharpoonsupdown

(), \rightharpoonup (), \rightharpoonupbar (), \rightharpoonupdash (), \rightimply (), \rightleftarrows (), \rightleftharpoons (), \rightleftharpoonsdown (), \rightleftharpoonsup (), \rightmoon (), \rightouterjoin (), \rightpentagon (), \rightpentagonblack (), \rightrightarrows (), \rightsquigarrow (), \rightsquigarrow (), \righttail (), \rightthreearrows (), \rightthreetimes (), \rightwhitearrow (), \ringplus (), \risingdotseq (), \rmoustache (), \rparenextender (), \rparengtr (), \rparenlend (), \rparenuend (), \rppolint (), \rq (), \rrangle (), \rrparenthesis (), \rsolbar (), \rsqhook (), \rsub (), \rtimes (), \rtriltri (), \ruledelayed (), \rvboxline (), \rvzigzag ().

\sampi (), \sansLmirrored (), \sansLturned (), \saturn (), \scissors (), \scpolint (), \scrB (), \scrE (), \scrF (), \scrH (), \scrI (), \scrL (), \scrM (), \scrR (), \scre (), \scrg (), \scro (), \scurel (), \searrow (), \seovnearrow (), \setminus (), \setminus (), \sharp (), \shortdowntack (), \shortleftarrow (), \shortlefttack (), \shortrightarrow (), \shortrightarrowleftarrow (), \shortuptack (), \shuffle (), \sigma (), \silon (), \silon (), \sim (), \simeq (), \simgE (), \simgtr (), \similarleftarrow (), \similarrightarrow (), \simlE (), \simless (), \simminussim (), \simneqq (), \simplus (), \simrdots (), \sinewave (), \slash (), \smallblacktriangleleft (), \smallblacktriangleright (), \smalldiamond (), \smallin (), \smallint (), \smallni (), \smallsetminus (), \smalltriangleleft (), \smalltriangleright (), \smashtimes (), \smblkdiamond (), \smblklozenge (), \smblksquare (), \smeparsl (), \smile (), \smiley (), \smt (), \smte (), \smwhitestar (), \smwhtcircle (), \smwhtlozenge (), \smwhtsquare (), \spadesuit (), \sphericalangle (), \sphericalangleup (), \sqcap (), \sqcup (), \sqint (), \sqlozenge (), \sqrt (), \sqrt3 (), \sqrt4 (), \sqrtbottom (), \sqsubset (), \sqsubseteq (), \sqsubsetneq (), \sqsupset (), \sqsupseteq (), \sqsupsetneq (), \squarecrossfill (), \squaregrayfill (), \squarehfill (), \squarehvfill (), \squareleftblack (), \squareleftblack (), \squarellblack (), \squarellquad (), \squarelrblack (), \squarelrquad (), \squareneswfill (), \squarenwsefill (), \squareulblack (), \squareulquad (), \squareurblack (), \squareurquad (), \squarevfill (), \squoval (), \ss (), \star (), \stareq (), \sterling (), \stigma (), \strns (), \subedot (), \submult (), \subrarr (), \subset (), \subsetapprox (), \subsetcirc (), \subsetdot (), \subseteq (), \subseteqq (), \subsetneq (), \subsetneqq (), \subsetplus (), \subsim (), \subsub (), \subsup (), \succ (), \succapprox (), \succcurlyeq (), \succeq (), \succeqq (), \succnapprox (), \succneq (), \succneqq (), \succnsim (), \succsim (), \sum (), \sumbottom (), \sumint (), \sumtop (), \sun (), \supdsub (), \supedot (), \suphsol (), \suphsub (), \suplarr (), \supmult (), \supn (), \supset (), \supsetapprox (), \supsetcirc (), \supsetdot (), \supseteq (), \supseteqq (), \supsetneq (), \supsetneqq (), \supsetplus (), \supsim (), \supsub (), \supsup (), \surd (), \swarrow ().

\talloblong (), \target (), \tau (), \taurus (), \testhookx (), \textAsterisks (), \textacute (), \textadvanced (), \textain (), \textasciiacute (), \textasciicircum (^), \textasciidieresis (), \textasciigrave ('), \textasciimacron (), \textasciitilde (~), \textasterisklow (), \textbackdprime (), \textbackprime (), \textbacktrprime (), \textbardotlessj (), \textbardotlessjvar (), \textbarglotstop (), \textbari (), \textbarl (), \textbaro (), \textbarrevglotstop (), \textbaru (), \textbeltl (), \textbenttailyogh (), \textbreve (), \textbrokenbar (), \textbullet (), \textbullseye (), \textcent (), \textcircledP (), \textcloseepsilon (), \textcloseomega (), \textcloserevepsilon (), \textcopyright (), \textcrb (), \textcrh (), \textcrinvglotstop (), \textcrlambda (), \textcrtwo (), \textctc (), \textctd (), \textctesh (), \textctj (), \textctl (), \textctn (), \textctt (), \textctyogh (), \textctz (), \textcurrency (), \textdctzlig (), \textdegree (), \textdiscount (), \textdollar ($), \textdotaccent (), \textdotlessj (), \textdoubleacute (), \textdoublebarpipe (), \textdoublepipe (), \textd-

prime (), \textdptr (), \textdyoghlig (), \textdzlig (), \textepsilon (), \textesh (), \textesti-
mated (), \textexclam (), \textexclamdown (), \textfishhookr (), \textflorin (), \textfranc
(), \textgamma (), \textglotstop (), \textgrave (), \texthalflength (), \texthamza (), \tex-
then (), \textheng (), \texthooks (), \texthookz (), \texthtb (), \texthtc (), \texthtd (),
\texthtg (), \texthth (), \texththeng (), \texthtk (), \texthtp (), \texthtq (), \texthtscg
(), \texthtt (), \texthvlig (), \texthyphen (), \textinvglotstop (), \textinvscr (), \tex-
tiota (), \textlengthmark (), \textlhalfring (), \textlhookd (), \textlhookk (), \textlhookl
(), \textlhookt (), \textlhti (), \textlira (), \textlonglegr (), \textlongy (), \textlongy (),
\textlooptoprevesh (), \textlowacute (), \textlowered (), \textlowgrave (), \textlowmacron
(), \textlptr (), \textltailm (), \textltailn (), \textltilde (), \textlyoghlig (), \textmacron (),
\textmu (), \textnumero (), \textogonek (), \textohm (), \textonehalf (), \textonequarter
(), \textonesuperior (), \textopeno (), \textordfeminine (), \textordmasculine (), \textover-
cross (), \textoz (), \textpertenthousand (), \textperthousand (), \textpesetas (), \textphi
(), \textpipe (), \textprime (), \textprimstress (), \textqprime (), \textquestiondown (),
\textquotedbl ("), \textquotedblleft (), \textquotedblright (), \textraised (), \textraise-
glotstop (), \textraiserevglotstop (), \textramshorns (), \textrecipe (), \textreferencemark
(), \textregistered (), \textretracted (), \textreve (), \textrevepsilon (), \textrevglotstop
(), \textrhalfring (), \textrhookrevepsilon (), \textrhookschwa (), \textrhoticity (), \tex-
tringaccent (), \textrptr (), \textrtaild (), \textrtaill (), \textrtailn (), \textrtailr (), \tex-
trtails (), \textrtailt (), \textrtailz (), \textsca (), \textscb (), \textsce (), \textscg (),
\textsch (), \textschwa (), \textsci (), \textscl (), \textscn (), \textscoelig (), \textscr (),
\textscripta (), \textscriptg (), \textscriptv (), \textscu (), \textscy (), \textsecstress (),
\textsemicolonreversed (), \textsilon (), \textsmalltilde (), \textstretchcvar (), \textsubw
(w), \textsuph (), \textsuphth (), \textsupinvscr (), \textsupj (), \textsupr (), \textsup-
turnr (), \textsupturnrrtail (), \textsupw (), \textsupy (), \texttctctlig (), \texttctctlig (),
\textthreequarters (), \textthreesuperior (), \texttrademark (), \texttrprime (), \texttslig
(), \textturna (), \textturncomma (), \textturnh (), \textturnk (), \textturnlonglegr (),
\textturnm (), \textturnmrleg (), \textturnr (), \textturnrrtail (), \textturnscripta (),
\textturnt (), \textturnv (), \textturnw (), \textturny (), \texttwosuperior (), \textup-
silon (), \textuptr (), \textvibyi (), \textvisiblespace (), \textyogh (), \th (), \therefore (),
\thermod (), \theta (), \thickapprox (), \thicksim (), \threedangle (), \threedotcolon (),
\tieconcat (), \tieinfty (), \times (), \timesbar (), \tminus (), \to (), \toea (), \tona (),
\tonebarextrahigh (), \tonebarextralow (), \tonebarhigh (), \tonebarlow (), \tonebarmid
(), \top (), \topbot (), \topcir (), \topfork (), \topsemicircle (), \tosa (), \towa (), \tplus
(), \trapezium (), \trianglecdot (), \triangledown (), \triangleexclam (), \triangleleft (),
\triangleleftblack (), \trianglelefteq (), \triangleminus (), \triangleodot (), \triangleplus
(), \triangleq (), \triangleright (), \trianglerightblack (), \trianglerighteq (), \triangles (),
\triangleserifs (), \triangletimes (), \triangleubar (), \tripleplus (), \trprime (), \turnan-
gle (), \turnediota (), \turnednot (), \twocaps (), \twocups (), \twoheaddownarrow (),
\twoheadleftarrow (), \twoheadleftarrowtail (), \twoheadleftdbkarrow (), \twoheadmaps-
from (), \twoheadmapsto (), \twoheadrightarrow (), \twoheadrightarrowtail (), \twohead-
uparrow (), \twoheaduparrowcircle (), \twolowline (), \twonotes (), \typecolon ().

\ubrbrak (), \uhorn (), \ularc (), \ulblacktriangle (), \ulcorner (), \ulcrop (), \ultri-
angle (), \uminus (), \underbrace (), \underbracket (), \underparen (), \unlhd (), \un-
rhd (), \upand (), \uparrow (), \uparrowbarred (), \uparrowoncircle (), \updasharrow
(), \updownarrow (), \updownarrowbar (), \updownarrows (), \updownharpoonleftleft (),

\updownharpoonleftright (), \updownharpoonrightleft (), \updownharpoonrightright (), \updownharpoonsleftright (), \upfishtail (), \upharpoonleft (), \upharpoonleftbar (), \upharpoonright (), \upharpoonrightbar (), \upharpoonsleftright (), \upin (), \upint (), \uplus (), \uprightcurvearrow (), \upuparrows (), \upwhitearrow (), \urarc (), \urblacktriangle (), \urcorner (), \urcrop (), \urtriangle ().

\v (), \vBar (), \vBarv (), \vDash (), \vDdash (), \varTheta (), \varVdash (), \varbarwedge (), \varbeta (), \varclubsuit (), \vardiamondsuit (), \vardoublebarwedge (), \varepsilon (), \varheartsuit (), \varhexagon (), \varhexagonblack (), \varhexagonlrbonds (), \varin (), \varisinobar (), \varisins (), \varkappa (), \varlrtriangle (), \varni (), \varniobar (), \varnis (), \varnothing (), \varointclockwise (), \varphi (), \varpi (), \varpropto (), \varrho (), \varrowextender (), \varsigma (), \varspadesuit (), \varstar (), \vartheta (), \vartriangle (), \vartriangleleft (), \vartriangleright (), \varveebar (), \vbraceextender (), \vbrtri (), \vdash (), \vdots (), \vectimes (), \vee (), \veebar (), \veedot (), \veedoublebar (), \veeeq (), \veemidvert (), \veeodot (), \veeonvee (), \veeonwedge (), \vert (|), \viewdata (), \vlongdash (), \vrectangle (), \vrectangleblack (), \vysmlblksquare (), \vysmlwhtsquare (), \vzigzag ().

\watchicon (), \wedge (), \wedgebar (), \wedgedot (), \wedgedoublebar (), \wedgemidvert (), \wedgeodot (), \wedgeonwedge (), \wedgeq (), \whitearrowupfrombar (), \whiteinwhitetriangle (), \whitepointerleft (), \whitepointerright (), \whitesquaretickleft (), \whitesquaretickright (), \whthorzoval (), \whtvertoval (), \wideangledown (), \wideangleup (), \wp (), \wr ().

\xbsol (), \xi (), \xsol (), \yen (), \zeta (), \zpipe (),

IF ANYBODY WILL CHECK WHETHER ALL NAMES CORRESPOND TO RIGHT TEX SYMBOLS I SHALL APPRECIATE IT GREATLY.

Appendix D GNU Free Documentation License

Version 1.2, November 2002

Copyright © 2000,2001,2002 Free Software Foundation, Inc.
51 Franklin St, Fifth Floor, Boston, MA 02110-1301, USA

0. PREAMBLE

   The purpose of this License is to make a manual, textbook, or other functional and useful document *free* in the sense of freedom: to assure everyone the effective freedom to copy and redistribute it, with or without modifying it, either commercially or non-commercially. Secondarily, this License preserves for the author and publisher a way to get credit for their work, while not being considered responsible for modifications made by others.

   This License is a kind of "copyleft", which means that derivative works of the document must themselves be free in the same sense. It complements the GNU General Public License, which is a copyleft license designed for free software.

   We have designed this License in order to use it for manuals for free software, because free software needs free documentation: a free program should come with manuals providing the same freedoms that the software does. But this License is not limited to software manuals; it can be used for any textual work, regardless of subject matter or whether it is published as a printed book. We recommend this License principally for works whose purpose is instruction or reference.

1. APPLICABILITY AND DEFINITIONS

   This License applies to any manual or other work, in any medium, that contains a notice placed by the copyright holder saying it can be distributed under the terms of this License. Such a notice grants a world-wide, royalty-free license, unlimited in duration, to use that work under the conditions stated herein. The "Document", below, refers to any such manual or work. Any member of the public is a licensee, and is addressed as "you". You accept the license if you copy, modify or distribute the work in a way requiring permission under copyright law.

   A "Modified Version" of the Document means any work containing the Document or a portion of it, either copied verbatim, or with modifications and/or translated into another language.

   A "Secondary Section" is a named appendix or a front-matter section of the Document that deals exclusively with the relationship of the publishers or authors of the Document to the Document's overall subject (or to related matters) and contains nothing that could fall directly within that overall subject. (Thus, if the Document is in part a textbook of mathematics, a Secondary Section may not explain any mathematics.) The relationship could be a matter of historical connection with the subject or with related matters, or of legal, commercial, philosophical, ethical or political position regarding them.

   The "Invariant Sections" are certain Secondary Sections whose titles are designated, as being those of Invariant Sections, in the notice that says that the Document is released

under this License. If a section does not fit the above definition of Secondary then it is not allowed to be designated as Invariant. The Document may contain zero Invariant Sections. If the Document does not identify any Invariant Sections then there are none.

The "Cover Texts" are certain short passages of text that are listed, as Front-Cover Texts or Back-Cover Texts, in the notice that says that the Document is released under this License. A Front-Cover Text may be at most 5 words, and a Back-Cover Text may be at most 25 words.

A "Transparent" copy of the Document means a machine-readable copy, represented in a format whose specification is available to the general public, that is suitable for revising the document straightforwardly with generic text editors or (for images composed of pixels) generic paint programs or (for drawings) some widely available drawing editor, and that is suitable for input to text formatters or for automatic translation to a variety of formats suitable for input to text formatters. A copy made in an otherwise Transparent file format whose markup, or absence of markup, has been arranged to thwart or discourage subsequent modification by readers is not Transparent. An image format is not Transparent if used for any substantial amount of text. A copy that is not "Transparent" is called "Opaque".

Examples of suitable formats for Transparent copies include plain ASCII without markup, Texinfo input format, LaTeX input format, SGML or XML using a publicly available DTD, and standard-conforming simple HTML, PostScript or PDF designed for human modification. Examples of transparent image formats include PNG, XCF and JPG. Opaque formats include proprietary formats that can be read and edited only by proprietary word processors, SGML or XML for which the DTD and/or processing tools are not generally available, and the machine-generated HTML, PostScript or PDF produced by some word processors for output purposes only.

The "Title Page" means, for a printed book, the title page itself, plus such following pages as are needed to hold, legibly, the material this License requires to appear in the title page. For works in formats which do not have any title page as such, "Title Page" means the text near the most prominent appearance of the work's title, preceding the beginning of the body of the text.

A section "Entitled XYZ" means a named subunit of the Document whose title either is precisely XYZ or contains XYZ in parentheses following text that translates XYZ in another language. (Here XYZ stands for a specific section name mentioned below, such as "Acknowledgements", "Dedications", "Endorsements", or "History".) To "Preserve the Title" of such a section when you modify the Document means that it remains a section "Entitled XYZ" according to this definition.

The Document may include Warranty Disclaimers next to the notice which states that this License applies to the Document. These Warranty Disclaimers are considered to be included by reference in this License, but only as regards disclaiming warranties: any other implication that these Warranty Disclaimers may have is void and has no effect on the meaning of this License.

2. VERBATIM COPYING

You may copy and distribute the Document in any medium, either commercially or noncommercially, provided that this License, the copyright notices, and the license notice saying this License applies to the Document are reproduced in all copies, and

that you add no other conditions whatsoever to those of this License. You may not use technical measures to obstruct or control the reading or further copying of the copies you make or distribute. However, you may accept compensation in exchange for copies. If you distribute a large enough number of copies you must also follow the conditions in section 3.

You may also lend copies, under the same conditions stated above, and you may publicly display copies.

3. COPYING IN QUANTITY

If you publish printed copies (or copies in media that commonly have printed covers) of the Document, numbering more than 100, and the Document's license notice requires Cover Texts, you must enclose the copies in covers that carry, clearly and legibly, all these Cover Texts: Front-Cover Texts on the front cover, and Back-Cover Texts on the back cover. Both covers must also clearly and legibly identify you as the publisher of these copies. The front cover must present the full title with all words of the title equally prominent and visible. You may add other material on the covers in addition. Copying with changes limited to the covers, as long as they preserve the title of the Document and satisfy these conditions, can be treated as verbatim copying in other respects.

If the required texts for either cover are too voluminous to fit legibly, you should put the first ones listed (as many as fit reasonably) on the actual cover, and continue the rest onto adjacent pages.

If you publish or distribute Opaque copies of the Document numbering more than 100, you must either include a machine-readable Transparent copy along with each Opaque copy, or state in or with each Opaque copy a computer-network location from which the general network-using public has access to download using public-standard network protocols a complete Transparent copy of the Document, free of added material. If you use the latter option, you must take reasonably prudent steps, when you begin distribution of Opaque copies in quantity, to ensure that this Transparent copy will remain thus accessible at the stated location until at least one year after the last time you distribute an Opaque copy (directly or through your agents or retailers) of that edition to the public.

It is requested, but not required, that you contact the authors of the Document well before redistributing any large number of copies, to give them a chance to provide you with an updated version of the Document.

4. MODIFICATIONS

You may copy and distribute a Modified Version of the Document under the conditions of sections 2 and 3 above, provided that you release the Modified Version under precisely this License, with the Modified Version filling the role of the Document, thus licensing distribution and modification of the Modified Version to whoever possesses a copy of it. In addition, you must do these things in the Modified Version:

A. Use in the Title Page (and on the covers, if any) a title distinct from that of the Document, and from those of previous versions (which should, if there were any, be listed in the History section of the Document). You may use the same title as a previous version if the original publisher of that version gives permission.

B. List on the Title Page, as authors, one or more persons or entities responsible for authorship of the modifications in the Modified Version, together with at least five of the principal authors of the Document (all of its principal authors, if it has fewer than five), unless they release you from this requirement.

C. State on the Title page the name of the publisher of the Modified Version, as the publisher.

D. Preserve all the copyright notices of the Document.

E. Add an appropriate copyright notice for your modifications adjacent to the other copyright notices.

F. Include, immediately after the copyright notices, a license notice giving the public permission to use the Modified Version under the terms of this License, in the form shown in the Addendum below.

G. Preserve in that license notice the full lists of Invariant Sections and required Cover Texts given in the Document's license notice.

H. Include an unaltered copy of this License.

I. Preserve the section Entitled "History", Preserve its Title, and add to it an item stating at least the title, year, new authors, and publisher of the Modified Version as given on the Title Page. If there is no section Entitled "History" in the Document, create one stating the title, year, authors, and publisher of the Document as given on its Title Page, then add an item describing the Modified Version as stated in the previous sentence.

J. Preserve the network location, if any, given in the Document for public access to a Transparent copy of the Document, and likewise the network locations given in the Document for previous versions it was based on. These may be placed in the "History" section. You may omit a network location for a work that was published at least four years before the Document itself, or if the original publisher of the version it refers to gives permission.

K. For any section Entitled "Acknowledgements" or "Dedications", Preserve the Title of the section, and preserve in the section all the substance and tone of each of the contributor acknowledgements and/or dedications given therein.

L. Preserve all the Invariant Sections of the Document, unaltered in their text and in their titles. Section numbers or the equivalent are not considered part of the section titles.

M. Delete any section Entitled "Endorsements". Such a section may not be included in the Modified Version.

N. Do not retitle any existing section to be Entitled "Endorsements" or to conflict in title with any Invariant Section.

O. Preserve any Warranty Disclaimers.

If the Modified Version includes new front-matter sections or appendices that qualify as Secondary Sections and contain no material copied from the Document, you may at your option designate some or all of these sections as invariant. To do this, add their titles to the list of Invariant Sections in the Modified Version's license notice. These titles must be distinct from any other section titles.

You may add a section Entitled "Endorsements", provided it contains nothing but endorsements of your Modified Version by various parties—for example, statements of peer review or that the text has been approved by an organization as the authoritative definition of a standard.

You may add a passage of up to five words as a Front-Cover Text, and a passage of up to 25 words as a Back-Cover Text, to the end of the list of Cover Texts in the Modified Version. Only one passage of Front-Cover Text and one of Back-Cover Text may be added by (or through arrangements made by) any one entity. If the Document already includes a cover text for the same cover, previously added by you or by arrangement made by the same entity you are acting on behalf of, you may not add another; but you may replace the old one, on explicit permission from the previous publisher that added the old one.

The author(s) and publisher(s) of the Document do not by this License give permission to use their names for publicity for or to assert or imply endorsement of any Modified Version.

5. COMBINING DOCUMENTS

    You may combine the Document with other documents released under this License, under the terms defined in section 4 above for modified versions, provided that you include in the combination all of the Invariant Sections of all of the original documents, unmodified, and list them all as Invariant Sections of your combined work in its license notice, and that you preserve all their Warranty Disclaimers.

    The combined work need only contain one copy of this License, and multiple identical Invariant Sections may be replaced with a single copy. If there are multiple Invariant Sections with the same name but different contents, make the title of each such section unique by adding at the end of it, in parentheses, the name of the original author or publisher of that section if known, or else a unique number. Make the same adjustment to the section titles in the list of Invariant Sections in the license notice of the combined work.

    In the combination, you must combine any sections Entitled "History" in the various original documents, forming one section Entitled "History"; likewise combine any sections Entitled "Acknowledgements", and any sections Entitled "Dedications". You must delete all sections Entitled "Endorsements."

6. COLLECTIONS OF DOCUMENTS

    You may make a collection consisting of the Document and other documents released under this License, and replace the individual copies of this License in the various documents with a single copy that is included in the collection, provided that you follow the rules of this License for verbatim copying of each of the documents in all other respects.

    You may extract a single document from such a collection, and distribute it individually under this License, provided you insert a copy of this License into the extracted document, and follow this License in all other respects regarding verbatim copying of that document.

7. AGGREGATION WITH INDEPENDENT WORKS

    A compilation of the Document or its derivatives with other separate and independent documents or works, in or on a volume of a storage or distribution medium, is called

an "aggregate" if the copyright resulting from the compilation is not used to limit the legal rights of the compilation's users beyond what the individual works permit. When the Document is included in an aggregate, this License does not apply to the other works in the aggregate which are not themselves derivative works of the Document.

If the Cover Text requirement of section 3 is applicable to these copies of the Document, then if the Document is less than one half of the entire aggregate, the Document's Cover Texts may be placed on covers that bracket the Document within the aggregate, or the electronic equivalent of covers if the Document is in electronic form. Otherwise they must appear on printed covers that bracket the whole aggregate.

8. TRANSLATION

Translation is considered a kind of modification, so you may distribute translations of the Document under the terms of section 4. Replacing Invariant Sections with translations requires special permission from their copyright holders, but you may include translations of some or all Invariant Sections in addition to the original versions of these Invariant Sections. You may include a translation of this License, and all the license notices in the Document, and any Warranty Disclaimers, provided that you also include the original English version of this License and the original versions of those notices and disclaimers. In case of a disagreement between the translation and the original version of this License or a notice or disclaimer, the original version will prevail.

If a section in the Document is Entitled "Acknowledgements", "Dedications", or "History", the requirement (section 4) to Preserve its Title (section 1) will typically require changing the actual title.

9. TERMINATION

You may not copy, modify, sublicense, or distribute the Document except as expressly provided for under this License. Any other attempt to copy, modify, sublicense or distribute the Document is void, and will automatically terminate your rights under this License. However, parties who have received copies, or rights, from you under this License will not have their licenses terminated so long as such parties remain in full compliance.

10. FUTURE REVISIONS OF THIS LICENSE

The Free Software Foundation may publish new, revised versions of the GNU Free Documentation License from time to time. Such new versions will be similar in spirit to the present version, but may differ in detail to address new problems or concerns. See http://www.gnu.org/copyleft/.

Each version of the License is given a distinguishing version number. If the Document specifies that a particular numbered version of this License "or any later version" applies to it, you have the option of following the terms and conditions either of that specified version or of any later version that has been published (not as a draft) by the Free Software Foundation. If the Document does not specify a version number of this License, you may choose any version ever published (not as a draft) by the Free Software Foundation.

ADDENDUM: How to use this License for your documents

To use this License in a document you have written, include a copy of the License in the document and put the following copyright and license notices just after the title page:

```
Copyright (C)  year  your name.
Permission is granted to copy, distribute and/or modify this document
under the terms of the GNU Free Documentation License, Version 1.2
or any later version published by the Free Software Foundation;
with no Invariant Sections, no Front-Cover Texts, and no Back-Cover
Texts.  A copy of the license is included in the section entitled ''GNU
Free Documentation License''.
```

If you have Invariant Sections, Front-Cover Texts and Back-Cover Texts, replace the "with...Texts." line with this:

```
with the Invariant Sections being list their titles, with
the Front-Cover Texts being list, and with the Back-Cover Texts
being list.
```

If you have Invariant Sections without Cover Texts, or some other combination of the three, merge those two alternatives to suit the situation.

If your document contains nontrivial examples of program code, we recommend releasing these examples in parallel under your choice of free software license, such as the GNU General Public License, to permit their use in free software.

Index